

Model:

Serial Number:

Year of manufacture:

Test carried out by

On:

Reference:

*NOTE: The VWART accuracy is in the range +/-2°C*

	HIGH TEMP	LOW TEMP
	VWART °C	VWART °C
DHW		
Keep-warm		
Space heating		
Overall with keep warm		

<b>Pressure test</b>		
No HIU damage		

<b>Dynamic DHW operation</b>	2a	
DHW not exceed 65°C		

<b>Low flow test at BESA flow rate of 0.02l/s</b>	3a	3b
DHW not exceed 65°C		
DHW temperature at set point +/- 3°C		

<b>Low flow test at manufacturer declared flow rate</b>	3c	3d
Declared minimum flow rate (l/sec)		
Not exceed 65°C		
DHW temperature at set point +/- 3°C		

<b>Keep-warm test</b>	4a	4b
Standby heat consumption - average (Watts)		
Standby electricity consumption - average (Watts)		
Total HIU heat loss (DH + electrical input) (Watts)		
Standby flow rate (the average flow rate) (l/hr)		

<b>DHW Response time test</b>	5a	5b
DHW response time (Seconds)		
Peak electrical heat during test (Watts)		
Output		
DHW temperature not exceed 65°C for more than 10 secs		
DHW reaches 45°C with 15 secs		

<b>Scaling risk assessment as defined in 2.26</b>	If any of the factors below occur then the risk of scaling of the DHW PHE in hard water areas increases		
HIU has a TMV or TRV on the DHW			
Test	2a	3a	3c
t32 above 60°C for more than 5 secs			
t12 exceeds 55°C at any point of the test			
Test	4a		4b
t12 exceeds 50°C at any time			




Photo of HIU being tested with the cover off.




Photo of HIU being tested with the cover on.




Photo of Manufacturers label and serial number.

## COMPONENT DATA AND DOCUMENTATION

[illegible]

Schematic diagram and drawing showing the structure and arrangement of the HIU with dimensions and weight		
Technical specification for electronic components including version of software		
Installation guide		
Commissioning guide		
Operation guide with a function description/ description of operations and care instructions as suited to the intended user category		
Declaration of Conformity for CE-marked HIUs		
Full parameter list for electronically controlled HIUs		

HIU Marking	Comment	Info present
Model name and type no.		
Serial no.		

**HIU MANUFACTURERS' DECLARED INFORMATION** (TO BE COMPLETED BY THE MANUFACTURER)

HIU Model	
Part No.	
Software version	
Test Date:	
Test No.	

DIMENSIONAL INFORMATION	
Dimensions with casing (HxDxW) (mm)	
Primary connections top/bottom	
Secondary HTG connections top/bottom	
Secondary BCW/DHW connections top/bottom	
Connection sizes Prim/Sec DHW/Sec HTG (mm)	
Empty weight kg** (Kg)	
Operating weight kg** (Kg)	

ELECTRICAL INFORMATION	
Power supply (230V 1 phase)	230V 1~
Maximum power (Watts)	
Standby power demand (Watts)	

HYDRAULIC INFORMATION	
Maximum primary pressure (Bar g)	
Maximum primary temperature (°C)	
Primary water volume (l)	
Maximum secondary DHW pressure (Bar g)	
Maximum secondary DHW temperature (°C)	
Secondary DHW water volume (l)	
Maximum secondary HTG pressure (Bar g)	
Maximum secondary HTG temperature (°C)	
Primary operating DP range min/max (kPa)	

DECLARED MAXIMUM PERFORMANCE LT TEST CONDITIONS	
DHW	
Maximum DHW production at 70°C (kW)	
Primary flow temperature (°C)	70
Primary return temperature (°C)	
Primary flow (m3/h)	
Primary $\Delta P^*$ (kPa)	
Secondary in/out temperature (°C)	10/55
Secondary $\Delta P$ (bar)	
HTG	
Maximum HTG production (kW)	
Primary flow temperature (°C)	70
Primary return temperature (°C)	
Primary $\Delta P^*$ (bar)	
Secondary in/out temperature (°C)	40/60
Secondary available DP at the output of HIU	

DECLARED MAXIMUM PERFORMANCE LT TEST CONDITIONS	
DHW	
Maximum DHW production at 60°C (kW)	
Primary flow temperature (°C)	60
Primary return temperature (°C)	
Primary flow (m³/h)	
Primary $\Delta P^*$ (kPa)	
Secondary in/out temperature (°C)	10/50
Secondary $\Delta P$ (bar)	
HTG	
Maximum HTG production (kW)	
Primary flow temperature (°C)	60
Primary return temperature (°C)	
Primary $\Delta P^*$ (bar)	
Secondary in/out temperature (°C)	35/45
Secondary available DP at the output of the HIU (kPa)	
HIU P&ID supplied by manufacturer with a legend for the components	

\*DP pressure not to include HM. Designers must add HM pressure drop.

\*\* Including HIU, casing and wall hung bracket

The information included in this page is for the specific model of HIU detailed in this test report. It is additional information voluntarily provided by the manufacturer who is solely accountable for the details submitted.

## MANUFACTURERS' DECLARATION

This is to confirm that the information supplied by  
accurate representation of the product listed on the BESA HIU Register.

relates to the specific HIU tested and is an

Signed



Position

Company

## COMMENTS/HISTORY

**BESA HIU TEST REPORT**  
**BOSCH Greenstar HIU KE****Client: BOSCH**

Project Number: E4616 Report Issue: 2

24 January 2022

Prepared By:



Simon Broxham - Project Engineer

Approved By:



Josh Welburn – Project Engineering Manager



THIS PAGE IS INTENTIONALLY LEFT BLANK



## **DISCLAIMER**

This report is confidential to the client named on the front cover.

This report may be stored, transmitted, or reproduced in full by the named client, however if the report is to be placed in the public domain or used for publicity / promotional purposes please inform a director of Enertek International Ltd.

The report must not be reproduced in part, edited, abridged or any extracts used for any purpose whatsoever without written permission from a director of Enertek International Ltd.

The client remains responsible for any data supplied by the client for use in this report. If this data could affect the test results this will be noted in the report.

Any test results contained in this report apply only to the specific sample(s) tested as described in the report.

This report does not imply or indicate any element of commercial approval, recommendation, or promotion by Enertek International Ltd.

## BESA SUMMARY SHEET

This test summary, downloaded from the BESA website, indicates that the HIU listed below has been tested against the criteria of the BESA HIU Test Regime.



Model: Greenstar HIU KE  
Serial Number: 5570-273-000010-773560062  
Year of manufacture: 2021

Test carried out by S.Broxham Enertek Int On: 12/15/21

Reference: E4616

	HIGH TEMP	LOW TEMP
	VWART °C	VWART °C
DHW	22	20
Keep-warm	38	40
Space heating	45	36
Overall with keep warm	32	32

*NOTE: The VWART accuracy is in the range +/-2°C*

<b>Pressure test</b>		
No HIU damage	Pass	Pass

<b>Dynamic DHW operation</b>	2a	
DHW not exceed 65°C	Pass	Pass

<b>Low flow test at BESA flow rate of 0.02l/s</b>	3a	3b
DHW not exceed 65°C	Pass	Pass
DHW temperature at set point +/- 3°C	n/a	n/a

<b>Low flow test at manufacturer declared flow rate</b>	3c	3d
Declared minimum flow rate (l/sec)	0.03	0.03
Not exceed 65°C	Yes	n/a
DHW temperature at set point +/- 3°C	Yes	n/a

<b>Keep-warm test</b>	4a	4b
Standby heat consumption - average (Watts)	49	57
Standby electricity consumption - average (Watts)	2.41	2.32
Total HIU heat loss (DH + electrical input) (Watts)		
Standby flow rate (the average flow rate) (l/hr)	3.96	6.0

<b>DHW Response time test</b>	5a	5b
DHW response time (Seconds)	13	15
Peak electrical heat during test (Watts)		
Output		
DHW temperature not exceed 65°C for more than 10 secs	Pass	Pass
DHW reaches 45°C with 15 secs	Pass	Pass

<b>Scaling risk assessment as defined in 2.26</b>	If any of the factors below occur then the risk of scaling of the DHW PHE in hard water areas increases		
HIU has a TMV or TRV on the DHW	No		
Test	2a	3a	3c
t32 above 60°C for more than 5 secs	Yes	No	No
t12 exceeds 55°C at any point of the test	No	No	No
Test	4a		4b
t12 exceeds 50°C at any time	No		No

# CONTENTS

<b>1</b>	<b>BRIEF .....</b>	<b>7</b>
<b>2</b>	<b>DEFINITIONS .....</b>	<b>8</b>
<b>3</b>	<b>TEST OBJECT .....</b>	<b>9</b>
3.1	Appliance Details.....	9
3.2	Appliance Design Pressures .....	9
3.3	Appliance Design Temperatures .....	9
<b>4</b>	<b>TEST METHOD.....</b>	<b>10</b>
4.1	Installation of Appliance .....	10
4.2	Test Regime .....	10
4.3	Measurement & Uncertainties.....	10
<b>5</b>	<b>TEST RESULTS .....</b>	<b>15</b>
5.1	Test 0 – Pressure Test .....	15
5.2	Test 1a to 1f – Space Heating 1-4 kW at 70 and 60°C .....	15
5.3	Test 2a – DHW Dynamic Tapping at 70 °C.....	16
5.4	Test 2b – DHW Dynamic Tapping at 60 °C .....	16
5.5	Test 3a & 3c – Low Flow DHW at 70 °C.....	16
5.6	Test 3b & 3d – Low Flow DHW at 60 °C .....	17
5.7	Test 4a – Keep-Warm at 70 °C .....	17
5.8	Test 4b – Keep-Warm at 60 °C .....	17
5.9	Test 5a – DHW Response Time at 70 °C.....	18
5.10	Test 5b – DHW Response Time at 60 °C.....	18
5.11	Overall Scaling Risk Assessment.....	18
5.12	VWART Calculations .....	19
<b>6</b>	<b>CONCLUSIONS .....</b>	<b>20</b>
<b>7</b>	<b>APPENDIX A.....</b>	<b>21</b>
7.1	Key Metric Plots .....	21
7.2	Key Metric and VWART Summary .....	38
<b>8</b>	<b>APPENDIX B .....</b>	<b>41</b>
8.1	Appliance Documentation.....	41
8.2	Appliance Photographs .....	42
8.3	Calibrations and Uncertainties.....	45

## LIST OF FIGURES

Figure 4.1 – EIL’s HIU Test Rig Schematic .....	11
Figure 7.1 - Test 1a – Space Heating 1 kW at 70 °C .....	22
Figure 7.2 - Test 1b – Space Heating 2 kW at 70 °C .....	23
Figure 7.3 - Test 1c – Space Heating 4 kW at 70 °C .....	24
Figure 7.4 - Test 1d – Space Heating 1 kW at 60 °C .....	25
Figure 7.5 - Test 1e – Space Heating 2 kW at 60 °C .....	26
Figure 7.6 - Test 1f – Space Heating 4 kW at 60 °C .....	27
Figure 7.7 - Test 2a – DHW only at 70 °C .....	28
Figure 7.8 - Test 2b – DHW only at 60 °C .....	29
Figure 7.9 - Test 3a – Low Flow DHW at 70 °C .....	30
Figure 7.10 - Test 3b – Low Flow DHW at 60 °C .....	31
Figure 7.11 - Test 3c – Manufacturers Declared Low Flow DHW at 70 °C .....	32
Figure 7.12 - Test 3d – Manufacturers Declared Low Flow DHW at 60 °C .....	33
Figure 7.13 - Test 4a – Keep-Warm at 70 °C .....	34
Figure 7.14 - Test 4b – Keep-Warm at 60 °C .....	35
Figure 7.15 - Test 5a – DHW Response Time at 70 °C .....	36
Figure 7.16 - Test 5b – DHW Response Time at 60 °C .....	37
Figure 8.1 – Photograph of Appliance [Case Fitted] .....	42
Figure 8.2 – Photograph of Appliance [Case Removed] .....	43
Figure 8.3 – Appliance Data Label .....	44

## LIST OF TABLES

Table 2.1 – Definitions and Abbreviations .....	8
Table 3.1 – Appliance Details .....	9
Table 3.2 – Appliance Design Maximum Pressures .....	9
Table 3.3 – Appliance Design Maximum Temperatures .....	9
Table 4.1 – Setup of Tests (Based on BESA Test Regime, Table 1: Test Schedule) .....	12
Table 4.2 – Test Reporting, (Adapted from BESA Test Regime, Table 5) .....	13
Table 5.1 - Test Results for Space Heating Tests 1a to 1f .....	15
Table 5.2 - Overall Scaling Risk Assessment .....	18
Table 5.3 – High Temperature VWARD Calculations .....	19
Table 5.4 – Low Temperature VWARD Calculations .....	19
Table 7.1 - Key Metrics of High Temperature Package .....	39
Table 7.2 - Key Metrics of Low Temperature Package .....	40
Table 8.1 – Documentation Supplied .....	41
Table 8.2 - EIL Equipment Calibration and Uncertainties .....	45

# 1 BRIEF

- 1.1.1 Enertek international Limited (EIL), were contracted to receive, install, and commission a production sample of the Greenstar HIU KE with Heat Meter.
- 1.1.2 To carry out the work involved to evaluate the performance of Domestic Hot Water (DHW) and Space Heating (SH) in accordance with the BESA UK HIU Test regime Technical Specification, Rev-009 October 2018, a publicly available online Test Regime. This is here-on referred to as the Test Regime throughout this document.
- 1.1.3 To provide a report detailing the tests carried out and generated results in accordance with the Test Regime criteria, including calculations for Volume Weighted Average Return Temperatures (VWART).

## 2 DEFINITIONS

2.1.1 The following definitions and abbreviations which have been used within this report can be found in table 2.1 below.

**Table 2.1 – Definitions and Abbreviations**

Symbol	Description	Unit
$P_1$	Power, Primary Side	kW
$P_2$	Power, Space Heating Side	kW
$P_3$	Power, Domestic Hot Water	kW
$t_{11}$	Temperature, Primary Side Supply Connection	°C
$t_{12}$	Temperature, Primary Side Return Connection	°C
$t_{21}$	Temperature, Space Heating Side Return Connection	°C
$t_{22}$	Temperature, Space Heating System Supply Connection	°C
$t_{31}$	Temperature, Cold Water Supply	°C
$t_{32}$	Temperature, Domestic Hot Water Output from HIU	°C
$q_1$	Volume Flow, Primary Side	L/s
$q_2$	Volume Flow, Space Heating Side	L/s
$q_3$	Volume flow, Domestic Hot Water	L/s
$\Delta p_1$	Primary Pressure drop across entire HIU Unit	kPa
$\Delta p_2$	Pressure Drop, Space Heating System across HIU	kPa
$\Delta p_3$	Pressure Drop, Domestic Hot Water across HIU	kPa
$VWART_{DHW}$	DHW Volume Weighted Return Temperature	°C
$VWART_{SH}$	Space Heating Volume Weighted Return Temperature	°C
$VWART_{KWH}$	Keep Warm Volume Weighted Return Temperature	°C
$VWART_{HEAT}$	Annual Volume Weighted Return Temperature for Heating Period	°C
$VWART_{NONHEAT}$	Annual Volume Weighted Return Temperature for Non-Heating	°C
$VWART_{HIU}$	Total Annual Volume Weighted Return Temperature	°C
DHW	Domestic Hot Water	—
HIU	Heat Interface Unit	—
SH	Space Heating	—
TMV	Thermostatic Mixing Valve	—
EIL	Enertek International Limited	—

### 3 TEST OBJECT

#### 3.1 Appliance Details

- 3.1.1 Details of the Greenstar HIU KE appliance are given in Table 3.1. Photograph of the installed appliance is given in Figure 8.2.

**Table 3.1 – Appliance Details**

Item	Description
Manufacturer	BOSCH Worcester
Model	Greenstar HIU KE
Serial Number	5570-273-000010-7735600662
Year of Manufacture	2021
DHW Priority	Yes

#### 3.2 Appliance Design Maximum Pressures

- 3.2.1 The maximum design pressures of the Greenstar HIU KE appliance for the primary side and the secondary side for both Space Heating and DHW are given in Table 3.2.

**Table 3.2 – Appliance Design Maximum Pressures**

Item	Value	Unit
Primary Side	10	Bar
Secondary Side Space Heating	2.5	Bar
Secondary Side DHW	10	Bar

#### 3.3 Appliance Design Maximum Temperatures

- 3.3.1 The maximum design temperatures of the Greenstar HIU KE appliance for the primary side and the secondary side for both Space Heating and DHW are given in Table 3.3.

**Table 3.3 – Appliance Design Maximum Temperatures**

Item	Value	Unit
Primary Side	90	°C
Secondary Side Space Heating	70	°C
Secondary Side DHW	60	°C

## 4 TEST METHOD

### 4.1 Installation of Appliance

- 4.1.1 The appliance was installed and commissioned (as received) and as defined in the product literature provided. Testing was carried out without further adjustment other than disabling the internal space heating pump and adjusting the setting of the SH and DHW set points through the user interface on the HIU controller to suit the conditions of the HIU test rig. The HIU rig schematic is given in Figure 4.1.

### 4.2 Test Regime

- 4.2.1 The testing described in this report was carried out in accordance with the BESA Test Regime. The Test Regime outlines a series of static and dynamic tests to determine the performance of a HIU's DHW and SH functions. The Regime outlines the test method including the reporting of the results, the performance requirements and the VWART calculations.
- 4.2.2 The setup of the BESA tests is reproduced in Table 4.1. The basis of reporting the performance of the HIU from the BESA Test Regime is reproduced in Table 4.2.
- 4.2.3 The Test Regime specifies the testing of two different test temperature packages. The first is the high temperature package, with a district primary supply of 70 °C and the second is the 'low temperature' package, with a district primary supply temperature of 60 °C.
- 4.2.4 As the Greenstar HIU KE is suitable for both high and low temperature operation, both test packages were carried out and results recorded within this report.

### 4.3 Measurement & Uncertainties

- 4.3.1 All measurements and uncertainties adhere to the requirements stipulated in the BESA Test Regime. All measurements were sampled at a rate of 1 Hz for all tests.
- 4.3.2 The BESA uncertainties of measurement requirements are as follows: Differential Pressure,  $\pm 1$  kPa; Temperature,  $\pm 0.1$  °C; Volume Flow,  $\pm 1.5$  %. Note: the time constant for the temperature sensors is less than 1.5 s.
- 4.3.3 EIL's reported uncertainty is based on a standard uncertainty by a coverage factor  $K=2$ , providing a level of confidence of approximately 95%. The uncertainty evaluation has been carried out in accordance with UKAS requirements. The EIL equipment list and uncertainties are given in Table 8.2, Appendix B.






Figure 4.1 – EIL's HIU Test Rig Schematic

**Table 4.1 – Setup of Tests (Based on BESA Test Regime, Table 1: Test Schedule)**

		<b>District Circuit</b>			<b>Domestic Hot Water</b>			<b>Space Heating</b>		
		Static Pressure	Differential Pressure	Flow Temperature	Temperature Set Point	Flow Rate	Heat Load	Flow Temperature	Return Temperature	Heat Load
<i>Symbol</i>		$[p_1]$	$[\Delta p_1]$	$[t_{11}]$	$[t_{32}]$	$[q_3]$	$[P_3]$	$[t_{22}]$	$[t_{21}]$	$[P_2]$
<i>Units</i>		$[kPa]$	$[kPa]$	$[^{\circ}C]$	$[^{\circ}C]$	$[Ls^{-1}]$	$[kW]$	$[^{\circ}C]$	$[^{\circ}C]$	$[kW]$
<b>Static Tests</b>										
0a	District Pressure Test	1.43 X Claimed Value	-	-	-	-	-	-	-	-
1a	1kW Space Heating	3.0	0.5	70	-	-	-	60	40	1
1b	2kW Space Heating	3.0	0.5	70	-	-	-	60	40	2
1c	4kW Space Heating	3.0	0.5	70	-	-	-	60	40	4
1d	1kW Space Heating	3.0	0.5	60	-	-	-	45	35	1
1e	2kW Space Heating	3.0	0.5	60	-	-	-	45	35	2
1f	4kW Space Heating	3.0	0.5	60	-	-	-	45	35	4
<b>Dynamic Tests</b>										
2a	Dynamic Tapping	3.0	0.5	70	55	See Test Profile	See Test Profile	-	-	-
2b	Dynamic Tapping	3.0	0.5	60	50			-	-	-
3a	Low Flow	3.0	0.5	70	55	0.02	Record Value.	-	-	-
3b	Low Flow	3.0	0.5	60	50	0.02	Record Value.	-	-	-
4a	Keep-Warm	3.0	0.5	70	55	0.00	0	-	-	-
4b	Keep-Warm	3.0	0.5	60	50	0.00	0	-	-	-
5a	DHW Response	3.0	0.5	70	55	0.13	Record Value.	-	-	-
5b	DHW Response	3.0	0.5	60	50	0.13	Record Value.	-	-	-

**Table 4.2 – Test Reporting, (Adapted from BESA Test Regime, Table 5)**

Test Designation		Reporting
0	District Pressure Test	Pass/Fail as to whether HIU manages pressure test without leaks or damage.
1a	Space Heating 1 kW, 60/40 °C secondary.	$t_{11}$ – Primary flow temperature. $t_{12}$ – Primary return temperature.
1b	Space Heating 2 kW, 60/40 °C Secondary.	Plot of key metrics over duration of test.
1c	Space Heating 4 kW, 60/40 °C Secondary.	<b>Note:</b> Outputs used as input data to ‘High Temperature’ Space Heating Volume Weighted Average Return Temperature calculation.
1d	Space Heating 1 kW, 45/35 °C Secondary.	$t_{11}$ – Primary flow temperature. $t_{12}$ – Primary return temperature.
1e	Space Heating 2 kW, 45/35 °C Secondary.	Plot of key metrics over duration of test.
1f	Space Heating 4 kW, 45/35 °C Secondary.	<b>Note:</b> Outputs used as input data to ‘Low Temperature’ Space Heating Volume Weighted Average Return Temperature calculation.
2a	DHW Only, DH 70 °C Flow, 55 °C DHW.	Pass/Fail on DHW (at $t_{32}$ ) exceeding 65.0 °C (to 1 decimal point) for more than 10 consecutive seconds. State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Assessment of scaling risk as per the criteria detailed in 2.26. <b>Note:</b> Outputs used as input data to ‘High Temperature’ Space Heating Volume Weighted Average Return Temperature calculation. Plot $t_{32}$ , $t_{31}$ , $q_3$ , $t_{12}$ , $q_1$
2b	DHW Only, DH 60 °C Flow, 50 °C DHW.	State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. <b>Note:</b> Outputs used as input data to ‘Low Temperature’ Domestic Hot Water Volume Weighted Average Return Temperature calculation. Plot $q_1$ , $q_3$ , $dp_1$ , $dp_3$
3a	Low Flow DHW, DH 70 °C Flow, 55 °C DHW.	Pass/Fail on DHW (at $t_{32}$ ) exceeding 65.0 °C (1 decimal place) for more than 10 consecutive seconds. Comment on ability to deliver DHW at low flow based on DHW temperature reaching at least 45.0 °C (1 decimal place) at the end of the 180 second period of low flow DHW. Comment on the ability to deliver stable DHW flow temperature (at $t_{32}$ ), defined as ability to maintain 55.0 +/- 3.0 °C (1 decimal place) during the last 60 seconds of the test. Maximum temperature achieved and +/- °C variance around 55.0 °C (1 decimal place) to be stated. Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow. Assessment of scaling risk as per criteria detailed in 2.26.
3b	Low Flow DHW, DH 60 °C Flow, 50 °C DHW.	Comment on the ability to deliver DHW at low flow rate based on DHW temperature reaching at least 45 °C (1 decimal place) at the end of the 180 second period of low flow DHW. Comment on the ability to deliver stable DHW flow temperature (at $t_{32}$ ), defined as ability to maintain 50.0 +/- 3 °C (1 decimal place) to be stated. Maximum temperature achieved and +/- °C variance around 50.0 °C (1 decimal place) to be stated. Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.

Test Designation		Reporting
4a	Keep-Warm, DH 70 °C Flow, 55 °C DHW.	<p>Assessment of whether valid keep-warm operation, based on 5a response time criteria: Pass/Fail.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Assessment of scaling risk based on duration of temperatures in excess of 55.0 °C (1 decimal place).</p> <p>State average heat load for the duration of the test.</p> <p>State the average primary flow rate for the duration of the test.</p> <p>Note: Outputs used as input data to 'High Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p> <p>Plot of key metrics over duration of test.</p>
4b	Keep-Warm, DH 60 °C Flow, 50 °C DHW.	<p>Assessment of whether valid keep-warm operation, based on 5b response time criteria: Pass/Fail.</p> <p>Observation on the operation of the HIU during keep-warm. Comment on HIU keep-warm controls options.</p> <p>Assessment of scaling risk based on extent and duration of temperatures in excess of 55.0 °C (1 decimal place).</p> <p>State average heat load for the duration of the test.</p> <p>State the average primary flowrate for the duration of the test.</p> <p><b>Note:</b> Outputs used as input data to 'Low Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p> <p>Plot of key metrics over duration of test.</p>
5a	DHW Response Time, DH 70 °C Flow, 55 °C DHW.	<p>Pass/Fail on DHW (at <math>t_{32}</math>) exceeding 65.0 °C (1 decimal place) for more than 10 consecutive seconds.</p> <p>State time to achieve 45.0 °C (1 decimal place) and not subsequently drop below 42.0 °C (1 decimal place).</p> <p>Plot <math>t_{32}</math>, <math>t_{31}</math>, <math>t_{12}</math>, <math>q_1</math> over duration of test.</p>
5b	DHW Response Time, DH 60 °C Flow, 50 °C DHW.	<p>State time to achieve a DHW temperature 45.0 °C (1 decimal place) and not subsequently drop below 42.0 °C (1 decimal place).</p> <p>Comment on stability of DHW temperature.</p> <p>Plot <math>t_{32}</math>, <math>t_{31}</math>, <math>t_{12}</math>, <math>q_1</math> over duration of test.</p>

## 5 TEST RESULTS

### 5.1 Test 0 – Pressure Test

- 5.1.1 The appliance has passed the requirements of the static pressure test, Test 0 of the BESA Test Regime as:
- 5.1.2 There was No damage observed during the static pressure test, with the primary flow pressurised to 14.3 bar (1.43 times the rated value), and
- 5.1.3 There were No leaks observed during the static pressure test, with the primary flow pressurised to 14.3 bar (1.43 times the rated value).

### 5.2 Test 1a to 1f – Space Heating 1-4 kW at 70 and 60°C

- 5.2.1 The plot of the key metrics of Tests 1a-1f for the space heating 1 - 4 kW at both 70 and 60 °C are displayed in Figure 7.1 to Figure 7.6 respectively. See Table 5.1 for summarised test results including the average primary return temperature,  $t_{12}$

**Table 5.1 - Test Results for Space Heating Tests 1a to 1f**

Test No & Description	Primary					Secondary				
	Flow Temperature	Return Temperature	Flow Rate	Differential Pressure	Heat Load	Return Temperature	Flow Temperature	Flow Rate	Differential Pressure	Heat Load
	$[t_{11}]$	$[t_{12}]$	$[q_1]$	$[\Delta p_1]$	$[P_1]$	$[t_{21}]$	$[t_{22}]$	$[q_2]$	$[\Delta p_2]$	$[P_2]$
	[°C]	[°C]	[Ls <sup>-1</sup> ]	[kPa]	[W]	[°C]	[°C]	[Ls <sup>-1</sup> ]	[kPa]	[W]
1a - 1 kW Space Heating (DH 70 °C flow)	69.5	42.2	0.012	51.7	1290	39.7	60.4	0.012	2.4	1039
1b - 2 kW Space Heating (DH 70 °C flow)	69.5	43.9	0.023	49.2	2277	40.0	59.9	0.024	1.9	1963
1c - 4 kW Space Heating (DH 70 °C flow)	69.7	45.7	0.048	50.9	4604	39.8	60.3	0.048	0.2	4117
1d - Space Heating 1 kW (DH 60 °C flow)	59.8	34.7	0.012	46.4	1224	34.6	45.1	0.023	2.0	1012
1e - Space Heating 2 kW (DH 60 °C flow)	59.6	35.4	0.024	54.9	2411	34.6	45.2	0.047	0.5	2095
1f - Space Heating 4 kW (DH 60 °C flow)	59.8	35.9	0.045	53.2	4483	34.6	45.4	0.094	4.9	4341

### **5.3 Test 2a – DHW Dynamic Tapping at 70 °C**

- 5.3.1 The appliance has passed the requirements of the DHW only at 70 °C, Test 2a of the BESA Test Regime as:
- 5.3.2 The domestic hot water output temperature,  $t_{32}$  did not exceed 65 °C for more than 10 seconds.
- 5.3.3 The maximum and minimum temperatures of  $t_{32}$  were 60.8 °C and 38.0 °C respectively.
- 5.3.4 The plot of the key metrics of the duration of Test 2a is displayed in Figure 7.7, Appendix A.

### **5.4 Test 2b – DHW Dynamic Tapping at 60 °C**

- 5.4.1 The maximum and minimum temperatures of  $t_{32}$  were 52.7 °C and 36.0 °C respectively.
- 5.4.2 The plot of the key metrics of the duration of Test 2b is displayed in Figure 7.8, Appendix A.

### **5.5 Test 3a & 3c – Low Flow DHW at 70 °C**

- 5.5.1 The appliance has passed the requirements of the Low Flow at 70 °C, Test 3a of the BESA Test Regime as:
- 5.5.2 The domestic hot water output temperature,  $t_{32}$  did not exceed 65 °C for more than 10 seconds, and,
- 5.5.3 The appliance did not maintain the DHW output temperature,  $t_{32}$  at  $55 \pm 3$  °C during the last 60 seconds of the test.
- 5.5.4 The maximum and minimum temperatures of  $t_{32}$  were 59.9 °C and 14.5 °C respectively.
- 5.5.5 As the appliance did not maintain a stable flow temperature at 1.2 l/min, the appliance was retested as test 3c at the manufacturers declared low flow rate which was 1.8 l/min.
- 5.5.6 At the manufacturers low flow rate of 1.8 l/min the appliance did maintain the DHW output temperature  $t_{32}$  at  $55 \pm 3$  °C during the last 60 seconds of the test.
- 5.5.7 The plot of the key metrics of the duration of Test 3a is displayed in Figure 7.9, Appendix A.
- 5.5.8 The plot of the key metrics of the duration of Test 3c is displayed in Figure 7.11, Appendix A.

## **5.6 Test 3b & 3d – Low Flow DHW at 60 °C**

- 5.6.1 The appliance did not maintain stable flow temperatures during Low Flow at 60 °C, Test 3b of the BESA Test Regime.
- 5.6.2 The appliance was retested as test 3d at the manufacturers declared low flow rate which was 1.8 l/min, the appliance was then seen to maintain DHW output temperature  $t_{32}$  at 50 °C during the last 60 seconds of the test.
- 5.6.3 The plot of the key metrics of the duration of Test 3b is displayed in Figure 7.10, Appendix A. Test 3d is displayed in Figure 7.12, Appendix A.

## **5.7 Test 4a – Keep-Warm at 70 °C**

- 5.7.1 The appliance has passed the requirements of the Keep-Warm at 70 °C, Test 4a of the BESA Test Regime as:
- 5.7.2 This is a valid keep warm operation based on 5a response time criteria, see 5.9.3.
- 5.7.3 The appliance is performing keep-warm cycling as the primary flow temperature,  $t_{11}$  varies by more than  $\pm 3$  °C during the final 3 hours of the test. Please see BESA HIU Standard technical note TN-018 Version 1 for a more detailed definition of cyclical data.
- 5.7.4 The average heat load on the primary side  $P_1$  is 49 W.
- 5.7.5 The average electrical consumption was 2.41 W.
- 5.7.6 The average primary flow  $q_1$  over the 8 hours test was 3.96 l/hr.
- 5.7.7 The keep-warm control was set to on.
- 5.7.8 The plot of the key metrics of the duration of Test 4a is displayed in Figure 7.13, Appendix A.

## **5.8 Test 4b – Keep-Warm at 60 °C**

- 5.8.1 The appliance has passed the requirements of the Keep-Warm at 60 °C, Test 4b of the BESA Test Regime as:
- 5.8.2 This is a valid keep warm operation based on 5b response time criteria, see 5.10.1.
- 5.8.3 The appliance is performing keep-warm cycling as the primary flow temperature,  $t_{11}$  varies by more than  $\pm 3$  °C during the final 3 hours of the test. Please see BESA HIU Standard technical note TN-018 Version 1 for a more detailed definition of cyclical data.
- 5.8.4 The average heat load on the primary side  $P_1$  is 57 W.
- 5.8.5 The average primary flow  $q_1$  over the 8 hours test was 6.0 l/hr.
- 5.8.6 The average electrical consumption was 2.32 W.
- 5.8.7 The keep-warm control was set to on.

5.8.8 The plot of the key metrics of the duration of Test 4b is displayed in Figure 7.14, Appendix A.

## 5.9 Test 5a – DHW Response Time at 70 °C

5.9.1 The appliance has passed the requirements of DHW Response Time at 70 °C, Test 5a of the BESA Test Regime as:

5.9.2 The domestic hot water output temperature,  $t_{32}$  did not exceed 65 °C for more than 10 seconds.

5.9.3 The DHW response time for  $t_{32}$  to reach 45 °C (and not subsequently drop below 42 °C) was 13 seconds; therefore this is a valid keep warm.

5.9.4 The plot of the key metrics of the duration of Test 5a is displayed in Figure 7.15, Appendix A.

## 5.10 Test 5b – DHW Response Time at 60 °C

5.10.1 The DHW response time for  $t_{32}$  to reach 45 °C (and not subsequently drop below 42 °C) was 13 seconds; therefore this is a valid keep warm.

5.10.2 The plot of the key metrics of the duration of Test 5b is displayed in Figure 7.16, Appendix A.

## 5.11 Overall Scaling Risk Assessment

5.11.1 If any of the below factors occur, then the risk of scaling of the DHW plate in hard water areas increases.

**Table 5.2 - Overall Scaling Risk Assessment**

<i>HIU has a TMV or TRV on the output of the DHW plate heat exchanger.</i>	No	
<b>Test Designation</b>	<b>2a</b>	<b>3a</b>
<i><math>t_{32}</math> above 60°C for more than 5 seconds</i>	Yes	No
<i><math>t_{12}</math> exceeds 55°C at any point of the test</i>	No	No
<b>Test Designation</b>	<b>4a</b>	<b>4b</b>
<i><math>t_{12}</math> exceeds 50°C at any time</i>	No	No



## 5.12 VWART Calculations

- 5.12.1 The Volume Weighted Average Return Temperatures (VWART) have been calculated as stipulated in the BESA UK HIU Test Regime document. The calculated VWART values for both the high temperature and low temperature tests described in this report are given below in Table 5.3 and Table 5.4 respectively.

**Table 5.3 – High Temperature VWART Calculations**

Description	Symbol	Value	Unit
Annual Heating Period Percentage	SH <sub>PROP</sub>	7.1	%
Annual Non-Heating Period Percentage	NSH <sub>PROP</sub>	92.9	%
Space Heating Volume Weighted Return Temperature	VWART <sub>SH</sub>	45	°C
DHW Volume Weighted Return Temperature	VWART <sub>DHW</sub>	22	°C
Keep Warm Volume Weighed Return Temperature	VWART <sub>KWM</sub>	38	°C
Annual Volume Weighted Return Temperature for Heating Period	VWART <sub>HEAT</sub>	44	°C
Annual Volume Weighted Return Temperature for Non-Heating	VWART <sub>NONHEAT</sub>	31	°C
Total Annual Volume Weighted Return Temperature	VWART <sub>OVERALL</sub>	32	°C

**Table 5.4 – Low Temperature VWART Calculations**

Description	Symbol	Value	Unit
Annual Heating Period Percentage	SH <sub>PROP</sub>	6.9	%
Annual Non-Heating Period Percentage	NSH <sub>PROP</sub>	93.1	%
Space Heating Volume Weighted Return Temperature	VWART <sub>SH</sub>	36	°C
DHW Volume Weighted Return Temperature	VWART <sub>DHW</sub>	20	°C
Keep Warm Volume Weighed Return Temperature	VWART <sub>KWM</sub>	40	°C
Annual Volume Weighted Return Temperature for Heating Period	VWART <sub>HEAT</sub>	35	°C
Annual Volume Weighted Return Temperature for Non-Heating	VWART <sub>NONHEAT</sub>	32	°C
Total Annual Volume Weighted Return Temperature	VWART <sub>OVERALL</sub>	32	°C

## 6 CONCLUSIONS

6.1.1 The appliance has passed the performance requirements of the BESA HIU Test Regime.

## **7 APPENDIX A**

### **7.1 Key Metric Plots**

- 7.1.1 The graphical plots of the key metrics of the tests described in this report are given in this section.

GRAPHICAL PLOTS START ON NEXT PAGE




Figure 7.1 - Test 1a – Space Heating 1 kW at 70 °C




Figure 7.2 - Test 1b – Space Heating 2 kW at 70 °C




Figure 7.3 - Test 1c – Space Heating 4 kW at 70 °C




Figure 7.4 - Test 1d – Space Heating 1 kW at 60 °C




Figure 7.5 - Test 1e – Space Heating 2 kW at 60 °C






Figure 7.6 - Test 1f – Space Heating 4 kW at 60 °C




Figure 7.7 - Test 2a – DHW only at 70 °C




Figure 7.8 - Test 2b – DHW only at 60 °C




Figure 7.9 - Test 3a – Low Flow DHW at 70 °C




Figure 7.10 - Test 3b – Low Flow DHW at 60 °C




Figure 7.11 - Test 3c – Manufacturers Declared Low Flow DHW at 70 °C




Figure 7.12 - Test 3d – Manufacturers Declared Low Flow DHW at 60 °C




Figure 7.13 - Test 4a – Keep-Warm at 70 °C






Figure 7.14 - Test 4b – Keep-Warm at 60 °C




Figure 7.15 - Test 5a – DHW Response Time at 70 °C




Figure 7.16 - Test 5b – DHW Response Time at 60 °C

## **7.2 Key Metric and VWARD Summary**

- 7.2.1 The summary tables of the key metrics and VWARDS of the tests described in this report are given in this section.

SUMMARY TABLES START ON NEXT PAGE



#### VWART Calculation with Keep Warm

Test carried out by Enertek International for High Temperature BESA Tests

Manufacturer: BOSCH

Model: Greenstar KE

Serial number: 5570-273-000010-7735600662

Calculation performed by S.Broxham of Enertek on: 19/12/2021

Primary Flow Temperature: 70°C

DHW Setpoint: 55°C

Space Heating Temperature: 60/40°C

	VWART (°C)	Volume (m3)
DHW	22	26.5
Standby	38	31.8
Space Heating	45	60.1

	VWART with keep warm active	
Period	VWART (°C)	% Time
No Heating	31	93%
Heating	44	7%
Overall	32	

Test Results									
		Power (p1)	Primary flow	VWART	Energy Used	Annual Operation	Volume	Events	Average duration
		[W]	[m³/hr]	[°C]	[kWh]	[Hours]	[m³]	[Per Year]	[Seconds]
1kW Space Heating	1a	1290	0.044	42	112	87.2	3.85	-	-
2kW Space Heating	1b	2277	0.081	44	913	401.0	32.62	-	-
4kW Space Heating	1c	4604	0.172	46	632	137.2	23.64	-	-
DHW Low Flow Rate	2a	10942	0.190	22	696	66.6	12.69	-	-
DHW Medium Flow Rate	2a	18463	0.342	22	301	16.1	5.49	-	-
DHW High Flow Rate	2a	24472	0.456	23	440	18.1	8.28	-	-
DHW Post Low Flow Rate	2a	-	0.000	18	-	-	0.00	10000	30
DHW Post Medium Flow Rate	2a	-	0.000	0	-	-	0.00	660	70
DHW Post High Flow Rate	2a	-	0.000	22	-	-	0.00	300	145
DHW Keep Warm Standby	4a	-	0.004	38	396	8033.7	31.77	-	-

Table 7.1 - Key Metrics of High Temperature Package



#### VWART Calculation with Keep Warm

Test carried out by Enertek International for Low Temperature BESA Tests

Manufacturer: Bosch

Model: Greenstar KE

Serial number: 5570-273-000010-7735600662

Calculation performed by S.Broxham of Enertek on: 19/12/2021

Primary Flow Temperature: 60°C

DHW Setpoint: 50°C

Space Heating Temperature: 45/35°C

	VWART (°C)	Volume (m3)
DHW	20	30.8
Standby	40	48.6
Space Heating	36	57.4

	VWART with keep warm active	
Period	VWART (°C)	% Time
No Heating	32	93%
Heating	35	7%
Overall	32	

Test Results									
		Power (p1) [W]	Primary flow [m³/hr]	VWART [°C]	Energy Used [kWh]	Annual Operation [Hours]	Volume [m³]	Events [Per Year]	Average duration [Seconds]
1kW Space Heating	1d	1224	0.044	35	119	96.9	4.24	-	-
2kW Space Heating	1e	2411	0.086	35	906	375.6	32.23	-	-
4kW Space Heating	1f	4483	0.161	36	584	130.2	20.97	-	-
DHW Low Flow Rate	2b	9649	0.193	19	695	75.6	14.60	-	-
DHW Medium Flow Rate	2b	16186	0.352	20	298	18.3	6.47	-	-
DHW High Flow Rate	2b	20970	0.459	21	442	21.2	9.71	-	-
DHW Post Low Flow Rate	2b	-	0.000	0	-	-	0.00	10000	30
DHW Post Medium Flow Rate	2b	-	0.000	0	-	-	0.00	660	70
DHW Post High Flow Rate	2b	-	0.000	0	-	-	0.00	300	145
DHW Keep Warm Standby	4b	-	0.006	40	460	8042.3	48.62	-	-

Table 7.2 - Key Metrics of Low Temperature Package

## 8 APPENDIX B

### 8.1 Appliance Documentation

8.1.1 The details of the appliance documentation are given in Table 8.1 below.

**Table 8.1 – Documentation Supplied**

	<b>Component:</b>	<b>Document Submitted (Y/N):</b>	<b>Manufacturer and Type:</b>
1	Space Heating Heat Exchanger	Y	SWEP, Copper brazed
2	Domestic Hot Water Heat Exchanger	Y	SWEP, Copper brazed
3	Controller for Space Heating	Y	Braga, Control board
4	Control Valve and Actuator for Space Heating	Y	ESBE Actuator
5	Space Heating Strainer	Y	N/A
6	Controller for Domestic Hot Water	Y	Braga, Control board
7	Control Valve and Actuator for Domestic Hot Water	Y	ESBE Actuator
8	Temperature Sensors	Y	Exa-thermometrics
9	Domestic Hot Water Isolating Valve	Y	Altecnic
10	Primary Side Strainer	Y	Italfim SPA
11	Drain Valves	Y	Orkli
12	Vent Valves	Y	Novasfer
13	Circulation Pump set with AAV & PRV	Y	Grundfos
14	Heat Meter	Y	Sontex 749 Mbus
15	Domestic Hot Water Flow Sensor	Y	Saginomiya
16	Pipes	Y	Bosch, Stainless steel
17	Connections	Y	Altecnic
18	Joints	Y	Altecnic
19	Gaskets	Y	Altecnic
20	Expansion Vessel	Y	Zilmet
21	Insulation	Y	Synprodo
22	Pressure Sensors	Y	Wika pressure gauge
A1	'O' Ring	Y	Altecnic
A2	Commissioning Guide	Y	Installation manual
A3	Operation Guides with a Function Description / Description of Operation and Care Instructions as Suited to the Intended User Category.	Y	Owner's manual
A4	Declaration of Conformity for CE-Marked HIUs.	Y	
A5	Full Parameter List for Electrically Controlled HIUs.	Y	Installation manual
A6	Maximum Primary Static Operating Differential Pressure.	Y	Installation manual
A7	Deactivation Procedure of the Internal SH Pump.	Y	Installation manual
	Model Name and Type Number	Y	Greenstar HIU KE with heat meter.
	Software Version / Date of Issue	Y	NF51.05; Power 230V / 50Hz - January 2022
	Serial Number	Y	5570-273-000010-7735600662

## 8.2 Appliance Photographs



Figure 8.1 – Photograph of Appliance [Case Fitted]








Figure 8.2 – Photograph of Appliance [Case Removed]



Greenstar HIU KE with heat meter  
Serial Number 5570-273-000010-7735600662

Electrical supply ~ 230V/50Hz/IPH	42 W
Maximum electrical power	
Ingress protection IPX4D	
Maximum operating pressure (static)	
Primary Circuit	10 bar
Maximum operating pressure (static)	
Secondary Circuit CH	2.5 bar
Maximum operating pressure secondary	
DHW circuit	10 bar
Maximum differential pressure (dynamic)	
Primary circuit	4 bar
Controlled differential pressure	0.3 bar
Maximum operating temperature	
Primary circuit	90 Deg C
Central heating output (min/max)	1/15 kW
Maximum DHW output at 35K rise	51.3 kW
Maximum DHW flow rate	21 l/min



Bosch Thermotechnology Ltd.  
Worcester WR4 9SW / United Kingdom

Figure 8.3 – Appliance Data Label



### 8.3 Calibrations and Uncertainties

8.3.1 A list of equipment, their calibrations and uncertainties are given in table 8.8 below.

**Table 8.2 - EIL Equipment Calibration and Uncertainties**

Equipment Name	ID Number	Calibration Certificate	Measurement Uncertainty $K=2$ $\frac{U}{\sqrt{20}}$	Units	Calibration Date	Calibration Due
Flow Meter [Primary Flow Rate]	FM 601	K48376FW1S2	±0.0004	l/s	07/07/2021	07/2022
Flow Meter [DHW Flow Rate]	FM 602	K48378FW	±0.00305	l/s	07/07/2021	07/2022
Flow Meter [SH Flow Rate]	FM 603	K48377FW	±0.04871	l/s	06/07/2021	07/2022
Flow Meter [DHW Flow Rate]	FM 605	K48375FW	±0.00576	l/s	05/07/2021	07/2022
Pressure Transducer [Primary Supply]	PT 086	K48379P	±6.91	kPa	05/07/2021	07/2022
Pressure Transducer [Primary Return]	PT 085	K48384P	±8.54	kPa	05/07/2021	07/2022
Pressure Transducer [DHW Output Pressure]	PT 083	K48380P	±21.27	kPa	05/07/2021	07/2022
Pressure Transducer [DHW Cold Water Supply]	PT 084	K48383P2	±9.21	kPa	20/07/2021	07/2022
Pressure Transducer [SH Flow]	PT 087	K48382P	±7.10	kPa	05/07/2021	07/2022
Pressure Transducer [SH Return]	PT 088	K48381P	±15.24	kPa	05/07/2021	07/2022
PRT Probe [Primary Supply Temp]	PRT 4709	443851	±0.6	°C	10/07/2021	07/2022
PRT Probe [Primary Return Temp]	PRT 4708	443851	±0.6	°C	10/07/2021	07/2022
PRT Probe [DHW Output Temp]	PRT 4711	443852	±0.6	°C	10/07/2021	07/2022
PRT Probe [Cold Water Supply Temp]	PRT 4710	443852	±1.91	°C	10/07/2021	07/2022
PRT Probe [SH Supply Temp]	PRT 4707	443851	±0.57	°C	10/07/2021	07/2022
PRT Probe [SH Return Temp]	PRT 4706	443851	±1.06	°C	10/07/2021	07/2022

Equipment Name	ID Number	Calibration Certificate	Measurement Uncertainty $K=2 \frac{U}{\sqrt{20}}$	Units	Calibration Date	Calibration Due
Pressure Transducer [Static Pressure Test]	PT 090	U100553-19	±50	kPa	21/11/2019	10/2022
Power Meter [Electrical Consumption]	PM1022	U103585-20	±1.03	W	28/07/2021	08/2022
Software	VERSION – LabVIEW, Version 5, Service pack 1					

Report Issue No	Reason for Report Update
1	Original Issue 31/01/2022
2	Photo of internal HIU updated. 02/03/2022

THIS PAGE IS INTENTIONALLY LEFT BLANK

THIS PAGE IS INTENTIONALLY LEFT BLANK



1 Malmo Road  
Sutton Fields  
Kingston upon Hull, HU7 0YF

+44 (0) 1482 877500  
[enertekinternational.com](http://enertekinternational.com)  
Registered in England No. 2262638

