

Model:

Serial Number:

Year of manufacture:

Test carried out by

On:

Reference:

*NOTE: The VWART accuracy is in the range +/-2°C*

|                        | HIGH TEMP | LOW TEMP |
|------------------------|-----------|----------|
|                        | VWART °C  | VWART °C |
| DHW                    |           |          |
| Keep-warm              |           |          |
| Space heating          |           |          |
| Overall with keep warm |           |          |

|                      |  |  |
|----------------------|--|--|
| <b>Pressure test</b> |  |  |
| No HIU damage        |  |  |

|                              |    |  |
|------------------------------|----|--|
| <b>Dynamic DHW operation</b> | 2a |  |
| DHW not exceed 65°C          |    |  |

|   |    |    |
|---|----|----|
| <b>Low flow test at BESA flow rate of 0.02l/s</b> | 3a | 3b |
| DHW not exceed 65°C                               |    |    |
| DHW temperature at set point +/- 3°C              |    |    |

|   |    |    |
|---|----|----|
| <b>Low flow test at manufacturer declared flow rate</b> | 3c | 3d |
| Declared minimum flow rate (l/sec)                      |    |    |
| Not exceed 65°C   |    |    |
| DHW temperature at set point +/- 3°C                    |    |    |

|   |    |    |
|---|----|----|
| <b>Keep-warm test</b>                               | 4a | 4b |
| Standby heat consumption - average (Watts)          |    |    |
| Standby electricity consumption - average (Watts)   |    |    |
| Total HIU heat loss (DH + electrical input) (Watts) |    |    |
| Standby flow rate (the average flow rate) (l/hr)    |    |    |

|   |    |    |
|---|----|----|
| <b>DHW Response time test</b>                         | 5a | 5b |
| DHW response time (Seconds)                           |    |    |
| Peak electrical heat during test (Watts)              |    |    |
| Output  |    |    |
| DHW temperature not exceed 65°C for more than 10 secs |    |    |
| DHW reaches 45°C with 15 secs                         |    |    |

|   |   |    |    |
|---|---|----|----|
| <b>Scaling risk assessment as defined in 2.26</b> | If any of the factors below occur then the risk of scaling of the DHW PHE in hard water areas increases |    |    |
| HIU has a TMV or TRV on the DHW                   |   |    |    |
| Test  | 2a  | 3a | 3c |
| t32 above 60°C for more than 5 secs               |   |    |    |
| t12 exceeds 55°C at any point of the test         |   |    |    |
| Test  | 4a  |    | 4b |
| t12 exceeds 50°C at any time                      |   |    |    |




Photo of HIU being tested with the cover off.




Photo of HIU being tested with the cover on.




Photo of Manufacturers label and serial number.

## COMPONENT DATA AND DOCUMENTATION

[illegible]

|  |  |  |
|--|--|--|
| Schematic diagram and drawing showing the structure and arrangement of the HIU with dimensions and weight                            |  |  |
| Technical specification for electronic components including version of software  |  |  |
| Installation guide   |  |  |
| Commissioning guide  |  |  |
| Operation guide with a function description/ description of operations and care instructions as suited to the intended user category |  |  |
| Declaration of Conformity for CE-marked HIUs   |  |  |
| Full parameter list for electronically controlled HIUs   |  |  |

| HIU Marking             | Comment | Info present |
|-------------------------|---------|--------------|
| Model name and type no. |         |              |
| Serial no.              |         |              |

**HIU MANUFACTURERS' DECLARED INFORMATION** (TO BE COMPLETED BY THE MANUFACTURER)

|                  |  |
|------------------|--|
| HIU Model        |  |
| Part No.         |  |
| Software version |  |
| Test Date:       |  |
| Test No.         |  |

| DIMENSIONAL INFORMATION                    |  |
|--|--|
| Dimensions with casing (HxDxW) (mm)        |  |
| Primary connections top/bottom             |  |
| Secondary HTG connections top/bottom       |  |
| Secondary BCW/DHW connections top/bottom   |  |
| Connection sizes Prim/Sec DHW/Sec HTG (mm) |  |
| Empty weight kg** (Kg)                     |  |
| Operating weight kg** (Kg)                 |  |

| ELECTRICAL INFORMATION       |                |
|------------------------------|----------------|
| Power supply (230V 1 phase)  | <b>230V 1~</b> |
| Maximum power (Watts)        |                |
| Standby power demand (Watts) |                |

| HYDRAULIC INFORMATION                    |  |
|--|--|
| Maximum primary pressure (Bar g)         |  |
| Maximum primary temperature (°C)         |  |
| Primary water volume (l)                 |  |
| Maximum secondary DHW pressure (Bar g)   |  |
| Maximum secondary DHW temperature (°C)   |  |
| Secondary DHW water volume (l)           |  |
| Maximum secondary HTG pressure (Bar g)   |  |
| Maximum secondary HTG temperature (°C)   |  |
| Primary operating DP range min/max (kPa) |  |

| DECLARED MAXIMUM PERFORMANCE LT TEST CONDITIONS |              |
|---|--------------|
| DHW   |              |
| Maximum DHW production at 70°C (kW)             |              |
| Primary flow temperature (°C)                   | <b>70</b>    |
| Primary return temperature (°C)                 |              |
| Primary flow (m <sup>3</sup> /h)                |              |
| Primary $\Delta P^*$ (kPa)                      |              |
| Secondary in/out temperature (°C)               | <b>10/55</b> |
| Secondary $\Delta P$ (bar)                      |              |
| HTG   |              |
| Maximum HTG production (kW)                     |              |
| Primary flow temperature (°C)                   | <b>70</b>    |
| Primary return temperature (°C)                 |              |
| Primary $\Delta P^*$ (bar)                      |              |
| Secondary in/out temperature (°C)               | <b>40/60</b> |
| Secondary available DP at the output of HIU     |              |

| DECLARED MAXIMUM PERFORMANCE LT TEST CONDITIONS                    |       |
|--|-------|
| DHW  |       |
| Maximum DHW production at 60°C (kW)                                |       |
| Primary flow temperature (°C)                                      | 60    |
| Primary return temperature (°C)                                    |       |
| Primary flow (m³/h)  |       |
| Primary $\Delta P^*$ (kPa)   |       |
| Secondary in/out temperature (°C)                                  | 10/50 |
| Secondary $\Delta P$ (bar)   |       |
| HTG  |       |
| Maximum HTG production (kW)  |       |
| Primary flow temperature (°C)                                      | 60    |
| Primary return temperature (°C)                                    |       |
| Primary $\Delta P^*$ (bar)   |       |
| Secondary in/out temperature (°C)                                  | 35/45 |
| Secondary available DP at the output of the HIU (kPa)              |       |
| HIU P&ID supplied by manufacturer with a legend for the components |       |

\*DP pressure not to include HM. Designers must add HM pressure drop.

\*\* Including HIU, casing and wall hung bracket

The information included in this page is for the specific model of HIU detailed in this test report. It is additional information voluntarily provided by the manufacturer who is solely accountable for the details submitted.

## MANUFACTURERS' DECLARATION

This is to confirm that the information supplied by  
accurate representation of the product listed on the BESA HIU Register.

relates to the specific HIU tested and is an

Signed

Position

Company

## COMMENTS/HISTORY

**BESA HIU TEST REPORT**  
**Nexus BiTherm ECO 45/16R****Client: Elco Heating Solutions Ltd**

Project Number: E4611 Report Issue: 1

05 July 2022

Prepared By:



Simon Broxham – Principal Engineer

Approved By:



Josh Welburn - Engineering Project Manager



THIS PAGE IS INTENTIONALLY LEFT BLANK



## **DISCLAIMER**

This report is confidential to the client named on the front cover.

This report may be stored, transmitted, or reproduced in full by the named client, however if the report is to be placed in the public domain or used for publicity / promotional purposes please inform a director of Enertek International Ltd.

The report must not be reproduced in part, edited, abridged or any extracts used for any purpose whatsoever without written permission from a director of Enertek International Ltd.

The client remains responsible for any data supplied by the client for use in this report. If this data could affect the test results this will be noted in the report.

Any test results contained in this report apply only to the specific sample(s) tested as described in the report.

This report does not imply or indicate any element of commercial approval, recommendation, or promotion by Enertek International Ltd.

# CONTENTS

|          |   |           |
|----------|---|-----------|
| <b>1</b> | <b>BRIEF .....</b>  | <b>6</b>  |
| <b>2</b> | <b>DEFINITIONS.....</b>                                   | <b>7</b>  |
| <b>3</b> | <b>TEST OBJECT .....</b>                                  | <b>8</b>  |
| 3.1      | Appliance Details.....                                    | 8         |
| 3.2      | Appliance Design Pressures .....                          | 8         |
| 3.3      | Appliance Design Temperatures .....                       | 8         |
| <b>4</b> | <b>TEST METHOD.....</b>                                   | <b>9</b>  |
| 4.1      | Installation of Appliance .....                           | 9         |
| 4.2      | Test Regime .....   | 9         |
| 4.3      | Measurement & Uncertainties.....                          | 9         |
| <b>5</b> | <b>TEST RESULTS .....</b>                                 | <b>14</b> |
| 5.1      | Test 0 – Pressure Test .....                              | 14        |
| 5.2      | Test 1a to 1f – Space Heating 1-4 kW at 70 and 60°C ..... | 14        |
| 5.3      | Test 2a – DHW Dynamic Tapping at 70 °C.....               | 15        |
| 5.4      | Test 2b – DHW Dynamic Tapping at 60 °C .....              | 15        |
| 5.5      | Test 3a & 3c – Low Flow DHW at 70 °C.....                 | 15        |
| 5.6      | Test 3b & 3d – Low Flow DHW at 60 °C .....                | 16        |
| 5.7      | Test 4a – Keep-Warm at 70 °C .....                        | 16        |
| 5.8      | Test 4b – Keep-Warm at 60 °C .....                        | 17        |
| 5.9      | Test 5a – DHW Response Time at 70 °C.....                 | 17        |
| 5.10     | Test 5b – DHW Response Time at 60 °C.....                 | 17        |
| 5.11     | Overall Scaling Risk Assessment.....                      | 18        |
| 5.12     | VWART Calculations .....                                  | 19        |
| <b>6</b> | <b>CONCLUSIONS .....</b>                                  | <b>20</b> |
| <b>7</b> | <b>APPENDIX A.....</b>                                    | <b>21</b> |
| 7.1      | Key Metric Plots .....                                    | 21        |
| 7.2      | Key Metric and VWART Summary .....                        | 38        |
| <b>8</b> | <b>APPENDIX B .....</b>                                   | <b>41</b> |
| 8.1      | Appliance Documentation.....                              | 41        |
| 8.2      | Appliance Photographs .....                               | 42        |
| 8.3      | Calibrations and Uncertainties.....                       | 45        |

## LIST OF FIGURES

|  |    |
|--|----|
| Figure 4.1 – EIL’s HIU Test Rig Schematic .....                            | 10 |
| Figure 7.1 - Test 1a – Space Heating 1 kW at 70 °C .....                   | 22 |
| Figure 7.2 - Test 1b – Space Heating 2 kW at 70 °C .....                   | 23 |
| Figure 7.3 - Test 1c – Space Heating 4 kW at 70 °C .....                   | 24 |
| Figure 7.4 - Test 1d – Space Heating 1 kW at 60 °C .....                   | 25 |
| Figure 7.5 - Test 1e – Space Heating 2 kW at 60 °C .....                   | 26 |
| Figure 7.6 - Test 1f – Space Heating 4 kW at 60 °C .....                   | 27 |
| Figure 7.7 - Test 2a – DHW only at 70 °C .....                             | 28 |
| Figure 7.8 - Test 2b – DHW only at 60 °C .....                             | 29 |
| Figure 7.9 - Test 3a – Low Flow DHW at 70 °C .....                         | 30 |
| Figure 7.10 - Test 3b – Low Flow DHW at 60 °C .....                        | 31 |
| Figure 7.11 - Test 3c – Manufacturers Declared Low Flow DHW at 70 °C ..... | 32 |
| Figure 7.12 - Test 3d – Manufacturers Declared Low Flow DHW at 60 °C ..... | 33 |
| Figure 7.13 - Test 4a – Keep-Warm at 70 °C .....                           | 34 |
| Figure 7.14 - Test 4b – Keep-Warm at 60 °C .....                           | 35 |
| Figure 7.15 - Test 5a – DHW Response Time at 70 °C .....                   | 36 |
| Figure 7.16 - Test 5b – DHW Response Time at 60 °C .....                   | 37 |
| Figure 8.1 – Photograph of Appliance [Case Fitted] .....                   | 42 |
| Figure 8.2 – Photograph of Appliance [Case Removed] .....                  | 43 |
| Figure 8.3 – Appliance Data Label .....                                    | 44 |

## LIST OF TABLES

|  |    |
|--|----|
| Table 2.1 – Definitions and Abbreviations .....                                      | 7  |
| Table 3.1 – Appliance Details .....  | 8  |
| Table 3.2 – Appliance Design Pressures .....   | 8  |
| Table 3.3 – Appliance Design Temperatures .....                                      | 8  |
| Table 4.1 – Setup of Tests (Based on BESA Test Regime, Table 1: Test Schedule) ..... | 11 |
| Table 4.2 – Test Reporting, (Adapted from BESA Test Regime, Table 5) .....           | 12 |
| Table 5.1 - Test Results for Space Heating Tests 1a to 1f .....                      | 14 |
| Table 5.2 - Overall Scaling Risk Assessment .....                                    | 18 |
| Table 5.3 – High Temperature VWARD Calculations .....                                | 19 |
| Table 5.4 – Low Temperature VWARD Calculations .....                                 | 19 |
| Table 7.1 - Key Metrics of High Temperature Package .....                            | 39 |
| Table 7.2 - Key Metrics of Low Temperature Package .....                             | 40 |
| Table 8.1 – Documentation Supplied .....   | 41 |
| Table 8.2 - EIL Equipment Calibration and Uncertainties .....                        | 45 |

# 1 BRIEF

- 1.1.1 Enertek international Limited (EIL), were contracted to receive, install, and commission a production sample, of the Elco Nexus BiTherm ECO 45/16R.
- 1.1.2 To carry out the work involved to evaluate the performance of Domestic Hot Water (DHW) and Space Heating (SH) in accordance with the BESA UK HIU Test regime Technical Specification, Rev-009 October 2018, a publicly available online test regime. This is here-on referred to as the Test Regime throughout this document.
- 1.1.3 To provide a report detailing the tests carried out and generated results in accordance with the Test Regime criteria, including calculations for Volume Weighted Average Return Temperatures (VWART).

## 2 DEFINITIONS

2.1.1 The following definitions and abbreviations which have been used within this report can be found in table 2.1 below.

**Table 2.1 – Definitions and Abbreviations**

| Symbol            | Description  | Unit |
|-------------------|--|------|
| $P_1$             | Power, Primary Side  | kW   |
| $P_2$             | Power, Space Heating Side                                    | kW   |
| $P_3$             | Power, Domestic Hot Water                                    | kW   |
| $t_{11}$          | Temperature, Primary Side Supply Connection                  | °C   |
| $t_{12}$          | Temperature, Primary Side Return Connection                  | °C   |
| $t_{21}$          | Temperature, Space Heating Side Return Connection            | °C   |
| $t_{22}$          | Temperature, Space Heating System Supply Connection          | °C   |
| $t_{31}$          | Temperature, Cold Water Supply                               | °C   |
| $t_{32}$          | Temperature, Domestic Hot Water Output from HIU              | °C   |
| $q_1$             | Volume Flow, Primary Side                                    | L/s  |
| $q_2$             | Volume Flow, Space Heating Side                              | L/s  |
| $q_3$             | Volume Flow, Domestic Hot Water                              | L/s  |
| $\Delta p_1$      | Primary Pressure Drop Across Entire HIU Unit                 | kPa  |
| $\Delta p_2$      | Pressure Drop, Space Heating System Across HIU               | kPa  |
| $\Delta p_3$      | Pressure Drop, Domestic Hot Water Across HIU                 | kPa  |
| $VWART_{DHW}$     | DHW Volume Weighted Return Temperature                       | °C   |
| $VWART_{SH}$      | Space Heating Volume Weighted Return Temperature             | °C   |
| $VWART_{KWH}$     | Keep Warm Volume Weighted Return Temperature                 | °C   |
| $VWART_{HEAT}$    | Annual Volume Weighted Return Temperature for Heating Period | °C   |
| $VWART_{NONHEAT}$ | Annual Volume Weighted Return Temperature for Non-Heating    | °C   |
| $VWART_{HIU}$     | Total Annual Volume Weighted Return Temperature              | °C   |
| DHW               | Domestic Hot Water   | —    |
| HIU               | Heat Interface Unit  | —    |
| SH                | Space Heating  | —    |
| TMV               | Thermostatic Mixing Valve                                    | —    |
| EIL               | Enertek International Limited                                | -    |

### 3 TEST OBJECT

#### 3.1 Appliance Details

- 3.1.1 Details of the HIU Nexus BiTherm ECO 45/16R appliance are given in Table 3.1. Photograph of the installed appliance is given in Figure 8.2.

**Table 3.1 – Appliance Details**

| Item                | Description              |
|---------------------|--------------------------|
| Manufacturer        | Elco Ltd                 |
| Model               | Nexus BiTherm ECO 45/16R |
| Serial Number       | CTPE2H1522A26            |
| Year of Manufacture | 2022                     |
| DHW Priority        | Yes                      |

#### 3.2 Appliance Design Pressures

- 3.2.1 The maximum design pressures of the Nexus BiTherm ECO 45/16R appliance for the primary side and the secondary side for both Space Heating and DHW are given in Table 3.2.

**Table 3.2 – Appliance Design Pressures**

| Item                         | Value | Unit |
|------------------------------|-------|------|
| Primary Side                 | 16    | Bar  |
| Secondary Side Space Heating | 3     | Bar  |
| Secondary Side DHW           | 10    | Bar  |

#### 3.3 Appliance Design Temperatures

- 3.3.1 The maximum design temperatures of the Nexus BiTherm ECO 45/16R appliance for the primary side and the secondary side for both Space Heating and DHW are given in Table 3.3

**Table 3.3 – Appliance Design Temperatures**

| Item                         | Value | Unit |
|------------------------------|-------|------|
| Primary Side                 | 85    | °C   |
| Secondary Side Space Heating | 85    | °C   |
| Secondary Side DHW           | 85    | °C   |

## 4 TEST METHOD

### 4.1 Installation of Appliance

- 4.1.1 The appliance was installed and commissioned (as received) and as defined in the product literature provided. Testing was carried out without further adjustment other than disabling the internal space heating pump and adjusting the setting of the SH and DHW set points through the user interface on the HIU controller to suit the conditions of the HIU test rig. The HIU rig schematic is given in Figure 4.1.

### 4.2 Test Regime

- 4.2.1 The testing described in this report was carried out in accordance with the BESA Test Regime. The Test Regime outlines a series of static and dynamic tests to determine the performance of a HIU's DHW and SH functions. The Regime outlines the test method including the reporting of the results, the performance requirements and the VWART calculations.
- 4.2.2 The setup of the BESA tests is reproduced in Table 4.1. The basis of reporting the performance of the HIU from the BESA Test Regime is reproduced in Table 4.2.
- 4.2.3 The Test Regime specifies the testing of two different test temperature packages. The first is the high temperature package, with a district primary supply of 70 °C and the second is the 'low temperature' package, with a district primary supply temperature of 60 °C.
- 1.1.1 As the Elco Ltd Nexus BiTherm ECO 45/16R is suitable for both high and low temperature operation, both test packages were carried out and results recorded within this report.

### 4.3 Measurement & Uncertainties

- 4.3.1 All measurements and uncertainties adhere to the requirements stipulated in the BESA Test Regime. All measurements were sampled at a rate of 1 Hz for all tests.
- 4.3.2 The BESA uncertainties of measurement requirements are as follows: Differential Pressure,  $\pm 1$  kPa; Temperature,  $\pm 0.1$  °C; Volume Flow,  $\pm 1.5$  %. Note: the time constant for the temperature sensors is less than 1.5 s.
- 4.3.3 EIL's reported uncertainty is based on a standard uncertainty by a coverage factor  $K=2$ , providing a level of confidence of approximately 95%. The uncertainty evaluation has been carried out in accordance with UKAS requirements. The EIL equipment list and uncertainties are given in Table 8.2, Appendix B.




Figure 4.1 – EIL's HIU Test Rig Schematic



**Table 4.1 – Setup of Tests (Based on BESA Test Regime, Table 1: Test Schedule)**

|                      |                        | <i>District Circuit</i> |                       |                  | <i>Domestic Hot Water</i> |                  |                  | <i>Space Heating</i> |                    |           |
|----------------------|------------------------|-------------------------|-----------------------|------------------|---------------------------|------------------|------------------|----------------------|--------------------|-----------|
|                      |                        | Static Pressure         | Differential Pressure | Flow Temperature | Temperature Set Point     | Flow Rate        | Heat Load        | Flow Temperature     | Return Temperature | Heat Load |
| <i>Symbol</i>        |                        | $[p_1]$                 | $[\Delta p_1]$        | $[t_{11}]$       | $[t_{32}]$                | $[q_3]$          | $[P_3]$          | $[t_{22}]$           | $[t_{21}]$         | $[P_2]$   |
| <i>Units</i>         |                        | $[kPa]$                 | $[kPa]$               | $[^{\circ}C]$    | $[^{\circ}C]$             | $[Ls^{-1}]$      | $[kW]$           | $[^{\circ}C]$        | $[^{\circ}C]$      | $[kW]$    |
| <b>Static Tests</b>  |                        |                         |                       |                  |                           |                  |                  |                      |                    |           |
| 0a                   | District Pressure Test | 1.43 X Claimed Value    | -                     | -                | -                         | -                | -                | -                    | -                  | -         |
| 1a                   | 1kW Space Heating      | 3.0                     | 0.5                   | 70               | -                         | -                | -                | 60                   | 40                 | 1         |
| 1b                   | 2kW Space Heating      | 3.0                     | 0.5                   | 70               | -                         | -                | -                | 60                   | 40                 | 2         |
| 1c                   | 4kW Space Heating      | 3.0                     | 0.5                   | 70               | -                         | -                | -                | 60                   | 40                 | 4         |
| 1d                   | 1kW Space Heating      | 3.0                     | 0.5                   | 60               | -                         | -                | -                | 45                   | 35                 | 1         |
| 1e                   | 2kW Space Heating      | 3.0                     | 0.5                   | 60               | -                         | -                | -                | 45                   | 35                 | 2         |
| 1f                   | 4kW Space Heating      | 3.0                     | 0.5                   | 60               | -                         | -                | -                | 45                   | 35                 | 4         |
| <b>Dynamic Tests</b> |                        |                         |                       |                  |                           |                  |                  |                      |                    |           |
| 2a                   | Dynamic Tapping        | 3.0                     | 0.5                   | 70               | 55                        | See Test Profile | See Test Profile | -                    | -                  | -         |
| 2b                   | Dynamic Tapping        | 3.0                     | 0.5                   | 60               | 50                        |                  |                  | -                    | -                  | -         |
| 3a                   | Low Flow               | 3.0                     | 0.5                   | 70               | 55                        | 0.02             | Record Value     | -                    | -                  | -         |
| 3b                   | Low Flow               | 3.0                     | 0.5                   | 60               | 50                        | 0.02             | Record Value     | -                    | -                  | -         |
| 4a                   | Keep-Warm              | 3.0                     | 0.5                   | 70               | 55                        | 0.00             | 0                | -                    | -                  | -         |
| 4b                   | Keep-Warm              | 3.0                     | 0.5                   | 60               | 50                        | 0.00             | 0                | -                    | -                  | -         |
| 5a                   | DHW Response           | 3.0                     | 0.5                   | 70               | 55                        | 0.13             | Record Value     | -                    | -                  | -         |
| 5b                   | DHW Response           | 3.0                     | 0.5                   | 60               | 50                        | 0.13             | Record Value     | -                    | -                  | -         |

**Table 4.2 – Test Reporting, (Adapted from BESA Test Regime, Table 5)**

| Test Designation |  | Reporting   |
|------------------|--|---|
| 0                | District Pressure Test                 | Pass/Fail as to whether HIU manages pressure test without leaks or damage.  |
| 1a               | Space Heating 1 kW, 60/40 °C Secondary | $t_{11}$ – Primary flow temperature.<br>$t_{12}$ – Primary return temperature.  |
| 1b               | Space Heating 2 kW, 60/40 °C Secondary | Plot of key metrics over duration of test.  |
| 1c               | Space Heating 4 kW, 60/40 °C Secondary | <b>Note:</b> Outputs used as input data to ‘High Temperature’ Space Heating Volume Weighted Average Return Temperature calculation.   |
| 1d               | Space Heating 1 kW, 45/35 °C Secondary | $t_{11}$ – Primary flow temperature.<br>$t_{12}$ – Primary return temperature.  |
| 1e               | Space Heating 2 kW, 45/35 °C Secondary | Plot of key metrics over duration of test.  |
| 1f               | Space Heating 4 kW, 45/35 °C Secondary | <b>Note:</b> Outputs used as input data to ‘Low Temperature’ Space Heating Volume Weighted Average Return Temperature calculation.  |
| 2a               | DHW only, DH 70 °C Flow, 55 °C DHW     | Pass/Fail on DHW (at $t_{32}$ ) exceeding 65.0 °C (to 1 decimal point) for more than 10 consecutive seconds.<br>State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow.<br>Assessment of scaling risk as per the criteria detailed in 2.26.<br><b>Note:</b> Outputs used as input data to ‘High Temperature’ Space Heating Volume Weighted Average Return Temperature calculation.<br>Plot $t_{32}$ , $t_{31}$ , $q_3$ , $t_{12}$ , $q_1$  |
| 2b               | DHW only, DH 60 °C Flow, 50 °C DHW     | State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow.<br><b>Note:</b> Outputs used as input data to ‘Low Temperature’ Domestic Hot Water Volume Weighted Average Return Temperature calculation.<br>Plot $q_1$ , $q_3$ , $dp_1$ , $dp_3$   |
| 3a               | Low Flow DHW, DH 70 °C Flow, 55 °C DHW | Pass/Fail on DHW (at $t_{32}$ ) exceeding 65.0 °C (1 decimal place) for more than 10 consecutive seconds.<br>Comment on ability to deliver DHW at low flow based on DHW temperature reaching at least 45.0 °C (1 decimal place) at the end of the 180 second period of low flow DHW.<br>Comment on the ability to deliver stable DHW flow temperature (at $t_{32}$ ), defined as ability to maintain 55.0 +/- 3.0 °C (1 decimal place) during the last 60 seconds of the test.<br>Maximum temperature achieved and +/- °C variance around 55.0 °C (1 decimal place) to be stated.<br>Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.<br>Assessment of scaling risk as per criteria detailed in 2.26. |
| 3b               | Low Flow DHW, DH 60 °C Flow, 50 °C DHW | Comment on the ability to deliver DHW at low flow rate based on DHW temperature reaching at least 45 °C (1 decimal place) at the end of the 180 second period of low flow DHW.<br>Comment on the ability to deliver stable DHW flow temperature (at $t_{32}$ ), defined as ability to maintain 50.0 +/- 3 °C (1 decimal place) to be stated.<br>Maximum temperature achieved and +/- °C variance around 50.0 °C (1 decimal place) to be stated.<br>Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.   |

| Test Designation |   | Reporting  |
|------------------|---|--|
| 4a               | Keep-Warm,<br>DH 70 °C Flow,<br>55 °C DHW         | <p>Assessment of whether valid Keep-Warm operation, based on 5a response time criteria: Pass/Fail.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Assessment of scaling risk based on duration of temperatures in excess of 55.0 °C (1 decimal place).</p> <p>State average heat load for the duration of the test.</p> <p>State the average primary flow rate for the duration of the test.</p> <p>Note: Outputs used as input data to 'High Temperature' Keep-Warm Volume Weighted Average Return Temperature calculation.</p> <p>Plot of key metrics over duration of test.</p>   |
| 4b               | Keep-Warm,<br>DH 60 °C Flow,<br>50 °C DHW         | <p>Assessment of whether valid Keep-Warm operation, based on 5a response time criteria: Pass/Fail.</p> <p>Observation on the operation of the HIU during Keep-Warm. Comment on HIU Keep-Warm controls options.</p> <p>Assessment of scaling risk based on extent and duration of temperatures in excess of 55.0 °C (1 decimal place).</p> <p>State average heat load for the duration of the test.</p> <p>State the average primary flowrate for the duration of the test.</p> <p><b>Note:</b> Outputs used as input data to 'Low Temperature' Keep-Warm Volume Weighted Average Return Temperature calculation.</p> <p>Plot of key metrics over duration of test.</p> |
| 5a               | DHW Response Time,<br>DH 70 °C Flow,<br>55 °C DHW | <p>Pass/Fail on DHW (at <math>t_{32}</math>) exceeding 65.0 °C (1 decimal place) for more than 10 consecutive seconds.</p> <p>State time to achieve 45.0 °C (1 decimal place) and not subsequently drop below 42.0 °C (1 decimal place).</p> <p>Plot <math>t_{32}</math>, <math>t_{31}</math>, <math>t_{12}</math>, <math>q_1</math> over duration of test.</p>  |
| 5b               | DHW Response Time,<br>DH 60 °C Flow,<br>50 °C DHW | <p>State time to achieve a DHW temperature 45.0 °C (1 decimal place) and not subsequently drop below 42.0 °C (1 decimal place).</p> <p>Comment on stability of DHW temperature.</p> <p>Plot <math>t_{32}</math>, <math>t_{31}</math>, <math>t_{12}</math>, <math>q_1</math> over duration of test.</p>   |

## 5 TEST RESULTS

### 5.1 Test 0 – Pressure Test

- 5.1.1 The appliance has passed the requirements of the static pressure test, Test 0 of the BESA Test Regime as:
- 5.1.2 There was No damage observed during the static pressure test, with the primary flow pressurised to 22.88 bar (1.43 times the rated value), and,
- 5.1.3 There were No leaks observed during the static pressure test, with the primary flow pressurised to 22.88 bar (1.43 times the rated value).

### 5.2 Test 1a to 1f – Space Heating 1-4 kW at 70 and 60°C

- 5.2.1 The plot of the key metrics of Tests 1a-1f for the space heating 1 - 4 kW at both 70 and 60 °C are displayed in Figure 7.1 to Figure 7.6 respectively. See Table 5.1 for summarised test results including the average primary return temperature,  $t_{12}$ .

**Table 5.1 - Test Results for Space Heating Tests 1a to 1f**

| Test No & Description                   | Primary          |                    |                     |                       |           | Secondary          |                  |                     |                       |           |
|---|------------------|--------------------|---------------------|-----------------------|-----------|--------------------|------------------|---------------------|-----------------------|-----------|
|   | Flow Temperature | Return Temperature | Flow Rate           | Differential Pressure | Heat Load | Return Temperature | Flow Temperature | Flow Rate           | Differential Pressure | Heat Load |
|   | $[t_{11}]$       | $[t_{12}]$         | $[q_1]$             | $[\Delta p_1]$        | $[P_1]$   | $[t_{21}]$         | $[t_{22}]$       | $[q_2]$             | $[\Delta p_2]$        | $[P_2]$   |
|   | [°C]             | [°C]               | [Ls <sup>-1</sup> ] | [kPa]                 | [W]       | [°C]               | [°C]             | [Ls <sup>-1</sup> ] | [kPa]                 | [W]       |
| 1a - 1 kW Space Heating (DH 70 °C flow) | 70.2             | 39.6               | 0.009               | 50.2                  | 1140      | 40.1               | 59.8             | 0.012               | 1.3                   | 965       |
| 1b - 2 kW Space Heating (DH 70 °C flow) | 70.3             | 40.0               | 0.017               | 50.6                  | 2204      | 39.8               | 59.8             | 0.024               | 1.7                   | 2006      |
| 1c - 4 kW Space Heating (DH 70 °C flow) | 70.4             | 41.2               | 0.035               | 49.6                  | 4283      | 40.1               | 60.2             | 0.048               | 3.6                   | 4021      |
| 1d - Space Heating 1 kW (DH 60 °C flow) | 59.8             | 34.4               | 0.010               | 51.2                  | 1062      | 34.9               | 44.6             | 0.024               | 1.7                   | 975       |
| 1e - Space Heating 2 kW (DH 60 °C flow) | 60.2             | 34.6               | 0.020               | 49.8                  | 2094      | 35.0               | 44.9             | 0.048               | 3.3                   | 2001      |
| 1f - Space Heating 4 kW (DH 60 °C flow) | 60.2             | 35.0               | 0.039               | 49.7                  | 4112      | 35.2               | 45.2             | 0.096               | 9.5                   | 4008      |

### **5.3 Test 2a – DHW Dynamic Tapping at 70 °C**

- 5.3.1 The appliance has passed the requirements of the DHW only at 70 °C, Test 2a of the BESA Test Regime as:
- 5.3.2 The domestic hot water output temperature,  $t_{32}$  did not exceed 65 °C for more than 10 seconds.
- 5.3.3 The maximum and minimum temperatures of  $t_{32}$  were 59.1 °C and 46.6 °C respectively.
- 5.3.4 The plot of the key metrics of the duration of Test 2a is displayed in Figure 7.7, Appendix A.

### **5.4 Test 2b – DHW Dynamic Tapping at 60 °C**

- 5.4.1 The maximum and minimum temperatures of  $t_{32}$  were 53.3 °C and 42.3 °C respectively.
- 5.4.2 The plot of the key metrics of the duration of Test 2b is displayed in Figure 7.8, Appendix A.

### **5.5 Test 3a & 3c – Low Flow DHW at 70 °C**

- 5.5.1 The appliance has passed the requirements of the Low Flow at 70 °C, Test 3a of the BESA Test Regime as:
- 5.5.2 The domestic hot water output temperature,  $t_{32}$  did not exceed 65 °C for more than 10 seconds.
- 5.5.3 The appliance did not maintain the DHW output temperature,  $t_{32}$  at  $55 \pm 3$  °C during the last 60 seconds of the test.
- 5.5.4 As the appliance did not maintain a stable flow temperature at 1.2 l/min, the appliance was retested as test 3c at the manufacturers declared low flow rate which was 2.4 l/min.
- 5.5.5 At the manufacturers low flow rate of 2.4 l/min the appliance did maintain the DHW output temperature  $t_{32}$  at  $55 \pm 3$  °C during the last 60 seconds of the test.
- 5.5.6 The plot of the key metrics of the duration of Test 3a is displayed in Figure 7.9, Appendix A.
- 5.5.7 The plot of the key metrics of the duration of Test 3c is displayed in Figure 7.11, Appendix A.

## **5.6 Test 3b & 3d – Low Flow DHW at 60 °C**

- 5.6.1 The appliance did not maintain stable flow temperatures during Low Flow at 60 °C, Test 3b of the BESA Test Regime.
- 5.6.2 The appliance was retested as test 3d at the manufacturers declared low flow rate which was 2.4 l/min, the appliance was then seen to maintain DHW output temperature  $t_{32}$  at 50°C during the last 60 seconds of the test.
- 5.6.3 The plot of the key metrics of the duration of Test 3b is displayed in Figure 7.10, Appendix A.
- 5.6.4 Test 3d is displayed in Figure 7.12, Appendix A.

## **5.7 Test 4a – Keep-Warm at 70 °C**

- 5.7.1 The appliance has passed the requirements of the Keep-Warm at 70 °C, Test 4a of the BESA Test Regime as:
- 5.7.2 This is a valid Keep-Warm operation based on 5a response time criteria, see 5.9.3.
- 5.7.3 The appliance is performing Keep-Warm cycling as the primary flow temperature,  $t_{11}$  varies by more than  $\pm 3$  °C during the final 3 hours of the test. Please see BESA HIU standard technical note TN-018 Version 1 for a more detailed definition of cyclical data.
- 5.7.4 The average heat load on the primary side  $P_1$  is 48 W.
- 5.7.5 The average electrical consumption was 4.2 W.
- 5.7.6 The average primary flow  $q_1$  over the 8 hours test was 2.8 l/hr.
- 5.7.7 The Keep-Warm control was set to 45°C.
- 5.7.8 The plot of the key metrics of the duration of Test 4a is displayed in Figure 7.13, Appendix A.

## **5.8 Test 4b – Keep-Warm at 60 °C**

- 5.8.1 The appliance has passed the requirements of the Keep-Warm at 60 °C, Test 4b of the BESA Test Regime as:
- 5.8.2 This is a valid Keep-Warm operation based on 5b response time criteria, see 5.10.1.
- 5.8.3 The appliance is performing Keep-Warm cycling as the primary flow temperature,  $t_{11}$  varies by more than  $\pm 3$  °C during the final 3 hours of the test. Please see BESA HIU Standard Technical Note TN-018 Version 1 for a more detailed definition of cyclical data.
- 5.8.4 The average heat load on the primary side  $P_1$  is 59 W.
- 5.8.5 The average primary flow  $q_1$  over the 8 hours test was 5.3 l/hr.
- 5.8.6 The average electrical consumption was 4.2 W.
- 5.8.7 The Keep-Warm control was set to 45°C.
- 5.8.8 The plot of the key metrics of the duration of Test 4b is displayed in Figure 7.14, Appendix A.

## **5.9 Test 5a – DHW Response Time at 70 °C**

- 5.9.1 The appliance has passed the requirements of DHW Response Time at 70 °C, Test 5a of the BESA Test Regime as:
- 5.9.2 The domestic hot water output temperature,  $t_{32}$  did not exceed 65 °C for more than 10 seconds.
- 5.9.3 The DHW response time for  $t_{32}$  to reach 45 °C (and not subsequently drop below 42 °C) was 15 seconds; therefore this is a valid Keep-Warm.
- 5.9.4 The plot of the key metrics of the duration of Test 5a is displayed in Figure 7.15, Appendix A.

## **5.10 Test 5b – DHW Response Time at 60 °C**

- 5.10.1 The DHW response time for  $t_{32}$  to reach 45 °C (and not subsequently drop below 42 °C) was 15 seconds; therefore this is a valid keep warm.
- 5.10.2 The plot of the key metrics of the duration of Test 5b is displayed in Figure 7.16, Appendix A.

## 5.11 Overall Scaling Risk Assessment

- 5.11.1 If any of the below factors occur, then the risk of scaling of the DHW plate in hard water areas increases.

**Table 5.2 - Overall Scaling Risk Assessment**

|   |           |           |
|---|-----------|-----------|
| <i>HIU has a TMV or TRV on the output of the DHW plate heat exchanger</i> | No        |           |
| <b>Test Designation</b>   | <b>2a</b> | <b>3a</b> |
| <i>t<sub>32</sub> above 60°C for more than 5 seconds</i>                  | No        | Yes       |
| <i>t<sub>12</sub> exceeds 55°C at any point of the test</i>               | No        | No        |
| <b>Test Designation</b>   | <b>4a</b> | <b>4b</b> |
| <i>t<sub>12</sub> exceeds 50°C at any time</i>                            | No        | No        |



## 5.12 VWART Calculations

- 5.12.1 The Volume Weighted Average Return Temperatures (VWART) have been calculated as stipulated in the BESA UK HIU Test Regime document. The calculated VWART values for both the high temperature and low temperature tests described in this report are given below in Table 5.3 and Table 5.4 respectively.

**Table 5.3 – High Temperature VWART Calculations**

| Description  | Symbol                   | Value | Unit |
|--|--------------------------|-------|------|
| Annual Heating Period Percentage                             | SH <sub>PROP</sub>       | 7     | %    |
| Annual Non-Heating Period Percentage                         | NSH <sub>PROP</sub>      | 93    | %    |
| Space Heating Volume Weighted Return Temperature             | VWART <sub>SH</sub>      | 40    | °C   |
| DHW Volume Weighted Return Temperature                       | VWART <sub>DHW</sub>     | 13    | °C   |
| Keep Warm Volume Weighed Return Temperature                  | VWART <sub>KWM</sub>     | 43    | °C   |
| Annual Volume Weighted Return Temperature for Heating Period | VWART <sub>HEAT</sub>    | 40    | °C   |
| Annual Volume Weighted Return Temperature for Non-Heating    | VWART <sub>NONHEAT</sub> | 28    | °C   |
| Total Annual Volume Weighted Return Temperature              | VWART <sub>OVERALL</sub> | 29    | °C   |

**Table 5.4 – Low Temperature VWART Calculations**

| Description  | Symbol                   | Value | Unit |
|--|--------------------------|-------|------|
| Annual Heating Period Percentage                             | SH <sub>PROP</sub>       | 7     | %    |
| Annual Non-Heating Period Percentage                         | NSH <sub>PROP</sub>      | 93    | %    |
| Space Heating Volume Weighted Return Temperature             | VWART <sub>SH</sub>      | 35    | °C   |
| DHW Volume Weighted Return Temperature                       | VWART <sub>DHW</sub>     | 15    | °C   |
| Keep Warm Volume Weighed Return Temperature                  | VWART <sub>KWM</sub>     | 44    | °C   |
| Annual Volume Weighted Return Temperature for Heating Period | VWART <sub>HEAT</sub>    | 35    | °C   |
| Annual Volume Weighted Return Temperature for Non-Heating    | VWART <sub>NONHEAT</sub> | 33    | °C   |
| Total Annual Volume Weighted Return Temperature              | VWART <sub>OVERALL</sub> | 33    | °C   |

## 6 CONCLUSIONS

6.1.1 The appliance has passed the performance requirements of the BESA HIU Test Regime.

## **7 APPENDIX A**

### **7.1 Key Metric Plots**

- 7.1.1 The graphical plots of the key metrics of the tests described in this report are given in this section.

GRAPHICAL PLOTS START ON NEXT PAGE




Figure 7.1 - Test 1a – Space Heating 1 kW at 70 °C





Figure 7.2 - Test 1b – Space Heating 2 kW at 70 °C



**Figure 7.3 - Test 1c – Space Heating 4 kW at 70 °C**





Figure 7.4 - Test 1d – Space Heating 1 kW at 60 °C



**Figure 7.5 - Test 1e – Space Heating 2 kW at 60 °C**






Figure 7.6 - Test 1f – Space Heating 4 kW at 60 °C




Figure 7.7 - Test 2a – DHW only at 70 °C




Figure 7.8 - Test 2b – DHW only at 60 °C





Figure 7.9 - Test 3a – Low Flow DHW at 70 °C



**Figure 7.10 - Test 3b – Low Flow DHW at 60 °C**




Figure 7.11 - Test 3c – Manufacturers Declared Low Flow DHW at 70 °C




Figure 7.12 - Test 3d – Manufacturers Declared Low Flow DHW at 60 °C




Figure 7.13 - Test 4a – Keep-Warm at 70 °C






Figure 7.14 - Test 4b – Keep-Warm at 60 °C




Figure 7.15 - Test 5a – DHW Response Time at 70 °C




Figure 7.16 - Test 5b – DHW Response Time at 60 °C

## **7.2 Key Metric and VWARD Summary**

- 7.2.1 The summary tables of the key metrics and VWARDS of the tests described in this report are given in this section.

SUMMARY TABLES START ON NEXT PAGE



#### VWART Calculation with Keep Warm

Test carried out by Enertek International for High Temperature BESA Tests

Manufacturer: Elco Heating Solutions Ltd

Model: Nexus BiTherm ECO 45/16R

Serial number: CTPE2H1522A26

Calculation performed by S.Broxham of Enertek on: 27/06/2022

Primary Flow Temperature: 70°C

DHW Setpoint: 55°C

Space Heating Temperature: 60/40°C

|               | VWART (°C) | Volume (m3) |
|---------------|------------|-------------|
| DHW           | 13         | 21.7        |
| Standby       | 43         | 22.4        |
| Space Heating | 40         | 45.7        |

| VWART with keep warm active |            |        |
|-----------------------------|------------|--------|
| Period                      | VWART (°C) | % Time |
| No Heating                  | 28         | 93%    |
| Heating                     | 40         | 7%     |
| Overall                     | 29         |        |

| Test Results              |    |       |              |       |             |                  |        |            |                  |
|---------------------------|----|-------|--------------|-------|-------------|------------------|--------|------------|------------------|
|                           |    | Power | Primary flow | VWART | Energy Used | Annual Operation | Volume | Events     | Average duration |
|                           |    | [W]   | [m³/hr]      | [°C]  | [kWh]       | [Hours]          | [m³]   | [Per Year] | [Seconds]        |
| 1kW Space Heating         | 1a | 1140  | 0.032        | 40    | 116         | 101.5            | 3.26   | -          | -                |
| 2kW Space Heating         | 1b | 2204  | 0.063        | 40    | 865         | 392.4            | 24.67  | -          | -                |
| 4kW Space Heating         | 1c | 4283  | 0.127        | 41    | 602         | 140.5            | 17.79  | -          | -                |
| DHW Low Flow Rate         | 2a | 11094 | 0.158        | 13    | 682         | 65.7             | 10.38  | -          | -                |
| DHW Medium Flow Rate      | 2a | 18601 | 0.284        | 14    | 296         | 16.0             | 4.53   | -          | -                |
| DHW High Flow Rate        | 2a | 24119 | 0.370        | 14    | 442         | 18.4             | 6.80   | -          | -                |
| DHW Post Low Flow Rate    | 2a | -     | 0.000        | 0     | -           | -                | 0.00   | 10000      | 30               |
| DHW Post Medium Flow Rate | 2a | -     | 0.000        | 13    | -           | -                | 0.00   | 660        | 70               |
| DHW Post High Flow Rate   | 2a | -     | 0.000        | 14    | -           | -                | 0.00   | 300        | 145              |
| DHW Keep Warm Standby     | 4a | -     | 0.003        | 43    | -           | 8025.5           | 22.44  | -          | -                |

Table 7.1 - Key Metrics of High Temperature Package



#### VWART Calculation with Keep Warm

Test carried out by Enertek International for Low Temperature BESA Tests  
 Manufacturer: Elco Heating Solutions Ltd  
 Model: Nexus BiTherm ECO 45/16R  
 Serial number: CTPE2H1522A26  
 Calculation performed by S.Broxham of Enertek on: 27/06/2022

Primary Flow Temperature: 60°C  
 DHW Setpoint: 50°C  
 Space Heating Temperature: 45/35°C

|               | VWART (°C) | Volume (m3) |
|---------------|------------|-------------|
| DHW           | 15         | 27.0        |
| Standby       | 44         | 43.0        |
| Space Heating | 35         | 51.3        |

|            | VWART with keep warm active |        |
|------------|-----------------------------|--------|
| Period     | VWART (°C)                  | % Time |
| No Heating | 33                          | 93%    |
| Heating    | 35                          | 7%     |
| Overall    | 33                          |        |

|                           |    | Test Results |                         |               |                      |                             |                |                      |                               |
|---------------------------|----|--------------|-------------------------|---------------|----------------------|-----------------------------|----------------|----------------------|-------------------------------|
|                           |    | Power<br>[W] | Primary flow<br>[m³/hr] | VWART<br>[°C] | Energy Used<br>[kWh] | Annual Operation<br>[Hours] | Volume<br>[m³] | Events<br>[Per Year] | Average duration<br>[Seconds] |
| 1kW Space Heating         | 1d | 1062         | 0.036                   | 34            | 107                  | 100.5                       | 3.63           | -                    | -                             |
| 2kW Space Heating         | 1e | 2094         | 0.071                   | 35            | 823                  | 393.3                       | 27.80          | -                    | -                             |
| 4kW Space Heating         | 1f | 4112         | 0.141                   | 35            | 579                  | 140.8                       | 19.83          | -                    | -                             |
| DHW Low Flow Rate         | 2b | 9941         | 0.175                   | 14            | 672                  | 73.3                        | 12.85          | -                    | -                             |
| DHW Medium Flow Rate      | 2b | 16916        | 0.327                   | 15            | 298                  | 17.6                        | 5.75           | -                    | -                             |
| DHW High Flow Rate        | 2b | 21672        | 0.412                   | 15            | 440                  | 20.5                        | 8.44           | -                    | -                             |
| DHW Post Low Flow Rate    | 2b | -            | 0.000                   | 0             | -                    | -                           | 0.00           | 10000                | 30                            |
| DHW Post Medium Flow Rate | 2b | -            | 0.000                   | 15            | -                    | -                           | 0.00           | 660                  | 70                            |
| DHW Post High Flow Rate   | 2b | -            | 0.001                   | 16            | -                    | -                           | 0.00           | 300                  | 145                           |
| DHW Keep Warm Standby     | 4b | -            | 0.005                   | 44            | -                    | 8014.0                      | 42.96          | -                    | -                             |

Table 7.2 - Key Metrics of Low Temperature Package

## 8 APPENDIX B

### 8.1 Appliance Documentation

8.1.1 The details of the appliance documentation are given in Table 8.1 below.

**Table 8.1 – Documentation Supplied**

|    | Component:   | Document Submitted (Y/N): | Manufacturer and type:                              |
|----|--|---------------------------|---|
| 1  | Space Heating Heat Exchanger   | Y                         | Swep E8LAS (Max70plates)                            |
| 2  | Domestic Hot Water Heat Exchanger  | Y                         | Swep E8LAS  |
| 3  | Controller for Space Heating   | Y                         | Argus Vision 882MS20_2Rb3c                          |
| 4  | Control Valve and Actuator for Space Heating   | Y                         | Frese 53-1304 PICV, 53-1183 Actuator                |
| 5  | Space Heating Strainer   | NA                        | NA  |
| 6  | Controller for Domestic Hot Water  | Y                         | Argus Vision 882MS20_2Rb3c                          |
| 7  | Control Valve and Actuator for Domestic Hot Water  | Y                         | Frese OEM DN20 PICV, 53-1183 Actuator               |
| 8  | Temperature Sensors  | Y                         | Tasseron TSB0AI                                     |
| 9  | Domestic Hot Water Isolating Valve   | NA                        | NA  |
| 10 | Primary Side Strainer  | NA                        | NA  |
| 11 | Drain Valves   | Y                         | Rastelli 25008                                      |
| 12 | Vent Valves  | NA                        | NA  |
| 13 | Circulation Pump set with AAV & PRV  | Y                         | Wilo Yonos Para 15/7.0                              |
| 14 | Heat Meter   | Y                         | Ploumeters RC15 DN15                                |
| 15 | Domestic Hot Water Flow Sensor   | Y                         | Sika VTY10  |
| 16 | Pipes  | Y                         | Hecapo 4503419000                                   |
| 17 | Connections  | Y                         | Hecapo 4503416500                                   |
| 18 | Joints   | NA                        | NA  |
| 19 | Gaskets  | Y                         | Donit Tesnit BA-U                                   |
| 20 | Expansion Vessel   | Y                         | Aquasystems VRP220-8                                |
| 21 | Insulation   | Y                         | Bautech 75-0, Armaflex AC,                          |
| 22 | Pressure Sensors   | Y                         | Huba OEM 505  |
| A1 | 'O' Ring   | NA                        | NA  |
| A2 | Commissioning guide.   | Y                         |   |
| A3 | Operation guides with a function description / description of operation and care instructions as suited to the intended user category. | Y                         | ViewSmart Temperature Control Instructions 2551851A |
| A4 | Declaration of Conformity for CE-marked HIUs.  | Y                         | 2020-05-01_EC Declaration                           |
| A5 | Full parameter list for electrically controlled HIUs.  | Y                         | Control Parameters                                  |
|    | Maximum primary static operating differential pressure.  | NA                        | Static - 16 bar, Differential - 4 bar               |
|    | Deactivation procedure of the internal SH pump.  | NA                        | SH Pump was unplugged                               |
|    | Model name and type number   | Y                         | Nexus BiTherm ECO 45/16R                            |
|    | Serial number  |                           | CTPE2H1522A26                                       |

## 8.2 Appliance Photographs



Figure 8.1 – Photograph of Appliance [Case Fitted]



Page 43 of 48




Figure 8.3 – Appliance Data Label

### 8.3 Calibrations and Uncertainties

8.3.1 A list of equipment, their calibrations and uncertainties are given in table 8.2 below.

**Table 8.2 - EIL Equipment Calibration and Uncertainties**

| Equipment Name                                 | ID Number | Calibration Certificate | Measurement Uncertainty<br>$K=2$<br>$\frac{U}{\sqrt{20}}$ | Units | Calibration Date | Calibration Due |
|--|-----------|-------------------------|---|-------|------------------|-----------------|
| Flow Meter<br>[Primary Flow Rate]              | FM 601    | K48376FW1S2             | ±0.0004   | l/s   | 07/07/2021       | 07/2022         |
| Flow Meter<br>[DHW Flow Rate]                  | FM 602    | K48378FW                | ±0.00305  | l/s   | 07/07/2021       | 07/2022         |
| Flow Meter<br>[SH Flow Rate]                   | FM 603    | K48377FW                | ±0.04871  | l/s   | 06/07/2021       | 07/2022         |
| Flow Meter<br>[DHW Flow Rate]                  | FM 605    | K48375FW                | ±0.00576  | l/s   | 05/07/2021       | 07/2022         |
| Pressure Transducer<br>[Primary Supply]        | PT 086    | K48379P                 | ±6.91   | kPa   | 05/07/2021       | 07/2022         |
| Pressure Transducer<br>[Primary Return]        | PT 085    | K48384P                 | ±8.54   | kPa   | 05/07/2021       | 07/2022         |
| Pressure Transducer<br>[DHW Output Pressure]   | PT 083    | K48380P                 | ±21.27  | kPa   | 05/07/2021       | 07/2022         |
| Pressure Transducer<br>[DHW Cold Water Supply] | PT 084    | K48383P2                | ±9.21   | kPa   | 20/07/2021       | 07/2022         |
| Pressure Transducer<br>[SH Flow]               | PT 087    | K48382P                 | ±7.10   | kPa   | 05/07/2021       | 07/2022         |
| Pressure Transducer<br>[SH Return]             | PT 088    | K48381P                 | ±15.24  | kPa   | 05/07/2021       | 07/2022         |
| PRT Probe<br>[Primary Supply Temp]             | PRT 4709  | 443851                  | ±0.6  | °C    | 10/07/2021       | 07/2022         |
| PRT Probe<br>[Primary Return Temp]             | PRT 4708  | 443851                  | ±0.6  | °C    | 10/07/2021       | 07/2022         |
| PRT Probe<br>[DHW Output Temp]                 | PRT 4711  | 443852                  | ±0.6  | °C    | 10/07/2021       | 07/2022         |
| PRT Probe<br>[Cold Water Supply Temp]          | PRT 4710  | 443852                  | ±1.91   | °C    | 10/07/2021       | 07/2022         |
| PRT Probe<br>[SH Supply Temp]                  | PRT 4707  | 443851                  | ±0.57   | °C    | 10/07/2021       | 07/2022         |
| PRT Probe<br>[SH Return Temp]                  | PRT 4706  | 443851                  | ±1.06   | °C    | 10/07/2021       | 07/2022         |

| Equipment Name                                | ID Number                                    | Calibration Certificate | Measurement Uncertainty<br>$K=2 \frac{U}{\sqrt{20}}$ | Units | Calibration Date | Calibration Due |
|---|--|-------------------------|--|-------|------------------|-----------------|
| Pressure Transducer<br>[Static Pressure Test] | PT 090                                       | U100553-19              | ±50  | kPa   | 11/2020          | 11/2022         |
| Power Meter<br>[Electrical Consumption]       | PM1022                                       | U103585-20              | ±1.03  | W     | 28/07/2021       | 09/2022         |
| Software                                      | VERSION – LabVIEW, Version 5, Service pack 1 |                         |  |       |                  |                 |

| Report<br>Issue No | Reason for Report Update |
|--------------------|--------------------------|
| 1                  | Original Issue           |



1 Malmo Road  
Sutton Fields  
Kingston upon Hull, HU7 0YF

+44 (0) 1482 877500  
[enertekinternational.com](http://enertekinternational.com)  
Registered in England No. 2262638

