

BESA HIU Test Report

Essco Controls EDGE Smart Twin

Carried out for
Essco Controls Ltd.

Report 101281/1

Compiled by Colin Judd

30 June 2020



This page is intentionally left blank

BESA HIU Test Report

Essco Controls EDGE Smart Twin

Carried out for: Essco Controls Ltd.
Unit 5 Nelson Industrial Park
Herald Road, Hedge End
Southampton
SO30 2JH
UK

Contract: Report 101281/1


Issued by: BSRIA Limited
Old Bracknell Lane West
Bracknell
Berkshire
RG12 7AH
UK

Telephone: +44 (0)1344 465600

Fax: +44 (0)1344 465626

Email: bsria@bsria.co.uk
Website: www.bsria.co.uk

QUALITY ASSURANCE

| Issue | Date | Compiled by: | Approved by: | Signature |
|-------|-------------|----------------------|------------------|---|
| Final | 30-Jun-2020 | Colin Judd | Tom Garrigan |  |
| | | Senior Test Engineer | Business Manager | |

DISCLAIMER

This Document must not be reproduced except in full without the written approval of an executive director of BSRIA. It is only intended to be used within the context described in the text.

This Document has been prepared by BSRIA Limited, with reasonable skill, care and diligence in accordance with BSRIA's Quality Assurance and within the scope of our Terms and Conditions of Business.

This Document is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the Document at its own risk.

CONTENTS

| | | |
|-------|--|----|
| 1 | INTRODUCTION | 6 |
| 2 | ITEM RECEIVED FOR TEST | 6 |
| 3 | APPROACH | 9 |
| 3.1 | Abbreviations | 9 |
| 3.2 | Instrumentation used | 10 |
| 3.3 | Uncertainty budget | 12 |
| 3.4 | Tests 1a to 1f | 12 |
| 3.5 | Tests 2a and 2b | 12 |
| 3.6 | Tests 3a and 3b | 12 |
| 3.7 | Tests 4a and 4b | 12 |
| 3.8 | Test 5a and 5b | 12 |
| 3.9 | Test set up | 13 |
| 4 | TEST RESULTS | 16 |
| 4.1 | Pressure test – 0a | 16 |
| 4.2 | Static testing – 1a, 1b, 1c, 1d, 1e and 1f | 16 |
| 4.3 | Dynamic testing of the HIU operation – 2a and 2b | 17 |
| 4.3.1 | Test 2a | 17 |
| 4.3.2 | Test 2b | 17 |
| 4.4 | Low flow DHW tests – 3a and 3b | 17 |
| 4.4.1 | Test 3a | 17 |
| 4.4.2 | Test 3b | 18 |
| 4.5 | Keep warm tests – 4a and 4b | 18 |
| 4.5.1 | Test 4a | 18 |
| 4.5.2 | Test 4b | 19 |
| 4.6 | DHW response time – 5a and 5b | 19 |
| 4.6.1 | Test 5a | 19 |
| 4.6.2 | Test 5b | 19 |
| 4.7 | Total scaling risk assessment | 20 |
| 4.8 | Volume Weighted Average Return Temperature | 20 |

FIGURES

| | | |
|-----------|--|----|
| Figure 1 | Essco Controls EDGE Smart Twin installed in the test rig | 8 |
| Figure 2 | Schematic of the test rig layout | 11 |
| Figure 3 | Results for test 1a: 1kW Space heating – DH 70°C supply | 21 |
| Figure 4 | Results for test 1b: 2kW Space heating – DH 70°C supply | 22 |
| Figure 5 | Results for test 1c: 4kW Space heating – DH 70°C supply | 23 |
| Figure 6 | Results for test 1d: 1kW Space heating – DH 60°C supply | 24 |
| Figure 7 | Results for test 1e: 2kW Space heating – DH 60°C supply | 25 |
| Figure 8 | Results for test 1f: 4kW Space heating – DH 60°C supply | 26 |
| Figure 9 | Results for test 2a: DHW dynamic test – DH 70°C supply | 27 |
| Figure 10 | Results for test 2b: DHW dynamic test – DH 60°C supply | 28 |
| Figure 11 | Results for test 3a: Low flow DHW test – DH 70°C supply | 29 |
| Figure 12 | Results for test 3b: Low flow DHW test – DH 60°C supply | 30 |
| Figure 13 | Results for test 4a: Keep warm test – DH 70°C supply | 31 |
| Figure 14 | Results for test 4b: Keep warm test – DH 60°C supply | 32 |
| Figure 15 | Results for test 5a: DHW response time – DH 70°C supply | 33 |
| Figure 16 | Results for test 5b: DHW response time – DH 60°C supply | 34 |

TABLES

| | | |
|---------|---|----|
| Table 1 | Manufacturer supplied data..... | 6 |
| Table 2 | HIU Component list | 7 |
| Table 3 | Abbreviations used..... | 9 |
| Table 4 | Instrumentation used..... | 10 |
| Table 5 | Uncertainty budget | 12 |
| Table 6 | Test setup as given in the test regime..... | 13 |
| Table 7 | Test reporting structure as given in the test regime..... | 14 |
| Table 8 | Results from the static tests..... | 16 |
| Table 9 | Total scaling risk assessment..... | 20 |

APPENDICES

| | | |
|-------------|--------------------------|----|
| APPENDIX A: | Data Charts | 21 |
| APPENDIX B: | VWART Calculations | 35 |

1 INTRODUCTION

BSRIA carried out a series of tests on one heat interface unit (HIU), the Essco Controls EDGE Smart Twin, manufactured by Essco Controls Ltd. Testing was carried out in accordance with the UK HIU Test Regime, October 2018. The test method covers testing one HIU at a primary inlet temperature of 70°C and 60°C. The HIU was a combined low temperature hot water (LTHW) and domestic hot water (DHW) unit.

This report is based on one sample of the above-mentioned product. Testing was carried out during May 2020. Charts of outputs obtained from this series of tests are shown in Appendix A of this report.

2 ITEM RECEIVED FOR TEST

The HIU received for testing was an Essco Controls Ltd. Essco Controls EDGE Smart Twin. This was a combined LTHW and DHW unit. The HIU was designed for both wet radiator systems and underfloor heating (UFH) systems. The test regime requires that the HIU is tested at two primary inlet temperatures, 70°C for wet radiator systems and 60°C for UFH systems. Table 1 gives details of the HIU tested.

Table 1 Manufacturer supplied data

| Description | Data |
|--|--|
| Model | Smart Twin HIU |
| Serial Number | ESS100010434 |
| Software version | Minibems 1.1.17 |
| Height | 670 mm |
| Width | 470 mm |
| Depth | 310 mm |
| Total unit weight (dry) | 48 kg (including cover) |
| Maximum DHW output | 46 kW based on 75°C primary flow (manufacturer supplied data) |
| Maximum central heating output | 10.5 kW based on 75°C primary flow (manufacturer supplied data) |
| Maximum primary supply temperature | 90°C |
| Recommended minimum DP | 60 kPa |
| Maximum working pressure primary side | 10 bar |
| Maximum working pressure DHW side | 10 bar |
| Safety relief valve setting secondary heating side | 4 bar |
| Expansion vessel capacity | 12 l |
| Ball valve connections | ¾" Female flat seal connection |
| Safety relief valve connection | ½" Female connection, SS discharge pipe |
| Electrical power supply voltage | 230 V AC±10% |
| Frequency | 50/60 Hz |


Table 2 gives a component list for the HIU as supplied by the Client.

Table 2 HIU Component list

| Description | Manufacturer |
|--|-------------------------------------|
| Space heating heat exchanger | SWEP E8LASW-Nx10 |
| DHW heat exchanger | SWEP E8LASW-Nx30 |
| DHW Flow sensor meter | Grundfos VFS - 98665024 |
| Check Valve on DCW inlet | Essco Controls – ESS-CV-1278 |
| Check Valve on filling circuit | Essco Controls – ESS-CV-1279 |
| Temperature sensors | Jumo - PCS_1.1503.10 |
| Primary side strainer | Essco Controls – ESS-ST-7812 |
| Controller for DHW and Space Heating | Minibems S/N M0051939N178 |
| Control valve and actuator for space heating and DHW | ESBE SLB126 - Art.432001200 |
| Heat Meter | Kamstrup S/N 67897887/ZV/19 |
| Differential pressure control valve | Frese PV Compact Valve |
| Circulation pump | Grundfos UPM3 - Art.98938540 |
| Safety valve | Pakkens |
| Air vent valves | Essco Controls – ESS-AAV-001 |
| Manometer | Essco Controls – ESS-PG-0-1 |
| Expansion Vessel | CIMM - RP Model (12 litres) |
| Space heating strainer | Essco Controls - ESS-ST-7812 |
| Pipes | Stainless Steel |
| Drain Valve | Pakkens Mini Ball Valves 0943012200 |
| Joints and connections | Essco Controls |

Figure 1 shows the Essco Controls EDGE Smart Twin installed in the test rig with the cover removed. A photograph of the name plate is also included.

Figure 1 Essco Controls EDGE Smart Twin installed in the test rig



3 APPROACH

3.1 ABBREVIATIONS

The abbreviations given in Table 3 are used throughout this report.

Table 3 Abbreviations used

| Abbreviation | Parameter | Units |
|-------------------|--|----------------------|
| DH | District Heating | - |
| SH | Space Heating | - |
| CWS | Cold Water Supply | - |
| P_1 | Heat load – primary side | [kW] |
| P_2 | Heat load – space heating system | [kW] |
| P_3 | Heat load – domestic hot water | [kW] |
| t_{10} | Temperature at DH supply upstream of 9m HIU supply pipework | [°C] |
| t_{11} | Temperature – primary side flow connection | [°C] |
| t_{12} | Temperature – primary side return connection | [°C] |
| t_{21} | Temperature – space heating system return connection | [°C] |
| t_{22} | Temperature – space heating system flow connection | [°C] |
| t_{31} | Temperature – cold water supply | [°C] |
| t_{32} | Temperature – domestic hot water flow from HIU | [°C] |
| q_1 | Volume flow – primary side | [l.s ⁻¹] |
| q_2 | Volume flow – space heating system | [l.s ⁻¹] |
| q_3 | Volume flow – domestic hot water | [l.s ⁻¹] |
| Δp_1 | Primary pressure drop across entire HIU unit | [bar] |
| Δp_2 | Pressure drop – space heating system across HIU | [bar] |
| Δp_3 | Pressure drop – domestic hot water across HIU | [bar] |
| $VWART_{DHW}$ | DHW Volume Weighted Average Return Temperature | [°C] |
| $VWART_{SH}$ | Space Heating Volume Weighted Average Return Temperature | [°C] |
| $VWART_{KWM}$ | Keep-warm Volume Weighted Average Return Temperature | [°C] |
| $VWART_{HEAT}$ | Annual Volume Weighted Average Return Temperature for Heating Period | [°C] |
| $VWART_{NONHEAT}$ | Annual Volume Weighted Average Return Temperature for Non-Heating | [°C] |
| $VWART_{HIU}$ | Total Annual Volume Weighted Return Temperature | [°C] |
| SH_{PROP} | Annual Heating Period | - |
| NSH_{PROP} | Annual Non-Space Heating Period | - |
| DH | District Heating (primary) circuit | - |
| SH | Space Heating circuit | - |
| CWS | Cold Water Supply | - |
| DHW | Domestic Hot Water | - |
| TMV | Thermostatic Mixing Valve | - |
| TRV | Temperature Regulating Valve | - |
| UFH | Under Floor Heating | - |

3.2 INSTRUMENTATION USED

Table 4 shows details of the instrumentation used for the tests.


Table 4 Instrumentation used

| Instrument | Manufacturer | Range | Units | ID No. | Calibration Due |
|---|---------------------|-----------------|-------------------|--------|-----------------|
| Keysight logging system | Keysight | N/A | N/A | 1595 | N/A |
| Static pressure transducer DHW circuit – Pressure test Primary circuit for all thermal tests | Fuji Electric | 0 – 10 | Bar | 1592 | 29-04-21 |
| Static pressure transducer SH circuit – Pressure test Secondary circuit for all thermal tests | Fuji Electric | 0 – 10 | Bar | 1593 | 29-04-21 |
| Platinum Resistance Thermometers (PRTs)* Used for measuring the inlet/outlet parameters during the testing | TC Ltd | 1 – 90 | °C | 1685 | 05-11-20 |
| Platinum Resistance Thermometer (PRT) | Anville Sensors Ltd | 1 – 90 | °C | 1685 | 05-11-20 |
| Flowmeter – DH circuit Space heating tests – (1a – 1f) | Siemens | 0 – 0.07 | l.s ⁻¹ | 2961 | 21-01-21 |
| Flowmeter – SH circuit Space heating tests – (1a – 1d) | Siemens | 0 – 0.07 | l.s ⁻¹ | 1678 | 28-04-21 |
| Flowmeter – SH circuit Space heating tests – (1f) | Danfoss | 0 – 0.2 | l.s ⁻¹ | 94 | 27-04-21 |
| Flowmeter – DH circuit Dynamic tests – (2a, 2b, 3c,3d) | Siemens | 0 – 0.5 | l.s ⁻¹ | 1545 | 27-04-21 |
| Flowmeter – DHW circuit Dynamic tests – (2a, 2b, 3c,3d) | Siemens | 0 – 0.2 | l.s ⁻¹ | 94 | 27-04-21 |
| Flowmeter – DH circuit Keep warm tests (4a & 4b) DHW response time tests (5a & 5b) | Siemens | 0 – 0.07 | l.s ⁻¹ | 2961 | 21-01-21 |
| Flowmeter – DHW circuit Keep warm tests (4a & 4b) DHW response time tests (5a & 5b) | Siemens | 0 – 0.5 | l.s ⁻¹ | 94 | 27-04-21 |
| Differential pressure transducer DH circuit for tests 1a – 1f, 2a, 2b, 3a, 3b, 4a, 4b, 5a,5b | Fuji Electric | 0 – 200 | kPa | 2065 | 15-01-21 |
| Differential pressure transducer SH and DHW circuit for tests 1a – 1f, 2a, 2b, 3a, 3b, 4a, 4b, 5a,5b | Fuji Electric | 0 – 200 | kPa | 1591 | 29-04-21 |
| Differential pressure transducer Secondary circuit tests 1a – 1f, 2a, 2b, 3a, 3b, 4a, 4b, 5a,5b | Fuji Electric | 0 – 600 | kPa | 2958 | 28-04-21 |
| Static pressure transducer Pressure test | Fuji Electric | 0 – 30 | barg | 1582 | 25-07-20 |
| Digital static pressure gauge – All thermal tests | Keller | 0 – 10 | Barg | 1760 | 09-03-21 |
| Stopwatch | Micronta | 3,601.03 | Secs | 1119 | 04-02-21 |
| Tape measure | Stanley | 1,000 | mm | 683 | 28-02-22 |
| Voltage and power draw | Yokogawa | 0-300V 0-25W | V/W | 116 | 20-08-20 |

*The time constant for these temperature sensors was ≤ 1.5 s.

The calibration certificates for all the instrumentation used during this series of tests are available on request from BSRIA (test@BSRIA.co.uk)

Figure 2 Schematic of the test rig layout



3.3 UNCERTAINTY BUDGET

The uncertainty of measurement given in the test regime is shown in Table 5.

Table 5 Uncertainty budget

| Parameter | Required Uncertainty | BSRIA Uncertainty |
|---|--|-------------------|
| Static pressure | ±10 kPa | ±0.72 kPa |
| Differential pressure, district heating | <i>Not supplied</i> | ±0.08 kPa |
| Differential pressure, domestic hot water | ±1 kPa | ±0.06 kPa |
| Differential pressure, space heating | ±1 kPa | ±0.06 kPa |
| Temperature | ±0.1°C | ±0.023°C |
| Volume flow (≥ 0.06 l/s) | ±1.5% | 0.0003 l/s |
| Volume flow (< 0.06 l/s) | To be specified in conjunction with each measurement | 0.0004 l/s |

The uncertainty of the instrumentation used was calculated according to M3003 – The Expression of Uncertainty and Confidence in Measurement. All the instrumentation used in this series of tests was within the required uncertainty quoted above.

3.4 TESTS 1A TO 1F

Once the rig was running, the space heating tests were allowed to stabilise at the required power output for the particular test. Once stable conditions had been achieved, the test was logged at a rate of 1 Hz for a minimum period of 300 seconds.

3.5 TESTS 2A AND 2B

Prior to the test being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW draw off test was carried out as per the flow regime specified in the test method. The flow rates were controlled using a manifold of three control valves set to the correct flows. The data was logged at a rate of 1 Hz.

3.6 TESTS 3A AND 3B

Prior to the tests being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW flow was reduced to 0.02 l/s as required by the test regime and logged for 180 seconds at a rate of 1 Hz.

3.7 TESTS 4A AND 4B

Prior to the test being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW flow was turned off and left for a minimum of 8 hours to establish “keep warm” conditions. During this test, the primary flow was diverted through a DN3 flowmeter so that the trickle flow could be measured. The data was logged at a rate of 1 Hz throughout the duration of the 8-hour test period.

3.8 TEST 5A AND 5B

These tests were carried out while the HIU was still in “keep warm” mode after the 8-hour keep warm test. With the data still being logged at a rate of 1 Hz, the DHW flow was immediately brought back to 0.13 l/s.

3.9 TEST SET UP

Table 6 shows the setup of the tests as given in the test regime.

Table 6 Test setup as given in the test regime

| Test No. | Test | Static pressure on return | dP across HIU | Primary flow temp | Hot water setpoint | DHW flow rate | DHW power | Space heat output | Space heat flow temp | Space heat return temp |
|---------------|---|---------------------------|-----------------|-------------------|--------------------|----------------------|----------------------|-------------------|----------------------|------------------------|
| | | bar | bar | °C | °C | l/s | kW | kW | °C | °C |
| | | | dP ₁ | t ₁₁ | t ₃₂ | q ₃ | P ₃ | P ₂ | t ₂₂ | t ₂₁ |
| Static tests | | | | | | | | | | |
| 0a | Static pressure test (same static pressure on both flow and return connections) | 1.43 times rated value | | 70 | 50 | - | - | - | n/a | n/a |
| 1a | Space Heating 1 kW | 3.0 | 0.5 | 70 | 55 | - | - | 1 | 60 | 40 |
| 1b | Space Heating 2 kW | 3.0 | 0.5 | 70 | 55 | - | - | 2 | 60 | 40 |
| 1c | Space Heating 4 kW | 3.0 | 0.5 | 70 | 55 | - | - | 4 | 60 | 40 |
| 1d | Space Heating 1 kW | 3.0 | 0.5 | 60 | 50 | - | - | 1 | 45 | 35 |
| 1e | Space Heating 2 kW | 3.0 | 0.5 | 60 | 50 | - | - | 2 | 45 | 35 |
| 1f | Space Heating 4 kW | 3.0 | 0.5 | 60 | 50 | - | - | 4 | 45 | 35 |
| Dynamic tests | | | | | | | | | | |
| 2a | DHW only DH 70°C flow | 3.0 | 0.5 | 70 | 55 | see DHW test profile | see DHW test profile | - | 60 | - |
| 2b | DHW only DH 60°C flow | 3.0 | 0.5 | 60 | 50 | | | - | 45 | - |
| 3a | Low flow DHW, DH 70°C flow | 3.0 | 0.5 | 70 | 55 | 0.02 | Record value | - | 60 | - |
| 3b | Low flow DHW, DH 60°C flow | 3.0 | 0.5 | 60 | 50 | 0.02 | Record value | - | 45 | - |
| 4a | Keep-warm, DH 70°C flow | 3.0 | 0.5 | 70 | 55 | 0 | 0 | - | 60 | - |
| 4b | Keep-warm, DH 60°C flow | 3.0 | 0.5 | 60 | 50 | 0 | 0 | - | 45 | - |
| 5a | DHW response time | 3.0 | 0.5 | 70 | 55 | 0.13 | Record value | - | 60 | - |
| 5b | DHW response time | 3.0 | 0.5 | 60 | 50 | 0.13 | Record value | - | 45 | - |

Table 7 shows the reporting structure of the tests as given in the test regime. See section 4 for the full test results.

Table 7 Test reporting structure as given in the test regime

| Test | Description | Reporting | Pass/Fail |
|----------------------|---------------------------------------|---|-----------|
| Static Tests | | | |
| 0 | Pressure tests | Pass/Fail as to whether HIU manages pressure test without leaks or damage. | Pass |
| 1a | Space Heating 1 kW, 60/40°C secondary | t ₁₁ -primary flow temperature t ₁₂ -primary return temperature. | N/A |
| 1b | Space Heating 2 kW, 60/40°C secondary | Plot of key metrics over duration of test. | N/A |
| 1c | Space Heating 4 kW, 60/40°C secondary | Note: Outputs used as input data to 'High Temperature' Space Heating Volume Weighted Average Return Temperature calculation. | N/A |
| 1d | Space Heating 1 kW, 45/35°C secondary | t ₁₁ -primary flow temperature t ₁₂ -primary return temperature | N/A |
| 1e | Space Heating 2 kW, 45/35°C secondary | Plot of key metrics over duration of test. | N/A |
| 1f | Space Heating 4 kW, 45/35°C secondary | Note: Outputs used as input data to 'Low Temperature' Space Heating Volume Weighted Average Return Temperature calculation. | N/A |
| Dynamic Tests | | | |
| 2a | DHW only, DH 70°C flow; 55°C DHW | Pass/Fail on DHW (at t ₃₂) exceeding 65.0°C (to 1 decimal point) for more than 10 consecutive seconds. State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Assessment of scaling risk as per criteria detailed in 2.26. Note: Outputs used as input data to 'High Temperature' Domestic Hot Water Weighted Average Return Temperature calculation. Plot t ₃₂ , t ₃₁ , q ₃ , t ₁₂ q ₁ | Pass |
| 2b | DHW only, DH 60°C flow; 50°C DHW | State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Plot t ₃₂ , t ₃₁ , q ₃ , t ₁₂ q ₁ Note: Outputs used as input data to 'Low Temperature' Domestic Hot Water Weighted Average Return Temperature calculation. | N/A |
| 3c | Low flow DHW, DH 70°C flow; 55°C DHW | Pass/Fail on DHW (at t ₃₂) exceeding 65.0°C (1 decimal place) for more than 10 consecutive seconds. Comment on ability to deliver DHW at low flow based on DHW temperature reaching at least 45.0°C (1 decimal place) at the end of the 180 second period of low flow DHW. Comment on ability to deliver stable DHW flow temperature (at t ₃₂), defined as ability to maintain 55.0 +/-3.0°C (1 decimal place) during the last 60 seconds of the test. Maximum temperature achieved and +/-°C variance around 55.0°C (1 decimal place) to be stated. Assessment of scaling risk as per criteria detailed in 2.26. Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow. | Pass |

| Test | Description | Reporting | Pass/Fail |
|------|---|---|-----------|
| 3d | Low flow DHW, DH 60°C flow; 50°C DHW | <p>Comment on ability to deliver DHW at low flow rate based on DHW temperature reaching at least 45.0°C (one decimal place) at the end of the 180 second period of low flow DHW.</p> <p>Comment on ability to deliver stable DHW flow temperature (at t_{32}), defined as ability to maintain 50.0 +/- 3°C (1 decimal place) during the last 60 seconds of the test. Maximum temperature achieved and +/- °C variance around 50.0°C (1 decimal place) to be stated.</p> <p>Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.</p> <p>Maximum temperature achieved and +/- °C variance around 50.0°C (1 decimal place) to be stated.</p> | N/A |
| 4a | Keep-warm, DH 70°C flow; 55°C DHW | <p>Assessment of whether valid keep-warm operation, based on 5a response time criteria: Pass / Fail.</p> <p>Observation on the operation of the HIU during keep-warm.</p> <p>Assessment of scaling risk, based on duration of temperatures in excess of 55.0°C (one decimal place). Plot temperature t_{10}.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Plot of key metrics over duration of test.</p> <p>State average heat load for the duration of the test.</p> <p>State average primary flowrate for the duration of the test.</p> <p>Note: Outputs used as input data to 'High Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p> | Pass |
| 4b | Keep-warm, DH 60°C flow; 50°C DHW | <p>Assessment of whether valid keep-warm operation, based on 5b response time criteria: Pass / Fail.</p> <p>Observation on the operation of the HIU during keep-warm.</p> <p>Assessment of scaling risk, based on duration of temperatures in excess of 55.0°C (one decimal place).</p> <p>Plot temperature t_{10}.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Plot of key metrics over duration of test.</p> <p>State average heat load for the duration of the test.</p> <p>State average primary flowrate for the duration of the test.</p> <p>Note: Outputs used as input data to 'Low Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p> | Pass |
| 5a | DHW response time, DH 70°C flow; 55°C DHW | <p>Pass/Fail on DHW (at t_{32}) exceeding 65.0°C (1 decimal place) for more than 10 consecutive seconds. State time to achieve a DHW temperature 45.0°C (1 decimal place) and not subsequently drop below 42.0°C (1 decimal place).'</p> <p>Plot t_{32}, t_{31}, q_3, t_{12}, q_1 over duration of test.</p> | Pass |
| 5b | DHW response time, DH 60°C flow; 50°C DHW | <p>Pass/Fail on DHW (at t_{32}). State time to achieve a DHW temperature 45.0°C (1 decimal place) and not subsequently drop below 42.0°C (1 decimal place).</p> <p>Plot t_{32}, t_{31}, q_3, t_{12}, q_1 over duration of test.</p> | Pass |

4 TEST RESULTS

During all of the tests, the ambient temperature within the vicinity of the HIU being tested was within the tolerance of $20^{\circ}\text{C} \pm 5^{\circ}\text{C}$ as specified in the test regime. Charts of the key metrics for the thermal tests are given in Appendix A.

4.1 PRESSURE TEST – 0A

The DHW circuit and the space heating circuit were pressurised to 1.5 bar. The primary circuit was pressurised to 1.43 times the rated maximum static pressure of 10 bar (test pressure 14.30bar). This pressure was held for 30 minutes. After the 30-minute test period, the connections and fittings on the HIU were inspected for leaks and any signs of deformation. During the 30-minute period, there were no leaks or signs of deformation.

Result – Pass.

4.2 STATIC TESTING – 1A, 1B, 1C, 1D, 1E AND 1F

The following tests were carried out on the space heating circuit:

- 1a – DH inlet 70°C , heating return at 40°C and a flow set to achieve 1kW heating duty
- 1b – DH inlet 70°C , heating return at 40°C and a flow set to achieve 2kW heating duty
- 1c – DH inlet 70°C , heating return at 40°C and a flow set to achieve 4kW heating duty
- 1d – DH inlet 60°C , heating return at 35°C and a flow set to achieve 1kW heating duty
- 1e – DH inlet 60°C , heating return at 35°C and a flow set to achieve 2kW heating duty
- 1f – DH inlet 60°C , heating return at 35°C and a flow set to achieve 4kW heating duty

For tests 1a to 1c, the space heating outlet temperature was set to achieve $60^{\circ}\text{C} (\pm 0.5^{\circ}\text{C})$ during the 4kw test. For tests 1d to 1f, the space heating outlet temperature was set to achieve $45^{\circ}\text{C} (\pm 0.5^{\circ}\text{C})$ during the 4kw test. Table 8 shows a summary of the results for the static tests.

Table 8 Results from the static tests

| Test | District Heating Circuit | | | | | Space Heating Circuit | | | |
|---------------------------|------------------------------------|------------------------------------|----------------|-----------------------|---------------|------------------------------------|------------------------------------|----------------|---------------|
| | t_{11} ($^{\circ}\text{C}$) | t_{12} ($^{\circ}\text{C}$) | q_1 (l/s) | Δp_1 (kPa) | P_1 (kW) | T_{21} ($^{\circ}\text{C}$) | T_{22} ($^{\circ}\text{C}$) | q_2 (l/s) | P_2 (kW) |
| 1a | 70.00 | 42.79 | 0.010 | 50.85 | 1.13 | 39.89 | 61.60 | 0.011 | 0.98 |
| 1b | 69.86 | 43.27 | 0.017 | 51.27 | 1.87 | 40.10 | 59.69 | 0.023 | 1.85 |
| 1c | 70.00 | 45.37 | 0.039 | 51.25 | 3.98 | 39.87 | 59.80 | 0.048 | 3.93 |
| 1d | 60.19 | 35.52 | 0.010 | 50.21 | 1.03 | 35.17 | 45.06 | 0.025 | 1.02 |
| 1e | 60.28 | 36.32 | 0.022 | 50.95 | 2.19 | 35.26 | 45.45 | 0.050 | 2.11 |
| 1f | 60.15 | 36.75 | 0.039 | 51.63 | 3.79 | 35.18 | 44.59 | 0.097 | 3.78 |
| Uncertainty for all tests | ± 0.023 | ± 0.018 | ± 0.0006 | 0.08 | ± 0.066 | ± 0.018 | ± 0.020 | ± 0.0002 | ± 0.015 |

4.3 DYNAMIC TESTING OF THE HIU OPERATION – 2A AND 2B

4.3.1 Test 2a

Test 2a was carried out with the DH water temperature set to 70°C and the cold-water supply to the DHW circuit at 10°C. The DHW outlet temperature in the HIU control software was set to achieve 55.0°C ($\pm 0.5^\circ\text{C}$) at a DHW flow rate of 0.130 l/s, prior to the test.

During test 2a:

- The DHW temperature did not exceed 65°C at any point during the test
- The maximum DHW temperature was 63.5°C
- The minimum DHW temperature was 46.5°C
- Details of the scaling risk are given in Table 9

Result – Pass

4.3.2 Test 2b

Test 2b was carried out with the DH water temperature set to 60°C and the cold-water supply to the DHW circuit at 10°C. The DHW outlet temperature in the HIU control software was set to achieve 50.0°C ($\pm 0.5^\circ\text{C}$) at a DHW flow rate of 0.130 l/s, prior to the test.

During test 2b:

- The maximum DHW temperature was 56.6°C
- The minimum DHW temperature was 44.1°C

Result – There is no pass/fail criteria for this test.

4.4 LOW FLOW DHW TESTS – 3A AND 3B

4.4.1 Test 3a

Test 3a was carried out with the DH water temperature set to 70°C and the cold water supply to the DHW circuit at 10°C. The DHW outlet temperature setpoint remained at the same position, set to achieve 55.0 ($\pm 0.5^\circ\text{C}$) at a DHW flow rate of 0.130 l/s. The low DHW flow rate was set to 0.02 l/s as required by the test regime.

During test 3a:

- The DHW temperature did not exceed 65°C at any point during the test
- The HIU was able to deliver DHW above 45°C at the end of the 180 second test
- During the last 60 seconds of the test the DHW temperature averaged 57.6°C and ranged from 57.0°C to 57.6°C. The results were within the stated tolerance of 55.0°C $\pm 3^\circ\text{C}$ during this time period.
- The DHW maximum and minimum outlet temperatures were 63.4°C and 54.9°C respectively during the 180 second test.
- Details of the scaling risk are given in Table 9

Result – Pass

4.4.2 Test 3b

Test 3b was carried out with the DH water temperature set to 60°C and the cold water supply to the DHW circuit at 10°C. The DHW outlet temperature setpoint remained at the same position, set to achieve 50.0 (±0.5°C) at a DHW flow rate of 0.130 l/s. The low DHW flow rate was set to 0.02 l/s as required by the test regime.

During test 3b:

- The HIU was able to deliver DHW above 45°C at the end of the 180 second test
- During the last 60 seconds of the test the DHW temperature averaged 51.4°C and ranged from 52.5°C to 50.5°C. The results were within the stated tolerance of 50.0°C ±3°C during this time period.
- The DHW maximum and minimum outlet temperatures were 56.4°C and 49.8°C respectively during the 180 second test.

Result – There is no pass/fail criteria for this test.

4.5 KEEP WARM TESTS – 4A AND 4B

The keep warm function was a pulsed flow on the DH circuit as can be seen on the charts in Appendix A.

4.5.1 Test 4a

Test 4a was carried out with the DH water temperature set to 70°C and the cold water supply to the DHW circuit at 10°C. The DHW outlet temperature setpoint remained at the same position, set to achieve 55.0 (±0.5°C) at a DHW flow rate of 0.130 l/s.

Based on the results for the DHW response time during test 5a, the HIU does perform a valid keep warm operation.

Once the keep warm function had stabilised (approximately 10,000 seconds into the test), the average t_{11} temperature for the remainder of the test (18,800 seconds) was 49.9°C varying between 51.3°C and 49.1°C. The average t_{12} temperature during this same period was 41.9°C varying between 42.4°C and 41.3°C.

During test 4a:

- The average heat load during the 8-hour keep warm period was 46 W
- The average primary flow rate during the 8-hour keep warm period was 4.3 l/h
- The average measured voltage was 243V
- The average measured electrical power draw was 14.8W
- Details of the scaling risk are given in Table 9

4.5.2 Test 4b

Test 4b was carried out with the DH water temperature set to 60°C and the cold water supply to the DHW circuit at 10°C. The DHW outlet temperature setpoint remained at the same position, set to achieve 50.0 (±0.5°C) at a DHW flow rate of 0.130 l/s.

Based on the results for the DHW response time during test 5b, the HIU does perform a valid keep warm operation.

Once the keep warm function had stabilised (approximately 8,000 seconds into the test), the average t_{11} temperature for the remainder of the test 20,800 seconds) was 47.9°C varying between 48.9°C and 47.4°C. The average t_{12} temperature during this period was 42.5°C varying between 43.1°C and 41.8°C.

- The average heat load during the 8-hour keep warm period was 45 W
- The average primary flow rate during the 8-hour keep warm period was 6.2 l/h
- The average measured voltage was 231V
- Details of the scaling risk are given in Table 9

4.6 DHW RESPONSE TIME – 5A AND 5B

4.6.1 Test 5a

Test 5a was carried out immediately after test 4a with all the settings and conditions the same.

During test 5a:

- The DHW temperature did not exceed 65.0°C during the test
- The DHW achieved 45.0°C in 6 seconds from the first recorded non-zero DHW flow reading
- The DHW temperature did not subsequently drop below 42.0°C

Not exceeding 65.0°C during the test – Pass

Achieving 45°C DHW within 15 seconds – Pass

DHW temperature not subsequently dropping below 42.0°C – Pass

Overall result – Pass

4.6.2 Test 5b

Test 5b was carried out immediately after test 4b with all the settings and conditions the same.

During test 5b:

- The DHW achieved 45.0°C in 9 seconds from the first recorded non-zero DHW flow reading
- The DHW temperature did not subsequently drop below 42.0°C

Achieving 45°C DHW within 15 seconds – Pass

DHW temperature not subsequently dropping below 42.0°C – Pass

Overall result – Pass

4.7 TOTAL SCALING RISK ASSESSMENT

The scaling risk criteria is given in section 2.26 of the test regime. Table 9 gives details of the scaling risk associated with this HIU. If any of the factors given in Table 9 occur, then there is an increased scaling risk of the DHW plate in hard water areas.

Table 9 Total scaling risk assessment

| Has the HIU got a TMV or TRV on the output of the DHW plate heat exchanger? | No | |
|---|------------|------------|
| | Test | |
| | 2a | 3a |
| t ₃₂ above 60°C for more than 5 seconds | Yes | Yes |
| t ₁₂ exceeds 55°C at any point of the test | No | No |
| | 4a | 4b |
| t ₁₂ exceeds 50°C at any time | No | No |

4.8 VOLUME WEIGHTED AVERAGE RETURN TEMPERATURE

The Volume Weighted Average Return Temperature (VWART) results are given in Appendix B.

APPENDIX A: DATA CHARTS

Figure 3 Results for test 1a: 1kW Space heating – DH 70°C supply




Figure 4 Results for test 1b: 2kW Space heating – DH 70°C supply




Figure 5 Results for test 1c: 4kW Space heating – DH 70°C supply




Figure 6 Results for test 1d: 1kW Space heating – DH 60°C supply




Figure 7 Results for test 1e: 2kW Space heating – DH 60°C supply




Figure 8 Results for test 1f: 4kW Space heating – DH 60°C supply




Figure 9 Results for test 2a: DHW dynamic test – DH 70°C supply




Figure 10 Results for test 2b: DHW dynamic test – DH 60°C supply




Figure 11 Results for test 3a: Low flow DHW test – DH 70°C supply




Figure 12 Results for test 3b: Low flow DHW test – DH 60°C supply




Figure 13 Results for test 4a: Keep warm test – DH 70°C supply




Figure 14 Results for test 4b: Keep warm test – DH 60°C supply




Figure 15 Results for test 5a: DHW response time – DH 70°C supply





Figure 16 Results for test 5b: DHW response time – DH 60°C supply



APPENDIX B: VWART CALCULATIONS

High Temperature VWART Calculations



High Temperature VWART Calculation for Essco Controls Ltd. HIU

Primary flow temperature = 70°C, DHW set point = 55°C, Space heating temperatures = 40°C/60°C

Test carried out by BSRIA Ltd. in May 2020, Test Reference 101281/1

Manufacturer: Essco Controls Ltd.; Model: Smart Twin; Serial number: ESS100010434; Year of manufacture: 2019

VWART calculation prepared by Colin Judd of BSRIA Ltd. on 27 May 2020

| | VWART (°C) | Volume (m ³) |
|---------------|------------|--------------------------|
| DHW | 22 | 27.2 |
| Keep warm | 41 | 34.1 |
| Space heating | 44 | 49.6 |

| | VWART with keep warm active | |
|------------|-----------------------------|--------|
| Period | VWART (°C) | % Time |
| No heating | 33 | 92% |
| Heating | 43 | 8% |
| Overall | 33 | |

| | DHW draw test results | | | Post DHW draw (60 seconds) | |
|--------|-----------------------|-----------------------------------|------------------|-----------------------------------|------------------|
| | Power (W) | Primary flow (m ³ /hr) | Return temp (°C) | Primary flow (m ³ /hr) | Return temp (°C) |
| Low | 11823 | 0.196 | 21.4 | 0.010 | 17.97 |
| Medium | 18807 | 0.340 | 21.8 | 0.025 | 22.18 |
| High | 24319 | 0.445 | 23.2 | 0.031 | 24.05 |

| DHW draw volumes per annum | | |
|----------------------------|--------------|--------------------------|
| Energy (kWh) | Time (hours) | Volume (m ³) |
| 729 | 61.66 | 12.110 |
| 297 | 15.79 | 5.376 |
| 444 | 18.26 | 8.121 |

| Post DHW draw volumes per annum | | |
|---------------------------------|------------------------|--------------------------|
| Events | Avg duration (seconds) | Volume (m ³) |
| 10000 | 30 | 0.870 |
| 660 | 75 | 0.342 |
| 300 | 145 | 0.370 |

| Keep warm test results | |
|-----------------------------------|------------------|
| Primary flow (m ³ /hr) | Return temp (°C) |
| 0.0043 | 41.2 |

| Keep warm volumes per annum | |
|-----------------------------|--------------------------|
| Time (hours) | Volume (m ³) |
| 8007 | 34.111 |

| | Space heating test results | | |
|------|----------------------------|-----------------------------------|------------------|
| | Power (W) | Primary flow (m ³ /hr) | Return temp (°C) |
| 1 kW | 998 | 0.036 | 42.8 |
| 2 kW | 1883 | 0.063 | 43.3 |
| 4 kW | 4001 | 0.140 | 45.4 |

| Space heating volumes per annum | | |
|---------------------------------|--------------|--------------------------|
| Energy (kWh) | Time (hours) | Volume (m ³) |
| 98 | 98.20 | 3.516 |
| 787 | 417.95 | 26.279 |
| 565 | 141.23 | 19.829 |

Low Temperature VWARD Calculations

**Low Temperature VWARD Calculation for Essco Controls Ltd. HIU**

Primary flow temperature = 60°C, DHW set point = 50°C, Space heating temperatures = 35°C/45°C

Test carried out by BSRIA Ltd. in May 2020, Test Reference 101281/1

Manufacturer: Essco Controls Ltd.; Model: Smart Twin; Serial number: ESS100010434; Year of manufacture: 2019

VWARD calculation prepared by Colin Judd of BSRIA Ltd. on 27 May 2020

| | VWARD (°C) | Volume (m ³) |
|----------------------|------------|--------------------------|
| DHW | 24 | 35.6 |
| Keep warm | 42 | 49.7 |
| Space heating | 36 | 53.5 |

| | VWARD with keep warm active | |
|-------------------|-----------------------------|--------|
| Period | VWARD (°C) | % Time |
| No heating | 34 | 93% |
| Heating | 36 | 7% |
| Overall | 34 | |

| | DHW draw test results | | | Post DHW draw (60 seconds) | |
|--------|-----------------------|-----------------------------------|------------------|-----------------------------------|------------------|
| | Power (W) | Primary flow (m ³ /hr) | Return temp (°C) | Primary flow (m ³ /hr) | Return temp (°C) |
| Low | 10352 | 0.229 | 23.4 | 0.016 | 19.61 |
| Medium | 16431 | 0.383 | 23.0 | 0.029 | 22.93 |
| High | 21333 | 0.510 | 24.5 | 0.024 | 24.95 |

| DHW draw volumes per annum | | |
|----------------------------|--------------|--------------------------|
| Energy (kWh) | Time (hours) | Volume (m ³) |
| 729 | 70.42 | 16.099 |
| 297 | 18.08 | 6.926 |
| 444 | 20.81 | 10.623 |

| Post DHW draw volumes per annum | | |
|---------------------------------|------------------------|--------------------------|
| Events | Avg duration (seconds) | Volume (m ³) |
| 10000 | 30 | 1.310 |
| 660 | 75 | 0.392 |
| 300 | 145 | 0.291 |

| Keep warm test results | |
|-----------------------------------|------------------|
| Primary flow (m ³ /hr) | Return temp (°C) |
| 0.0062 | 42.1 |

| Keep warm volumes per annum | |
|-----------------------------|--------------------------|
| Time (hours) | Volume (m ³) |
| 8038 | 49.723 |

| | Space heating test results | | |
|------|----------------------------|-----------------------------------|------------------|
| | Power (W) | Primary flow (m ³ /hr) | Return temp (°C) |
| 1 kW | 1033 | 0.036 | 35.5 |
| 2 kW | 2128 | 0.079 | 36.3 |
| 4 kW | 3820 | 0.140 | 36.7 |

| Space heating volumes per annum | | |
|---------------------------------|--------------|--------------------------|
| Energy (kWh) | Time (hours) | Volume (m ³) |
| 98 | 94.86 | 3.415 |
| 787 | 369.81 | 29.289 |
| 565 | 147.89 | 20.767 |