

# BESA HIU Test Report

## Compact VX1-1

Carried out for  
Heat Products Ltd

Report 61539/1

Compiled by Colin Judd

2 April 2019



This page is intentionally left blank

# BESA HIU Test Report

## Compact VX1-1

Carried out for: Heat Products Ltd  
40 South Hampshire Industrial Estate  
Brunel Road  
Totton, Hampshire  
SO40 3SA  
UK

Contract: Report 61539/1

Issued by: BSRIA Limited  
Old Bracknell Lane West  
Bracknell  
Berkshire  
RG12 7AH  
UK


Telephone: +44 (0)1344 465600

Fax: +44 (0)1344 465626

Email: [bsria@bsria.co.uk](mailto:bsria@bsria.co.uk)

Website: [www.bsria.co.uk](http://www.bsria.co.uk)

## QUALITY ASSURANCE

Issue	Date	Compiled by:	Approved by:	Signature
Final	27-Jan-2020	Colin Judd	Tom Garrigan	
		Senior Test Engineer	Business Manager	

## DISCLAIMER

*This Document must not be reproduced except in full without the written approval of an executive director of BSRIA. It is only intended to be used within the context described in the text.*

*This Document has been prepared by BSRIA Limited, with reasonable skill, care and diligence in accordance with BSRIA's Quality Assurance and within the scope of our Terms and Conditions of Business.*

*This Document is confidential to the client and we accept no responsibility of whatsoever nature to third parties to whom this report, or any part thereof, is made known. Any such party relies on the Document at its own risk.*

## CONTENTS

1	INTRODUCTION .....	6
2	ITEM RECEIVED FOR TEST .....	6
3	APPROACH .....	9
3.1	Abbreviations .....	9
3.2	Instrumentation used .....	10
3.3	Uncertainty budget .....	12
3.4	Tests 1a to 1f .....	12
3.5	Tests 2a and 2b.....	12
3.6	Tests 3a and 3b.....	12
3.7	Tests 4a and 4b.....	12
3.8	Test 5a and 5b .....	12
3.9	Test set up .....	13
4	TEST RESULTS.....	16
4.1	Pressure test – 0a .....	16
4.2	Static testing – 1a, 1b, 1c, 1d, 1e and 1f.....	16
4.3	Dynamic testing of the HIU operation – 2a and 2b .....	17
4.3.1	Test 2a .....	17
4.3.2	Test 2b .....	17
4.4	Low flow DHW test – 3a and 3b .....	17
4.4.1	Test 3a .....	17
4.4.2	Test 3b .....	18
4.5	Keep warm tests – 4a and 4b .....	18
4.5.1	Test 4a .....	18
4.5.2	Test 4b .....	18
4.6	DHW response time – 5a and 5b.....	19
4.6.1	Test 5a .....	19
4.6.2	Test 5b .....	19
4.7	Total scaling risk assessment.....	19
4.8	Volume Weighted Average Return Temperature .....	19

## FIGURES

Figure 1	Compact VX1-1 HIU installed in the test rig .....	8
Figure 2	Schematic of the test rig layout. ....	11
Figure 3	Results for test 1a: 1kW Space heating – DH 70°C supply .....	20
Figure 4	Results for test 1b: 2kW Space heating – DH 70°C supply .....	21
Figure 5	Results for test 1c: 4kW Space heating – DH 70°C supply .....	22
Figure 6	Results for test 1d: 1kW Space heating – DH 60°C supply .....	23
Figure 7	Results for test 1e: 2kW Space heating – DH 60°C supply .....	24
Figure 8	Results for test 1f: 4kW Space heating – DH 60°C supply .....	25
Figure 9	Results for test 2a: DHW dynamic test – DH 70°C .....	26
Figure 10	Results for test 2b: DHW dynamic test – DH 60°C .....	27
Figure 11	Results for test 3a: Low flow DHW test – DH 70°C.....	28
Figure 12	Results for test 3b: Low flow DHW test – DH 60°C .....	29
Figure 13	Results for point 4a: Keep warm test – DH 70°C supply .....	30
Figure 14	Results for point 4b: Keep warm test – DH 60°C supply .....	31
Figure 15	Results for test 5a: DHW response time – DH 70°C supply.....	32
Figure 16	Results for test 5b: DHW response time – DH 60°C supply .....	33

## TABLES

Table 1	Manufacturer supplied data.....	6
Table 2	HIU Component list .....	7
Table 3	Abbreviations used.....	9
Table 4	Instrumentation used.....	10
Table 5	Test setup as given in the test regime.....	13
Table 6	Test reporting structure as given in the test regime.....	14
Table 7	Results from the static tests.....	16
Table 8	Total scaling risk assessment.....	19

## APPENDICES

APPENDIX A:	Data Charts .....	20
APPENDIX B:	VWART calculations.....	34

## 1 INTRODUCTION

BSRIA carried out a series of tests on one Heat Interface Unit (HIU), the Compact VX1-1 HIU, manufactured by Heat Products Ltd. Testing was carried out in accordance with the UK HIU Test Regime, October 2018. The test method covers testing one HIU at a primary inlet temperature of 70°C and 60°C. The HIU was a combined low temperature hot water (LTHW) and domestic hot water (DHW) unit.

This report is based on one sample of the above-mentioned product. Testing was carried out during March 2019. Charts of outputs obtained from this series of tests are shown in Appendix A of this report.

## 2 ITEM RECEIVED FOR TEST

The HIU received for testing was a Heat Products Ltd Compact VX1-1. This was a combined LTHW and DHW unit. The HIU was designed for both wet radiator systems and underfloor heating (UFH) systems. The test regime requires that the HIU is tested at two primary inlet temperatures, 70°C for wet radiator systems and 60°C for UFH systems. Table 1 gives details of the HIU tested.

**Table 1 Manufacturer supplied data**

Description	Data
Model	Compact VX1-1
Serial Number	1901271
Height	745 mm
Width	530 mm
Depth	360 mm
Total unit weight	36 kg (including cover)
Maximum DHW output	35 kW (manufacturer supplied data)
Maximum central heating output	5 kW (manufacturer supplied data)
Maximum primary supply temperature	90°C
Recommended minimum DP	60 kPa
Maximum working pressure primary side	16 bar
Maximum working pressure DHW side	6 bar
Safety relief valve setting secondary heating side	2.5 bar
Expansion vessel capacity	8 litres
Ball valve connections	¾"
Safety relief valve connection	¾"
Electrical power supply voltage	230 V
Frequency	50 Hz

Table 2 gives a component list for the HIU as supplied by the Client. All necessary documentation was supplied with the HIU.

**Table 2 HIU Component list**

Description	Manufacturer
Circulating pump	Lowara ecocirc M 15-6/130
Control valve for DHW	Danfoss IHPT kvs 2.4
Thermostatic control for space heating	Danfoss RAVK 35-75C
Space heating valve	Danfoss VMA 15 kvs 1.6
Space heating zone valve	Danfoss Thermal actuator TWA-Z
Differential pressure control valve	Danfoss ABPM 15
DHW isolating valve	Altecnic AL085805R 3/4"
DHW heat exchanger	Danfoss XBO6H-1 26
Drain valves	Pintossi 0035000014
Expansion vessel	CIMM 8L 950820
Gaskets	Thoenes BA1100180024201
Heat meter	Danfoss Sonometer 1100/Sharky 775
Joints and connections	Nut & gasket. Flat face
Manometer	Modus B101A144B
Pipes	Stainless steel 316 19mm
Primary side strainer	Pintossi 3/4" 60 mesh
Safety valve	Pintossi 0057301525
Space heating heat exchanger	Danfoss XBO6H-1 16
Space heating strainer	Pintossi 3/4" 60 mesh
Temperature sensors	Integrated in IHPT

Figure 1 shows the Compact VX1-1 HIU installed in the test rig with the cover removed. A photograph of the name plate is also included.

**Figure 1 Compact VX1-1 HIU installed in the test rig**





### 3 APPROACH

#### 3.1 ABBREVIATIONS

The abbreviations given in Table 3 are used throughout this report.

**Table 3 Abbreviations used**

Abbreviation	Parameter	Units
DH	District Heating	
SH	Space Heating	
CWS	Cold Water Supply	
$P_1$	Heat load – primary side	[kW]
$P_2$	Heat load – space heating system	[kW]
$P_3$	Heat load – domestic hot water	[kW]
$t_{10}$	Temperature at DH supply upstream of 9m HIU supply pipework	[°C]
$t_{11}$	Temperature – primary side flow connection	[°C]
$t_{12}$	Temperature – primary side return connection	[°C]
$t_{21}$	Temperature – space heating system return connection	[°C]
$t_{22}$	Temperature – space heating system flow connection	[°C]
$t_{31}$	Temperature – cold water supply	[°C]
$t_{32}$	Temperature – domestic hot water flow from HIU	[°C]
$q_1$	Volume flow – primary side	[l.s <sup>-1</sup> ]
$q_2$	Volume flow – space heating system	[l.s <sup>-1</sup> ]
$q_3$	Volume flow – domestic hot water	[l.s <sup>-1</sup> ]
$\Delta p_1$	Primary pressure drop across entire HIU unit	[bar]
$\Delta p_2$	Pressure drop – space heating system across HIU	[bar]
$\Delta p_3$	Pressure drop – domestic hot water across HIU	[bar]
$VWART_{DHW}$	DHW Volume Weighted Average Return Temperature	[°C]
$VWART_{SH}$	Space Heating Volume Weighted Average Return Temperature	[°C]
$VWART_{KWM}$	Keep-warm Volume Weighted Average Return Temperature	[°C]
$VWART_{HEAT}$	Annual Volume Weighted Average Return Temperature for Heating Period	[°C]
$VWART_{NONHEAT}$	Annual Volume Weighted Average Return Temperature for Non-Heating	[°C]
$VWART_{HIU}$	Total Annual Volume Weighted Return Temperature	[°C]
$SH_{PROP}$	Annual Heating Period	-
$NSH_{PROP}$	Annual Non-Space Heating Period	-
DH	District Heating (primary) circuit	
SH	Space Heating circuit	
CWS	Cold Water Supply	
DHW	Domestic Hot Water	-
TMV	Thermostatic Mixing Valve	-
TRV	Temperature Regulating Valve	-
UFH	Under Floor Heating	-

### 3.2 INSTRUMENTATION USED

Table 4 shows details of the instrumentation used for the tests.

**Table 4 Instrumentation used**


Instrument	Manufacturer	Range	Units	ID No.	Calibration Due
Keysight logging system	Keysight	N/A	N/A	1595	N/A
Platinum Resistance Thermometers (PRTs)	Anville Sensors Ltd	-10 – 95	°C	1596	01-06-19
Static pressure transducer Primary circuit for all tests	Fuji Electric	0 – 10	Bar	1592	26-06-19
Static pressure transducer Secondary circuit for all tests	Fuji Electric	0 – 10	Bar	1593	25-06-19
ET7026 logging system	IPC	-	-	1685	N/A
Platinum Resistance Thermometers (PRTs)* Used for measuring the inlet/outlet parameters during the testing	TC Ltd	1 – 90	°C	1685	05-11-19
Platinum Resistance Thermometer (PRT)	Anville Sensors Ltd	1 – 90	°C	1685	05-11-19
Flowmeter – DH circuit Space heating tests – (1a – 1f)	Siemens	0 – 0.07	l.s-1	1678	28-06-19
Flowmeter – SH circuit Space heating tests – (1a – 1e)	Siemens	0 – 0.07	l.s-1	2961	09-01-20
Flowmeter – SH circuit Space heating tests – (1f)	Siemens	0 – 0.5	l.s-1	1544	13-06-19
Flowmeter – Primary circuit Dynamic tests – (2a, 2b, 3a,3b) DHW response time tests – (5a,5b)	Siemens	0 – 0.5	l.s-1	1544	13-06-19
Flowmeter – Secondary circuit Dynamic tests – (2a, 2b, 3a,3b) DHW response time tests – (5a,5b)	Siemens	0 – 0.5	l.s-1	2063	13-03-20
Flowmeter – Primary circuit Keep warm tests (4a, 4b)	Siemens	0 – 0.07	l.s-1	1678	28-06-19
Flowmeter – Secondary circuit Keep warm tests (4a, 4b)	Siemens	0 – 0.5	l.s-1	2063	13-03-20
Differential pressure transducer Primary circuit for all tests	Fuji Electric	0 – 200	kPa	2065	07-01-20
Differential pressure transducer Secondary circuit for all tests	Fuji Electric	0 – 200	kPa	1591	22-06-19
Digital pressure gauge	Keller	0 – 30	barg	202437	08-01-20
Stopwatch	RS	3,603.02	Secs	183	29-08-19
Tape measure	Stanley	1,000	mm	683	28-02-22

\*The time constant for these temperature sensors was  $\leq 1.5$  s.

The calibration certificates for all the instrumentation used during this series of tests are available on request from BSRIA (test@BSRIA.co.uk).

Figure 2 shows a schematic of the test rig layout.

**Figure 2 Schematic of the test rig layout.**



### 3.3 UNCERTAINTY BUDGET

The uncertainty of measurement given in the test regime is as follows:

Parameter	Required Uncertainty	BSRIA Uncertainty
Static pressure	±10 kPa	±0.65 kPa
Differential pressure, district heating	<i>Not supplied</i>	±0.06 kPa
Differential pressure, domestic hot water	±1 kPa	±0.06 kPa
Differential pressure, space heating	±1 kPa	±0.06 kPa
Temperature	±0.1°C	±0.02°C
Volume flow (≥ 0.06 l/s)	±1.5%	0.0012 l/s
Volume flow (< 0.06 l/s)	To be specified in conjunction with each measurement	0.0006 l/s

The uncertainty of the instrumentation used was calculated according to M3003 – The Expression of Uncertainty and Confidence in Measurement. All the instrumentation used in this series of tests was within the required uncertainty quoted above.

### 3.4 TESTS 1A TO 1F

Once the rig was running, the space heating tests were allowed to stabilise at the required power output for the particular test. Once stable conditions had been achieved, the test was logged at a rate of 1 Hz (i.e. 1 second) for a minimum period of 300 seconds.

### 3.5 TESTS 2A AND 2B

Prior to the test being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW draw off test was carried out as per the flow regime specified in the test method. The flow rates were controlled using a manifold of three control valves set to the correct flows. The data was logged at a rate of 1 Hz.

### 3.6 TESTS 3A AND 3B

Prior to the test being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW flow was reduced to 0.02 l/s and logged for 180 seconds at a rate of 1 Hz.

### 3.7 TESTS 4A AND 4B

Prior to the test being carried out, the rig was running at the required stable conditions for a minimum of 120 seconds. After this period, the DHW flow was turned off and left for a minimum of 8 hours to establish “keep warm” conditions. During this test, the primary flow was diverted through a DN3 flowmeter so that the trickle flow could be measured. The data was logged at a rate of 1 Hz throughout the duration of the 8-hour test period.

### 3.8 TEST 5A AND 5B

These tests were carried out while the HIU was still in “keep warm” mode after the 8-hour keep warm test. With the data still being logged at a rate of 1 Hz, the DHW flow was immediately brought back to 0.13 l/s.

### 3.9 TEST SET UP

Table 5 shows the setup of the tests as given in the test regime.

**Table 5 Test setup as given in the test regime**

Test No.	Test	static pressure on return	dP across HIU	Primary flow temp	Hot water setpoint	DHW flow rate	DHW power	space heat output	space heat flow temp	space heat return temp
		bar	bar	°C	°C	l/s	kW	kW	°C	°C
			dP <sub>1</sub>	t <sub>11</sub>	t <sub>32</sub>	q <sub>3</sub>	P <sub>3</sub>	P <sub>2</sub>	t <sub>22</sub>	t <sub>21</sub>
Static tests										
0a	Static pressure test (same static pressure on both flow and return connections)	1.43 times rated value		70	50	-	-	-	n/a	n/a
1a	Space Heating 1 kW	3.0	0.5	70	55	-	-	1	60	40
1b	Space Heating 2 kW	3.0	0.5	70	55	-	-	2	60	40
1c	Space Heating 4 kW	3.0	0.5	70	55	-	-	4	60	40
1d	Space Heating 1 kW	3.0	0.5	60	50	-	-	1	45	35
1e	Space Heating 2 kW	3.0	0.5	60	50	-	-	2	45	35
1f	Space Heating 4 kW	3.0	0.5	60	50	-	-	4	45	35
Dynamic tests										
2a	DHW only DH 70°C flow	3.0	0.5	70	55	see DHW test profile	see DHW test profile	-	60	-
2b	DHW only DH 60°C flow	3.0	0.5	60	50			-	45	-
3a	Low flow DHW, DH 70°C flow	3.0	0.5	70	55	0.02	Record value	-	60	-
3b	Low flow DHW, DH 60°C flow	3.0	0.5	60	50	0.02	Record value	-	45	-
4a	Keep-warm, DH 70°C flow	3.0	0.5	70	55	0	0	-	60	-
4b	Keep-warm, DH 60°C flow	3.0	0.5	60	50	0	0	-	45	-
5a	DHW response time	3.0	0.5	70	55	0.13	Record value	-	60	-
5b	DHW response time	3.0	0.5	60	50	0.13	Record value	-	45	-

Table 6 shows the reporting structure of the tests as given in the test regime. See section 5 for the full test results.

**Table 6 Test reporting structure as given in the test regime**

Test	Description	Reporting	Pass/Fail
<b>Static Tests</b>			
0	Pressure tests	Pass/Fail as to whether HIU manages pressure test without leaks or damage.	Pass
1a	Space Heating 1 kW, 60/40°C secondary	t <sub>11</sub> -primary flow temperature t <sub>12</sub> -primary return temperature.	N/A
1b	Space Heating 2 kW, 60/40°C secondary	Plot of key metrics over duration of test.	N/A
1c	Space Heating 4 kW, 60/40°C secondary	<b>Note:</b> Outputs used as input data to 'High Temperature' Space Heating Volume Weighted Average Return Temperature calculation.	N/A
1d	Space Heating 1 kW, 45/35°C secondary	t <sub>11</sub> -primary flow temperature t <sub>12</sub> -primary return temperature	N/A
1e	Space Heating 2 kW, 45/35°C secondary	Plot of key metrics over duration of test.	N/A
1f	Space Heating 4 kW, 45/35°C secondary	<b>Note:</b> Outputs used as input data to 'Low Temperature' Space Heating Volume Weighted Average Return Temperature calculation.	N/A
<b>Dynamic Tests</b>			
2a	DHW only, DH 70°C flow; 55°C DHW	Pass/Fail on DHW (at t <sub>32</sub> ) exceeding 65.0°C (to 1 decimal point) for more than 10 consecutive seconds. State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Assessment of scaling risk as per criteria detailed in 2.26. <b>Note:</b> Outputs used as input data to 'High Temperature' Domestic Hot Water Weighted Average Return Temperature calculation. Plot t <sub>32</sub> , t <sub>31</sub> , q <sub>3</sub> , t <sub>12</sub> q <sub>1</sub>	Pass
2b	DHW only, DH 60°C flow; 50°C DHW	State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Plot t <sub>32</sub> , t <sub>31</sub> , q <sub>3</sub> , t <sub>12</sub> q <sub>1</sub> <b>Note:</b> Outputs used as input data to 'Low Temperature' Domestic Hot Water Weighted Average Return Temperature calculation.	N/A
3a	Low flow DHW, DH 70°C flow; 55°C DHW	Pass/Fail on DHW (at t <sub>32</sub> ) exceeding 65.0°C (1 decimal place) for more than 10 consecutive seconds. Comment on ability to deliver DHW at low flow based on DHW temperature reaching at least 45.0°C (1 decimal place) at the end of the 180 second period of low flow DHW. Comment on ability to deliver stable DHW flow temperature (at t <sub>32</sub> ) , defined as ability to maintain 55.0 +/-3.0°C (1 decimal place) during the last 60 seconds of the test. Maximum temperature achieved and +/-°C variance around 55.0°C (1 decimal place) to be stated. Assessment of scaling risk as per criteria detailed in 2.26. Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.	Pass

Test	Description	Reporting	Pass/Fail
3b	Low flow DHW, DH 60°C flow; 50°C DHW	<p>Comment on ability to deliver DHW at low flow rate based on DHW temperature reaching at least 45°C (one decimal place) at the end of the 180 second period of low flow DHW.</p> <p>Comment on ability to deliver stable DHW flow temperature (at t<sub>32</sub>), defined as ability to maintain 50.0 +/-3°C (1 decimal place) during the last 60 seconds of the test. Maximum temperature achieved and +/-°C variance around 55.0°C (1 decimal place) to be stated.</p> <p>Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.</p> <p>Maximum temperature achieved and +/-°C variance around 50.0°C (1 decimal place) to be stated.</p>	N/A
4a	Keep-warm, DH 70°C flow; 55°C DHW	<p>Assessment of whether valid keep-warm operation, based on 5a response time criteria: Pass / Fail.</p> <p>Observation on the operation of the HIU during keep-warm.</p> <p>Assessment of scaling risk, based on duration of temperatures in excess of 55.0°C (one decimal place). Plot temperature t<sub>10</sub>.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Plot of key metrics over duration of test.</p> <p>State average heat load for the duration of the test.</p> <p>State average primary flowrate for the duration of the test.</p> <p><b>Note:</b> Outputs used as input data to High Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p>	Pass
4b	Keep-warm, DH 60°C flow; 50°C DHW	<p>Assessment of whether valid keep-warm operation, based on 5b response time criteria: Pass / Fail.</p> <p>Observation on the operation of the HIU during keep-warm.</p> <p>Assessment of scaling risk, based on duration of temperatures in excess of 55.0°C (one decimal place).</p> <p>Plot temperature t<sub>10</sub>.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Plot of key metrics over duration of test.</p> <p>State average heat load for the duration of the test.</p> <p>State average primary flowrate for the duration of the test.</p> <p><b>Note:</b> Outputs used as input data to 'Low Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p>	Pass
5a	DHW response time, DH 70°C flow; 55°C DHW	<p>Pass/Fail on DHW (at t<sub>32</sub>) exceeding 65.0°C (1 decimal place) for more than 10 consecutive seconds. State time to achieve a DHW temperature 45.0°C (1 decimal place) and not subsequently drop below 42.0°C (1 decimal place).'</p> <p>Plot t<sub>32</sub>, t<sub>31</sub>, q<sub>3</sub>, t<sub>12</sub>, q<sub>1</sub> over duration of test.</p>	Pass
5b	DHW response time, DH 60°C flow; 50°C DHW	<p>State time to achieve a DHW temperature 45.0°C (1 decimal place) and not subsequently drop below 42.0°C (1 decimal place).</p> <p>Plot t<sub>32</sub>, t<sub>31</sub>, q<sub>3</sub>, t<sub>12</sub>, q<sub>1</sub> over duration of test.</p>	Pass

## 4 TEST RESULTS

Charts of the key metrics for the thermal tests are given in Appendix A.

### 4.1 PRESSURE TEST – 0A

The DHW circuit and the space heating circuit were pressurised to 1.5 bar. The primary circuit was pressurised to 1.43 times the rated maximum static pressure of 16 bar (test pressure 22.88 bar). This pressure was held for 30 minutes. After the 30-minute test period, the connections and fittings on the HIU were inspected for leaks and any signs of deformation.

During the 30-minute period, there were no leaks or signs of deformation.

Result – Pass.

### 4.2 STATIC TESTING – 1A, 1B, 1C, 1D, 1E AND 1F

The following tests were carried out on the radiator space heating circuit:

- 1a – DH inlet 70°C, heating return at 40°C and a flow set to achieve 1kW heating duty
- 1b – DH inlet 70°C, heating return at 40°C and a flow set to achieve 2kW heating duty
- 1c – DH inlet 70°C, heating return at 40°C and a flow set to achieve 4kW heating duty
- 1d – DH inlet 60°C, heating return at 35°C and a flow set to achieve 1kW heating duty
- 1e – DH inlet 60°C, heating return at 35°C and a flow set to achieve 2kW heating duty
- 1f – DH inlet 60°C, heating return at 35°C and a flow set to achieve 4kW heating duty

For tests 1a to 1c, the space heating outlet temperature was set to achieve 60°C on the HIU control valve during the 4kw test.

For tests 1d to 1f, the space heating outlet temperature was set to achieve 45°C on the HIU control valve during the 4kw test.

Table 7 shows a summary of the results for the static tests.

**Table 7 Results from the static tests**

Test	District Heating Circuit				Space Heating Circuit				
	t <sub>11</sub> (°C)	t <sub>12</sub> (°C)	q <sub>1</sub> (l/s)	P <sub>1</sub> (kW)	T <sub>21</sub> (°C)	T <sub>22</sub> (°C)	q <sub>2</sub> (l/s)	Δp <sub>2</sub> (kPa)	P <sub>2</sub> (kW)
1a	70.06	39.73	0.008	1.01	40.00	62.02	0.011	0.02	1.01
1b	70.17	42.28	0.017	1.98	40.03	63.22	0.020	0.25	1.94
1c	69.98	41.43	0.034	4.06	40.12	60.28	0.048	1.53	4.05
1d	59.93	34.82	0.010	1.05	35.00	46.69	0.020	0.32	0.98
1e	60.00	35.17	0.019	1.97	35.07	45.93	0.043	1.40	1.95
Uncertainty	±0.019	±0.018	±0.0006	±0.07	±0.02	±0.02	±0.0006	±0.054	±0.06
1f	60.03	35.20	0.039	4.05	35.05	44.99	0.096	5.82	3.99
Uncertainty	±0.018	±0.018	±0.0006	±0.07	±0.02	±0.02	±0.0012	±0.055	±0.05



## 4.3 DYNAMIC TESTING OF THE HIU OPERATION – 2A AND 2B

### 4.3.1 Test 2a

Test 2a was carried out with the DH water temperature set to 70°C and the cold-water supply to the DHW circuit at 10°C. The DHW outlet temperature was set to achieve 55.0 (±0.5°C) at a DHW flow rate of 0.130 l/s, prior to the test.

During test 2a:

- The DHW temperature did not exceed 65°C at any point during the test
- The maximum DHW temperature was 57.8°C
- The minimum DHW temperature was 53.7°C
- Details of the scaling risk are given in Table 8

Result – Pass

### 4.3.2 Test 2b

Test 2b was carried out with the DH water temperature set to 60°C and the cold-water supply to the DHW circuit at 10°C. The DHW outlet temperature was set to achieve 50.0 (±0.5°C) at a DHW flow rate of 0.130 l/s, prior to the test.

During test 2b:

- The maximum DHW temperature was 52.4°C
- The minimum DHW temperature was 49.2°C

Result – There is no pass/fail criteria for this test.

## 4.4 LOW FLOW DHW TEST – 3A AND 3B

### 4.4.1 Test 3a

Test 3a was carried out with the DH water temperature set to 70°C and the cold water supply to the DHW circuit at 10°C. The DHW outlet temperature setpoint remained at the same position, set to achieve 55.0 (±0.5°C) at a DHW flow rate of 0.130 l/s.

During test 3a:

- The DHW temperature did not exceed 65.0°C during the test
- The unit did maintain a stable temperature during the test, but it was above the upper limit of the stated tolerance of 55.0 ±3°C during the last 60 seconds of the test
- The DHW maximum and minimum outlet temperatures were 59.8°C and 55.1°C respectively
- Details of the scaling risk are given in Table 8

Result – Pass

#### 4.4.2 Test 3b

Test 3b was carried out with the DH water temperature set to 60°C and the cold water supply to the DHW circuit at 10°C. The DHW outlet temperature setpoint remained at the same position, set to achieve 50.0 (±0.5°C) at a DHW flow rate of 0.130 l/s.

During test 3b:

- The unit did maintain a stable temperature during the test, but it was above the upper limit of the stated tolerance of 50.0 ±3°C during the last 60 seconds of the test
- The DHW maximum and minimum outlet temperatures were 53.7°C and 50.0°C respectively

Result – There is no pass/fail criteria for this test.

### 4.5 KEEP WARM TESTS – 4A AND 4B

The keep warm function was a trickle flow that went through the heat exchanger.

#### 4.5.1 Test 4a

Test 4a was carried out with the DH water temperature set to 70°C and the cold water supply to the DHW circuit at 10°C. The DHW outlet temperature setpoint remained at the same position, set to achieve 55.0 (±0.5°C) at a DHW flow rate of 0.130 l/s.

Based on the results for the DHW response time during test 5a, the HIU does perform a valid keep warm operation.

Once the keep warm function had stabilised (approximately 6500 seconds into the test), the average  $t_{12}$  temperature was 49.5°C varying between 49.7°C and 49.1 °C.

During test 4a:

- The average heat load during the 8-hour keep warm period was 61 W
- The average primary flow rate during the 8-hour keep warm period was 7.8 l/h
- Details of the scaling risk are given in Table 8

#### 4.5.2 Test 4b

Test 4b was carried out with the DH water temperature set to 60°C and the cold water supply to the DHW circuit at 10°C. The DHW outlet temperature setpoint remained at the same position, set to achieve 50.0 (±0.5°C) at a DHW flow rate of 0.130 l/s.

Based on the results for the DHW response time during test 5b, the HIU does perform a valid keep warm operation.

Once the keep warm function had stabilised (approximately 8500 seconds into the test), the average  $t_{12}$  temperature was 51.0°C varying between 51.3°C and 50.8°C.

During test 4b:

- The average heat load during the 8-hour keep warm period was 58 W
- The average primary flow rate during the 8-hour keep warm period was 10.4 l/h
- Details of the scaling risk are given in Table 8

## 4.6 DHW RESPONSE TIME – 5A AND 5B

### 4.6.1 Test 5a

Test 5a was carried out immediately after test 4a with all the settings and conditions the same.

During test 5a:

- The DHW temperature did not exceed 65.0°C during the test
- The DHW achieved 45.0°C in 4 seconds from the first recorded non-zero DHW flow reading

Result

Scaling risk factor – Pass

Achieving 45°C DHW within 15 seconds – Pass

### 4.6.2 Test 5b

Test 5b was carried out immediately after test 4b with all the settings and conditions the same.

During test 5b:

- The DHW achieved 45.0°C in 4 seconds from the first recorded non-zero DHW flow reading

Result

Achieving 45°C DHW within 15 seconds – Pass

## 4.7 TOTAL SCALING RISK ASSESSMENT

The scaling risk criteria is given in section 2.26 of the test regime. Table 8 gives detailed of the scaling risk during tests 2a, 3a, 4a and 4b.

**Table 8 Total scaling risk assessment**

Has the HIU got a TMV or TRV on the output of the DHW plate heat exchanger?	No	
	Test	
	2a	3a
t <sub>32</sub> above 60°C for more than 5 seconds	No	No
t <sub>12</sub> exceeds 55°C at any point of the test	No	No
	4a	4b
t <sub>12</sub> exceeds 50°C at any time	No	No

## 4.8 VOLUME WEIGHTED AVERAGE RETURN TEMPERATURE

The Volume Weighted Average Return Temperature (VWART) results are given in Appendix B.

APPENDIX A: DATA CHARTS

Figure 3 Results for test 1a: 1kW Space heating – DH 70°C supply




Figure 4 Results for test 1b: 2kW Space heating – DH 70°C supply




Figure 5 Results for test 1c: 4kW Space heating – DH 70°C supply




Figure 6 Results for test 1d: 1kW Space heating – DH 60°C supply




Figure 7 Results for test 1e: 2kW Space heating – DH 60°C supply






Figure 8 Results for test 1f: 4kW Space heating – DH 60°C supply




Figure 9 Results for test 2a: DHW dynamic test – DH 70°C




Figure 10 Results for test 2b: DHW dynamic test – DH 60°C




Figure 11 Results for test 3a: Low flow DHW test – DH 70°C




Figure 12 Results for test 3b: Low flow DHW test – DH 60°C




Figure 13 Results for point 4a: Keep warm test – DH 70°C supply




Figure 14 Results for point 4b: Keep warm test – DH 60°C supply




Figure 15 Results for test 5a: DHW response time – DH 70°C supply







Figure 16 Results for test 5b: DHW response time – DH 60°C supply



## APPENDIX B: VWARD CALCULATIONS

### High Temperature VWARD Calculations



#### High Temperature VWARD Calculation for Heat products Ltd. HIU

Primary flow temperature = 70°C, DHW set point = 55°C, Space heating temperatures = 60°C/40°C

Test carried out by BSRIA Ltd. in March 2019, Test Reference 61539/1

Manufacturer: Heat Product Ltd.; Model: Compact VX1-1; Serial number: 1901271; Year of manufacture: 2019

VWARD calculation prepared by Colin Judd of BSRIA Ltd on 29 March 2019

	VWARD (°C)	Volume (m <sup>3</sup> )
<b>DHW</b>	19	24.73
<b>Keep warm</b>	49	62.25
<b>Space heating</b>	42	45.00

	VWARD with keep warm active	
Period	VWARD (°C)	% Time
<b>No heating</b>	40	93%
<b>Heating</b>	42	7%
<b>Overall</b>	40	

	DHW draw test results			Post DHW draw (60 seconds)	
	Power (W)	Primary flow (m <sup>3</sup> /hr)	Return temp (°C)	Primary flow (m <sup>3</sup> /hr)	Return temp (°C)
Low	11718	0.196	18.3	0.000	0.00
Medium	19008	0.319	18.5	0.000	0.00
High	24453	0.415	19.1	0.000	0.00

DHW draw volumes per annum		
Energy (kWh)	Time (hours)	Volume (m <sup>3</sup> )
729	62.21	12.219
297	15.63	4.984
444	18.16	7.529

Post DHW draw volumes per annum		
Events	Avg duration (seconds)	Volume (m <sup>3</sup> )
10000	30	0.000
660	75	0.000
300	145	0.000

Keep warm test results	
Primary flow (m <sup>3</sup> /hr)	Return temp (°C)
0.0078	48.9

Keep warm volumes per annum	
Time (hours)	Volume (m <sup>3</sup> )
8022	62.252

	Space heating test results		
	Power (W)	Primary flow (m <sup>3</sup> /hr)	Return temp (°C)
1 kW	1012	0.029	39.7
2 kW	1938	0.062	42.3
4 kW	4046	0.123	41.4

Space heating volumes per annum		
Energy (kWh)	Time (hours)	Volume (m <sup>3</sup> )
98	96.79	2.791
787	406.04	25.005
565	139.64	17.208

## Low Temperature VVART Calculations

**Low Temperature VVART Calculation for Heat Product Ltd. HIU**

Primary flow temperature = 60°C, DHW set point = 50°C, Space heating temperatures = 45°C/35°C

Test carried out by BSRIA Ltd. in March 2019, Test Reference 61539/1

Manufacturer: Heat Product Ltd.; Model: Compact VX1-1; Serial number: 1901271; Year of manufacture: 2019

VVART calculation prepared by Colin Judd of BSRIA Ltd on 29 March 2019

	VVART (°C)	Volume (m <sup>3</sup> )
<b>DHW</b>	20	31.53
<b>Keep warm</b>	46	83.18
<b>Space heating</b>	35	51.04

	VVART with keep warm active	
<b>Period</b>	VVART (°C)	% Time
<b>No heating</b>	39	93%
<b>Heating</b>	36	7%
<b>Overall</b>	39	

	DHW draw test results			Post DHW draw (60 seconds)	
	Power (W)	Primary flow (m <sup>3</sup> /hr)	Return temp (°C)	Primary flow (m <sup>3</sup> /hr)	Return temp (°C)
Low	10537	0.227	19.5	0.000	0.00
Medium	17119	0.366	19.6	0.000	0.00
High	21541	0.461	19.9	0.000	0.00

DHW draw volumes per annum		
Energy (kWh)	Time (hours)	Volume (m <sup>3</sup> )
729	69.18	15.689
297	17.35	6.343
444	20.61	9.495

Post DHW draw volumes per annum		
Events	Avg duration (seconds)	Volume (m <sup>3</sup> )
10000	30	0.000
660	75	0.000
300	145	0.000

Keep warm test results	
Primary flow (m <sup>3</sup> /hr)	Return temp (°C)
0.0104	46.2

Keep warm volumes per annum	
Time (hours)	Volume (m <sup>3</sup> )
8009	83.183

	Space heating test results		
	Power (W)	Primary flow (m <sup>3</sup> /hr)	Return temp (°C)
1 kW	977	0.036	34.8
2 kW	1960	0.068	35.2
4 kW	3975	0.140	35.2

Space heating volumes per annum		
Energy (kWh)	Time (hours)	Volume (m <sup>3</sup> )
98	100.27	3.610
787	401.48	27.475
565	142.14	19.956