

BESA HIU PARTIAL TEST REPORT
HIPER II TWIN PLATE HIU HIPER2TP1580ZE

Client: Intatec Ltd
Airfield Industrial Estate
Hixon
Staffordshire
ST18 0PF


Project Number: E4591

Date: 09 September 2021

Report Number: 1 Issue 4

Prepared By: 

Simon Broxham - Project Engineer

Approved By: 

Josh Welburn – Project Engineering Manager



DISCLAIMER

This report is confidential to the client named on the front cover.

This report may be stored, transmitted or reproduced in full by the named client, however if the report is to be placed in the public domain or used for publicity / promotional purposes please inform a director of Enertek International Ltd.

The report must not be reproduced in part, edited, abridged or any extracts used for any purpose whatsoever without written permission from a director of Enertek International Ltd.

The client remains responsible for any data supplied by the client for use in this report. If this data could affect the test results this will be noted in the report.

Any test results contained in this report apply only to the specific sample(s) tested as described in the report.

This report does not imply or indicate any element of commercial approval, recommendation or promotion by Enertek International Ltd.

BESA SUMMARY SHEET

This test summary, downloaded from the BESA website, indicates that the HIU listed below has been tested against the criteria of the BESA HIU Test Regime.



Model: HIPER2TP1580ZE

Serial Number: INE211410015AR

Year of manufacture: 2021

Test carried out by Enertek International On: 1/6/21

Reference: E4591

NOTE: The VWART accuracy is in the range +/-2°C

	HIGH TEMP	LOW TEMP
	VWART °C	VWART °C
DHW	15	16
Keep-warm	37	37
Space heating	43	35
Overall with keep warm	28	26

Pressure test		
No HIU damage	Pass	Pass

Dynamic DHW operation	2a	
DHW not exceed 65°C	Pass	Pass

Low flow test at BESA flow rate of 0.02l/s	3a	3b
DHW not exceed 65°C	Pass	Pass
DHW temperature at set point +/- 3°C	Pass	Pass

Low flow test at manufacturer declared flow rate	3c	3d
Declared minimum flow rate (l/sec)	1.2	1.2
Not exceed 65°C	Yes	n/a
DHW temperature at set point +/- 3°C	n/a	n/a

Keep-warm test	4a	4b
Standby heat consumption - average (Watts)	42	42
Standby electricity consumption - average (Watts)		
Total HIU heat loss (DH + electrical input) (Watts)		
Standby flow rate (the average flow rate) (l/hr)	3.3	4.5

DHW Response time test	5a	5b
DHW response time (Seconds)	13	15
Peak electrical heat during test (Watts)		
Output		
DHW temperature not exceed 65°C for more than 10 secs	Pass	Pass
DHW reaches 45°C with 15 secs	Pass	Pass

Scaling risk assessment as defined in 2.26	If any of the factors below occur then the risk of scaling of the DHW PHE in hard water areas increases		
HIU has a TMV or TRV on the DHW	No		
Test	2a	3a	3c
t32 above 60°C for more than 5 secs	No	No	No
t12 exceeds 55°C at any point of the test	No	No	No
Test	4a		4b
t12 exceeds 50°C at any time	No		No

CONTENTS

1	BRIEF	5
2	DEFINITIONS.....	6
3	TEST OBJECT	7
3.1	Appliance Details.....	7
3.2	Appliance Design Pressures	7
3.3	Appliance Design Temperatures	7
4	TEST METHOD	8
4.1	Installation of Appliance	8
4.2	Test Regime.....	8
4.3	Measurement & Uncertainties	8
5	TEST RESULTS	13
5.1	Test 0 – Pressure Test	13
5.2	Test 1a to 1f – Space Heating 1-4 kW at 70 and 60 °C.....	13
5.3	Test 2a – DHW Dynamic Tapping at 70 °C.....	14
5.4	Test 2b – DHW Dynamic Tapping at 60 °C	14
5.5	Test 3a – Low Flow DHW at 70 °C	14
5.6	Test 3b – Low Flow DHW at 60 °C.....	14
5.7	Test 4a – Keep-Warm at 70 °C	15
5.8	Test 4b – Keep-Warm at 60 °C	15
5.9	Test 5a – DHW Response Time at 70 °C.....	16
5.10	Test 5b – DHW Response Time at 60 °C.....	16
5.11	Overall Scaling Risk Assessment.....	16
5.12	VWART Calculations	17
6	CONCLUSIONS	18
7	APPENDIX A.....	19
7.1	Key Metric Plots	19
7.2	Key Metric and VWART Summary	34
8	APPENDIX B.....	37
8.1	Appliance Documentation	37
8.2	Appliance Components	38
8.3	Appliance Photographs	39
8.4	Calibrations and Uncertainties	41

LIST OF FIGURES

Figure 4.1 – EIL’s HIU Test Rig Schematic	9
Figure 7.1 - Test 1a – Space Heating 1 kW at 70 °C	20
Figure 7.2 - Test 1b – Space Heating 2 kW at 70 °C	21
Figure 7.3 - Test 1c – Space Heating 4 kW at 70 °C	22
Figure 7.4 - Test 1d – Space Heating 1 kW at 60 °C	23
Figure 7.5 - Test 1e – Space Heating 2 kW at 60 °C	24
Figure 7.6 - Test 1f – Space Heating 4 kW at 60 °C	25
Figure 7.7 - Test 2a – DHW only at 70 °C	26
Figure 7.8 - Test 2b – DHW only at 60 °C	27
Figure 7.9 - Test 3a – Low Flow DHW at 70 °C	28
Figure 7.10 - Test 3b – Low Flow DHW at 60 °C	29
Figure 7.11 - Test 4a – Keep-Warm at 70 °C	30
Figure 7.12 - Test 4b – Keep-Warm at 60 °C	31
Figure 7.13 - Test 5a – DHW Response Time at 70 °C	32
Figure 7.14 - Test 5b – DHW Response Time at 60 °C	33
Figure 8.1 – Photograph of Appliance [Case Fitted]	39
Figure 8.2 –Appliance Data Label	39
Figure 8.3 – Photograph of Appliance (Case Removed)	40

LIST OF TABLES

Table 3.1 – Appliance Details.....	7
Table 3.2 – Appliance Design Pressures	7
Table 3.3 – Appliance Design Temperatures	7
Table 4.1 – Setup of Tests (Based on BESA Test Regime, Table 1: Test Schedule)	10
Table 4.2 – Test Reporting, [Adapted From BESA Test Regime, Table 5]	11
Table 5.1 - Test Results for Space Heating Tests 1a to 1f	13
Table 5.2 - Overall Scaling Risk Assessment	16
Table 5.3 – High Temperature VWART Calculations.....	17
Table 5.4 – Low Temperature VWART Calculations	17
Table 7.1 - Key Metrics of High Temperature Package.....	35
Table 7.2 - Key Metrics of Low Temperature Package	36
Table 8.1 – Documentation Supplied.	37
Table 8.2 – Appliance Components Details	38
Table 8.3 - EIL Equipment Calibration and Uncertainties	41

1 BRIEF

- 1.1.1 Enertek international Limited (EIL), were contracted to receive, install and commission a production sample, of the Hiper II Twin Plate HIPER2TP1580ZE. This is a variant of the HIPER II, Serial No: 300001, the data and results of which can be found in report [HIPER II E4412](#).
- 1.1.2 The variation in the HIPER II TWIN PLATE HIU HIPER2TP1580ZE compared to the original is on the Space Heating side only. Therefore DHW test results and Keep Warm results are being brought forward from the original test report [HIPER II E4412](#), used in all necessary calculations and re-printed in this report.
- 1.1.3 To carry out the work involved to evaluate the performance of Space Heating (SH) in accordance with the BESA UK HIU Test Regime Technical Specification, Rev-009, a publicly available online test regime. This is here-on referred to as the Test Regime throughout this document.
- 1.1.4 To provide a report detailing the tests carried out and generated results in accordance with the Test Regime criteria, including calculations for Volume Weighted Average Return Temperatures (VWART).

2 DEFINITIONS

2.1.1 The following definitions and abbreviations have been used within this report:

Symbol	Description	Unit
P_1	Power, Primary Side	kW
P_2	Power, Space Heating Side	kW
P_3	Power, Domestic Hot Water	kW
t_{11}	Temperature, Primary Side Supply Connection	°C
t_{12}	Temperature, Primary Side Return Connection	°C
t_{21}	Temperature, Space Heating Side Return Connection	°C
t_{22}	Temperature, Space Heating System Supply Connection	°C
t_{31}	Temperature, Cold Water Supply	°C
t_{32}	Temperature, Domestic Hot Water Output from HIU	°C
q_1	Volume Flow, Primary Side	L/s
q_2	Volume Flow, Space Heating Side	L/s
q_3	Volume flow, Domestic Hot Water	L/s
Δp_1	Primary Pressure drop across entire HIU Unit	kPa
Δp_2	Pressure Drop, Space Heating System across HIU	kPa
Δp_3	Pressure Drop, Domestic Hot Water across HIU	kPa
$VWART_{DHW}$	DHW Volume Weighted Return Temperature	°C
$VWART_{SH}$	Space Heating Volume Weighted Return Temperature	°C
$VWART_{KWH}$	Keep Warm Volume Weighted Return Temperature	°C
$VWART_{HEAT}$	Annual Volume Weighted Return Temperature for Heating Period	°C
$VWART_{NONHEAT}$	Annual Volume Weighed Return Temperature for Non-Heating	°C
$VWART_{HIU}$	Total Annual Volume Weighted Return Temperature	°C
DHW	Domestic Hot Water	—
HIU	Heat Interface Unit	—
SH	Space Heating	—
TMV	Thermostatic Mixing Valve	—

3 TEST OBJECT

3.1 Appliance Details

3.1.1 Details of the HIU HIPER2TP1580ZE appliance are given in Table 3.1. Photograph of the installed appliance is given in

3.1.2 Figure 8.2.

Table 3.1 – Appliance Details

Item	Description
Manufacturer	Intatec Ltd
Model	HIPER2TP1580ZE
Serial Number	INE211410015AR
Year of Manufacture	2021
DHW Priority	Yes

3.2 Appliance Design Pressures

3.2.1 The maximum design pressures of the HIPER2TP1580ZE appliance for the primary side and the secondary side for both Space Heating and DHW are given in Table 3.2.

Table 3.2 – Appliance Design Pressures

Item	Value	Unit
Primary Side	16	Bar
Secondary Side Space Heating	3	Bar
Secondary Side DHW	10	Bar

3.3 Appliance Design Temperatures

3.3.1 The maximum design temperatures of the HIPER2TP1580ZE appliance for the primary side and the secondary side for both Space Heating and DHW are given in Table 3.3

Table 3.3 – Appliance Design Temperatures

Item	Value	Unit
Primary Side	85	°C
Secondary Side Space Heating	85	°C
Secondary Side DHW	65	°C

Test Method

3.4 Installation of Appliance

- 3.4.1 The appliance was installed and commissioned (as received) and as defined in the product literature provided. Testing was carried out without further adjustment other than disabling the internal space heating pump and adjusting the setting of the SH points through the user interface on the HIU controller to suit the conditions of the HIU test rig. The HIU rig schematic is given in Figure 4.1.

3.5 Test Regime

- 3.5.1 The testing described in this report was carried out in accordance with the BESA Test Regime. The Test Regime outlines a series of static and dynamic tests to determine the performance of a HIU's DHW and SH functions. The Regime outlines the test method including the reporting of the results, the performance requirements and the VWARD calculations.
- 3.5.2 The setup of the BESA tests is reproduced in Table 4.4. The basis of reporting the performance of the HIU from the BESA Test Regime is reproduced in Table 4.5.
- 3.5.3 The Test Regime specifies the testing of two different test temperature packages. The first is the high temperature package, with a district primary supply of 70 °C and the second is the 'low temperature' package, with a district primary supply temperature of 60 °C.
- 3.5.4 As the Intatec, HIPER2TP1580ZE is suitable for both high and low temperature operation, both test packages were carried out and results recorded within this report.

3.6 Measurement & Uncertainties

- 3.6.1 All measurements and uncertainties adhere to the requirements stipulated in the BESA Test Regime. All measurements were sampled at a rate of 1 Hz for all tests.
- 3.6.2 The BESA uncertainties of measurement requirements are as follows: Differential Pressure, ± 1 kPa; Temperature, ± 0.1 °C; Volume Flow, ± 1.5 %. Note: the time constant for the temperature sensors is less than 1.5 s.
- 3.6.3 EIL's reported uncertainty is based on a standard uncertainty by a coverage factor $K=2$, providing a level of confidence of approximately 95%. The uncertainty evaluation has been carried out in accordance with UKAS requirements. The EIL equipment list and uncertainties are given in Table 8.3, Appendix B.




Figure 4.1 – EIL's HIU Test Rig Schematic

Table 4.4 – Setup of Tests (Based on BESA Test Regime, Table 1: Test Schedule)

		District Circuit			Domestic Hot Water			Space Heating		
		Static Pressure	Differential Pressure	Flow Temperature	Temperature Set Point	Flow Rate	Heat Load	Flow Temperature	Return Temperature	Heat Load
<i>Symbol</i>		$[p_1]$	$[\Delta p_1]$	$[t_{11}]$	$[t_{32}]$	$[q_3]$	$[P_3]$	$[t_{22}]$	$[t_{21}]$	$[P_2]$
<i>Units</i>		$[kPa]$	$[kPa]$	$[^{\circ}C]$	$[^{\circ}C]$	$[Ls^{-1}]$	$[kW]$	$[^{\circ}C]$	$[^{\circ}C]$	$[kW]$
Static Tests										
0a	District Pressure Test	1.43 X Claimed Value	-	-	-	-	-	-	-	-
1a	1kW Space Heating	3.0	0.5	70	-	-	-	60	40	1
1b	2kW Space Heating	3.0	0.5	70	-	-	-	60	40	2
1c	4kW Space Heating	3.0	0.5	70	-	-	-	60	40	4
1d	1kW Space Heating	3.0	0.5	60	-	-	-	45	35	1
1e	2kW Space Heating	3.0	0.5	60	-	-	-	45	35	2
1f	4kW Space Heating	3.0	0.5	60	-	-	-	45	35	4
Dynamic Tests										
2a	Dynamic Tapping	3.0	0.5	70	55	See Test Profile	See Test Profile	-	-	-
2b	Dynamic Tapping	3.0	0.5	60	50			-	-	-
3a	Low Flow	3.0	0.5	70	55	0.02	Record Value.	-	-	-
3b	Low Flow	3.0	0.5	60	50	0.02	Record Value.	-	-	-
4a	Keep-Warm	3.0	0.5	70	55	0.00	0	-	-	-
4b	Keep-Warm	3.0	0.5	60	50	0.00	0	-	-	-
5a	DHW Response	3.0	0.5	70	55	0.13	Record Value.	-	-	-
5b	DHW Response	3.0	0.5	60	50	0.13	Record Value.	-	-	-

Table 4.5 – Test Reporting, [Adapted From BESA Test Regime, Table 5]

Test Designation		Reporting
0	District Pressure Test.	Pass/Fail as to whether HIU manages pressure test without leaks or damage.
1a	Space Heating 1 kW, 60/40 °C Secondary.	t_{11} – Primary flow temperature. t_{12} – Primary return temperature. Plot of key metrics over duration of test. Note: Outputs used as input data to ‘High Temperature’ Space Heating Volume Weighted Average Return Temperature calculation.
1b	Space Heating 2 kW, 60/40 °C Secondary.	
1c	Space Heating 4 kW, 60/40 °C Secondary.	
1d	Space Heating 1 kW, 45/35 °C Secondary.	t_{11} – Primary flow temperature. t_{12} – Primary return temperature. Plot of key metrics over duration of test. Note: Outputs used as input data to ‘Low Temperature’ Space Heating Volume Weighted Average Return Temperature calculation.
1e	Space Heating 2 kW, 45/35 °C Secondary.	
1f	Space Heating 4 kW, 45/35 °C Secondary.	
2a	DHW only, DH 70 °C Flow, 55 °C DHW.	Pass/Fail on DHW (at t_{32}) exceeding 65.0 °C (to 1 decimal point) for more than 10 consecutive seconds. State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Assessment of scaling risk as per the criteria detailed in 2.26. Note: Outputs used as input data to ‘High Temperature’ Space Heating Volume Weighted Average Return Temperature calculation. Plot t_{32} , t_{31} , q_3 , t_{12} , q_1
2b	DHW only, DH 60 °C Flow, 50 °C DHW.	State the maximum and minimum DHW temperatures over the period of the test when there is a DHW flow. Note: Outputs used as input data to ‘Low Temperature’ Domestic Hot Water Volume Weighted Average Return Temperature calculation. Plot q_1 , q_3 , dp_1 , dp_3
3a	Low flow DHW, DH 70 °C Flow, 55 °C DHW.	Pass/Fail on DHW (at t_{32}) exceeding 65.0 °C (1 decimal place) for more than 10 consecutive seconds. Comment on ability to deliver DHW at low flow based on DHW temperature reaching at least 45.0 °C (1 decimal place) at the end of the 180 second period of low flow DHW. Comment on the ability to deliver stable DHW flow temperature (at t_{32}), defined as ability to maintain 55.0 +/- 3.0 °C (1 decimal place) during the last 60 seconds of the test. Maximum temperature achieved and +/- °C variance around 55.0 °C (1 decimal place) to be stated. Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow. Assessment of scaling risk as per criteria detailed in 2.26.
3b	Low flow DHW, DH 60 °C flow, 50 °C DHW.	Comment on the ability to deliver DHW at low flow rate based on DHW temperature reaching at least 45 °C (1 decimal place) at the end of the 180 second period of low flow DHW. Comment on the ability to deliver stable DHW flow temperature (at t_{32}), defined as ability to maintain 50.0 +/- 3 °C (1 decimal place) to be stated. Maximum temperature achieved and +/- °C variance around 50.0 °C (1 decimal place) to be stated. Plot of key metrics for 60 seconds of 0.13 l/s flow and the subsequent 180 seconds of 0.02 l/s DHW flow.

Test Designation		Reporting
4a	Keep-warm, DH 70 °C Flow, 55 °C DHW.	<p>Assessment of whether valid keep-warm operation, based on 5a response time criteria: Pass/Fail.</p> <p>Comment on HIU keep-warm controls options.</p> <p>Assessment of scaling risk based on duration of temperatures in excess of 55.0 °C (1 decimal place).</p> <p>State average heat load for the duration of the test.</p> <p>State the average primary flow rate for the duration of the test.</p> <p>Note: Outputs used as input data to 'High Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p> <p>Plot of key metrics over duration of test.</p>
4b	Keep-Warm, DH 60 °C Flow, 50 °C DHW.	<p>Assessment of whether valid keep-warm operation, based on 5a response time criteria: Pass/Fail.</p> <p>Observation on the operation of the HIU during keep-warm. Comment on HIU keep-warm controls options.</p> <p>Assessment of scaling risk based on extent and duration of temperatures in excess of 55.0 °C (1 decimal place).</p> <p>State average heat load for the duration of the test.</p> <p>State the average primary flowrate for the duration of the test.</p> <p>Note: Outputs used as input data to 'Low Temperature' Keep-warm Volume Weighted Average Return Temperature calculation.</p> <p>Plot of key metrics over duration of test.</p>
5a	DHW Response Time, DH 70 °C Flow, 55 °C DHW.	<p>Pass/Fail on DHW (at t_{32}) exceeding 65.0 °C (1 decimal place) for more than 10 consecutive seconds.</p> <p>State time to achieve 45.0 °C (1 decimal place) and not subsequently drop below 42.0 °C (1 decimal place).</p> <p>Plot t_{32}, t_{31}, t_{12}, q_1 over duration of test.</p>
5b	DHW Response Time, DH 60 °C Flow, 50 °C DHW.	<p>State time to achieve a DHW temperature 45.0 °C (1 decimal place) and not subsequently drop below 42.0 °C (1 decimal place).</p> <p>Comment on stability of DHW temperature.</p> <p>Plot t_{32}, t_{31}, t_{12}, q_1 over duration of test.</p>

4 TEST RESULTS

4.1 Test 0 – Pressure Test

- 4.1.1 The appliance has passed the requirements of the static pressure test, Test 0 of the BESA Test Regime as:
- 4.1.2 There was No damage observed during the static pressure test, with the primary flow pressurised to 22.88 bar (1.43 times the rated value), and,
- 4.1.3 There were No leaks observed during the static pressure test, with the primary flow pressurised to 22.88 bar (1.43 times the rated value).

4.2 Test 1a to 1f – Space Heating 1-4 kW at 70 and 60 °C

- 4.2.1 The plot of the key metrics of Tests 1a-1f for the space heating 1 - 4 kW at both 70 and 60 °C are displayed in Figure 7.1 to Figure 7.6 respectively. See Table 5.1 for summarised test results including the average primary return temperature, t_{12} .

Table 5.1 - Test Results for Space Heating Tests 1a to 1f

Test	Description	Primary					Secondary				
		Flow Temperature	Return Temperature	Flow Rate	Differential Pressure	Heat Load	Return Temperature	Flow Temperature	Flow Rate	Differential Pressure	Heat Load
		$[t_{11}]$	$[t_{12}]$	$[q_1]$	$[\Delta p_1]$	$[P_1]$	$[t_{21}]$	$[t_{22}]$	$[q_2]$	$[\Delta p_2]$	$[P_2]$
		[°C]	[°C]	[Ls ⁻¹]	[kPa]	[W]	[°C]	[°C]	[Ls ⁻¹]	[kPa]	[W]
1a	- 1 kW Space Heating (DH 70 °C flow)	70.0	41.3	0.010	51.9	1211	40.1	59.8	0.014	-1.1	1100
1b	- 2 kW Space Heating (DH 70 °C flow)	69.8	42.4	0.019	50.5	2073	40.0	59.6	0.024	-0.6	2010
1c	- 4 kW Space Heating (DH 70 °C flow)	70.1	43.1	0.035	50.6	3946	40.0	59.5	0.048	0.2	3950
1d	- Space Heating 1 kW (DH 60 °C flow)	59.9	35.3	0.010	56.4	1071	35.3	44.7	0.025	-0.7	1010
1e	- Space Heating 2 kW (DH 60 °C flow)	60.5	35.0	0.020	50.3	2074	34.6	44.6	0.048	0.1	2020
1f	- Space Heating 4 kW (DH 60 °C flow)	60.2	35.5	0.039	49.6	3984	34.9	44.9	0.094	2.9	3940

4.3 Test 2a – DHW Dynamic Tapping at 70 °C

4.3.1 The following data for test 2a is taken from [E4412 HIPER 2](#) original test results and report.

4.3.2 The domestic hot water output temperature, t_{32} did not exceed 65 °C for more than 10 seconds.

4.3.3 The maximum and minimum temperatures of t_{32} were 63.4°C and 46.90°C respectively.

4.3.4 The plot of the key metrics of the duration of Test 2a is displayed in Figure 7.7, Appendix.

4.4 Test 2b – DHW Dynamic Tapping at 60 °C

4.4.1 The following data for test 2b is taken from [E4412 HIPER 2](#) original test results and report.

4.4.2 The maximum and minimum temperatures of t_{32} were 54.52°C and 44.01°C respectively.

4.4.3 The plot of the key metrics of the duration of Test 2b is displayed in Figure 7.8, Appendix.

4.5 Test 3a – Low Flow DHW at 70 °C

4.5.1 The following data for test 3a is taken from [E4412 HIPER 2](#) original test results and report.

4.5.2 The appliance has passed the requirements of the Low Flow at 70 °C, Test 3a of the BESA Test Regime as:

4.5.3 The domestic hot water output temperature, t_{32} did not exceed 65 °C for more than 10 seconds, and,

4.5.4 The appliance did maintain the DHW output temperature, t_{32} at 55 ± 3 °C during the last 60 seconds of the test.

4.5.5 The maximum and minimum temperatures of t_{32} were 58.14°C and 49.91°C respectively.

4.5.6 The plot of the key metrics of the duration of Test 3a is displayed in Figure 7.9, Appendix.

4.6 Test 3b – Low Flow DHW at 60 °C

4.6.1 The following data for test 3b is taken from [E4412 HIPER 2](#) original test results and report.

4.6.2 The appliance has passed the requirements of the Low Flow at 60 °C, Test 3b of the BESA Test Regime as:

4.6.3 The maximum and minimum temperatures of t_{32} were 52.19°C and 46.38°C respectively.

4.6.4 The plot of the key metrics of the duration of Test 3b is displayed in Figure 7.10, Appendix.

4.7 Test 4a – Keep-Warm at 70 °C

4.7.1 The following data for test 4a is taken from [E4412 HIPER 2](#) original test results and report.

4.7.2 The appliance has passed the requirements of the keep-warm at 70 °C, Test 4a of the BESA Test Regime as:

4.7.3 This is a valid keep warm operation based on 5a response time criteria, see 4.9.4.

4.7.4 The appliance is not performing keep-warm cycling as the primary flow temperature, t_{11} varies by more than ± 3 °C during the final 3 hours of the test.

4.7.5 The average heat load on the primary side P_1 is 42 W.

4.7.6 The average primary flow q_1 over the 8 hours test was 3.3 l/hr.

4.7.7 The Keep-warm control was set to 39°C.

4.7.8 The plot of the key metrics of the duration of Test 4a is displayed in Figure 7.11, Appendix.

4.8 Test 4b – Keep-Warm at 60 °C

4.8.1 The following data for test 4b is taken from [E4412 HIPER 2](#) original test results and report.

4.8.2 The appliance has passed the requirements of the keep-warm at 60 °C, Test 4b of the BESA Test Regime as:

4.8.3 This is a valid keep warm operation based on 5b response time criteria, see 4.10.1.

4.8.4 The appliance is not performing keep-warm cycling as the primary flow temperature, t_{11} varies by more than ± 3 °C during the final 3 hours of the test.

4.8.5 The average heat load on the primary side P_1 is 42 W.

4.8.6 The average primary flow q_1 over the 8 hours test was 4.5 l/hr.

4.8.7 The Keep-warm control was set to 39°C.

4.8.8 The plot of the key metrics of the duration of Test 4b is displayed in Figure 7.12, Appendix.

4.9 Test 5a – DHW Response Time at 70 °C

4.9.1 The following data for test 5a is taken from [E4412 HIPER 2](#) original test results and report.

4.9.2 The appliance has passed the requirements of DHW Response Time at 70°C, Test 5a of the BESA Test Regime as:

4.9.3 The domestic hot water output temperature, t_{32} did not exceed 65 °C for more than 10 seconds.

4.9.4 The DHW response time for t_{32} to reach 45 °C (and not subsequently drop below 42 °C) was 13 seconds; therefore this is a valid keep warm.

4.9.5 The plot of the key metrics of the duration of Test 5a is displayed in Figure 7.13, Appendix.

4.10 Test 5b – DHW Response Time at 60 °C

4.10.1 The following data for test 5b is taken from [E4412 HIPER 2](#) original test results and report.

4.10.2 The DHW response time for t_{32} to reach 45 °C (and not subsequently drop below 42 °C) was 15 seconds; therefore this is a valid keep warm.

4.10.3 The plot of the key metrics of the duration of Test 5b is displayed in Figure 7.14, Appendix.

4.11 Overall Scaling Risk Assessment

4.11.1 If any of the below factors occur, then the risk of scaling of the DHW plate in hard water areas increases.

Table 5.2 - Overall Scaling Risk Assessment

<i>HIU has a TMV or TRV on the output of the DHW plate heat exchanger.</i>	No	
Test Designation	2a	3a
<i>t_{32} above 60°C for more than 5 seconds</i>	No	No
<i>t_{12} exceeds 55°C at any point of the test</i>	No	No
Test Designation	4a	4b
<i>t_{12} exceeds 50°C at any time</i>	No	No

4.12 VWART Calculations

4.12.1 The Volume Weighted Average Return Temperatures (VWART) have been calculated as stipulated in the BESA UK HIU Test Regime document. The calculated VWART values for both the high temperature and low temperature tests described in this report are given below in Table 5.3 and Table 5.4 respectively.

Table 5.3 – High Temperature VWART Calculations

Description	Symbol	Value	Unit
Annual Heating Period Percentage	SH _{PROP}	7.1	%
Annual Non-Heating Period Percentage	NSH _{PROP}	92.9	%
Space Heating Volume Weighted Return Temperature	VWART _{SH}	43	°C
DHW Volume Weighted Return Temperature	VWART _{DHW}	15	°C
Keep Warm Volume Weighted Return Temperature	VWART _{KWM}	37	°C
Annual Volume Weighted Return Temperature for Heating Period	VWART _{HEAT}	41	°C
Annual Volume Weighted Return Temperature for Non-Heating	VWART _{NONHEAT}	27	°C
Total Annual Volume Weighted Return Temperature	VWART _{OVERALL}	28	°C

Table 5.4 – Low Temperature VWART Calculations

Description	Symbol	Value	Unit
Annual Heating Period Percentage	SH _{PROP}	7.2	%
Annual Non-Heating Period Percentage	NSH _{PROP}	93.0	%
Space Heating Volume Weighted Return Temperature	VWART _{SH}	35	°C
DHW Volume Weighted Return Temperature	VWART _{DHW}	16	°C
Keep Warm Volume Weighted Return Temperature	VWART _{KWM}	37	°C
Annual Volume Weighted Return Temperature for Heating Period	VWART _{HEAT}	35	°C
Annual Volume Weighted Return Temperature for Non-Heating	VWART _{NONHEAT}	26	°C
Total Annual Volume Weighted Return Temperature	VWART _{OVERALL}	26	°C

5 CONCLUSIONS

5.1.1 The appliance has passed the performance requirements of the BESA HIU Test Regime.

6 APPENDIX A

6.1 Key Metric Plots

6.1.1 The graphical plots of the key metrics of the tests described in this report are given in this section.

GRAPHICAL PLOTS START ON NEXT PAGE




Figure 7.1 - Test 1a – Space Heating 1 kW at 70 °C




Figure 7.2 - Test 1b – Space Heating 2 kW at 70 °C




Figure 7.3 - Test 1c – Space Heating 4 kW at 70 °C




Figure 7.4 - Test 1d – Space Heating 1 kW at 60 °C




Figure 7.5 - Test 1e – Space Heating 2 kW at 60 °C




Figure 7.6 - Test 1f – Space Heating 4 kW at 60 °C




Figure 7.7 - Test 2a – DHW only at 70 °C




Figure 7.8 - Test 2b – DHW only at 60 °C




Figure 7.9 - Test 3a – Low Flow DHW at 70 °C




Figure 7.10 - Test 3b – Low Flow DHW at 60 °C




Figure 7.11 - Test 4a – Keep-Warm at 70 °C




Figure 7.12 - Test 4b – Keep-Warm at 60 °c




Figure 7.13 - Test 5a – DHW Response Time at 70 °C




Figure 7.14 - Test 5b – DHW Response Time at 60 °C

6.2 Key Metric and VWARD Summary

6.2.1 The summary tables of the key metrics and VWARDS of the tests described in this report are given in this section.

SUMMARY TABLES START ON NEXT PAGE



VWART Calculation with Keep Warm

Test carried out by Enertek International for High Temperature BESA Tests

Manufacturer: Intatec Ltd

Model: HIPER2TPSZ80

Serial number: INE211410015AR

Calculation performed by S.Broxham of Enertek on: 05/05/2021

Primary Flow Temperature: 70°C

DHW Setpoint: 55°C

Space Heating Temperature: 60/40°C

	VWART (°C)	Volume (m3)
DHW	15	22.8
Standby	37	27.1
Space Heating	43	47.8

	VWART with keep warm active	
Period	VWART (°C)	% Time
No Heating	27	93%
Heating	41	7%
Overall	28	

Test Results									
		Power [W]	Primary flow [m³/hr]	VWART [°C]	Energy Used [kWh]	Annual Operation [Hours]	Volume [m³]	Events [Per Year]	Average duration [Seconds]
1kW Space Heating	1a	1211	0.037	41	108	89.0	3.33	-	-
2kW Space Heating	1b	2073	0.067	42	811	391.1	26.36	-	-
4kW Space Heating	1c	3946	0.126	43	565	143.2	18.09	-	-
DHW Low Flow Rate	2a	11017	0.006	14	705	66.2	11.12	-	-
DHW Medium Flow Rate	2a	18379	0.009	15	295	16.2	4.65	-	-
DHW High Flow Rate	2a	23919	0.008	15	444	18.6	6.92	-	-
DHW Post Low Flow Rate	2a	-	0.274	13	-	-	0.08	10000	30
DHW Post Medium Flow Rate	2a	-	0.361	15	-	-	0.00	660	70
DHW Post High Flow Rate	2a	-	0.351	15	-	-	0.00	300	145
DHW Keep Warm Standby	4a	-	0.003	37	-	8035.8	27.11	-	-

Table 7.1 - Key Metrics of High Temperature Package



VWART Calculation with Keep Warm

Test carried out by Enertek International for Low Temperature BESA Tests

Manufacturer: Intatec Ltd

Model: HIPER2TPSZ80

Serial number: INE211410015AR

Calculation performed by S.Broxham of Enertek on: 05/05/2021

Primary Flow Temperature: 60°C

DHW Setpoint: 50°C

Space Heating Temperature: 45/35°C

	VWART (°C)	Volume (m3)
DHW	16	30.5
Standby	37	24.8
Space Heating	35	51.0

VWART with keep warm active		
Period	VWART (°C)	% Time
No Heating	26	93%
Heating	35	7%
Overall	26	

Test Results									
		Power [W]	Primary flow [m³/hr]	VWART [°C]	Energy Used [kWh]	Annual Operation [Hours]	Volume [m³]	Events [Per Year]	Average duration [Seconds]
1kW Space Heating	1d	1071	0.038	35	104	97.5	3.66	-	-
2kW Space Heating	1e	2074	0.070	35	808	389.6	27.38	-	-
4kW Space Heating	1f	3984	0.140	36	569	142.8	19.94	-	-
DHW Low Flow Rate	2b	450	0.006	15	485	1620.7	9.59	-	-
DHW Medium Flow Rate	2b	613	0.007	16	170	484.6	3.31	-	-
DHW High Flow Rate	2b	708	0.013	18	391	627.3	8.04	-	-
DHW Post Low Flow Rate	2b	-	0.296	15	-	-	6.84	10000	30
DHW Post Medium Flow Rate	2b	-	0.383	16	-	-	1.37	660	70
DHW Post High Flow Rate	2b	-	0.400	17	-	-	1.37	300	145
DHW Keep Warm Standby	4b	-	0.005	37	-	5397.4	24.82	-	-

Table 7.2 - Key Metrics of Low Temperature Package

7 APPENDIX B

7.1 Appliance Documentation

7.1.1 The details of the appliance documentation are given in Table 8.1 below.

Table 8.1 – Documentation Supplied.

	Component:	Document Submitted (Y/N):	Manufacturer and Type:
1	Space Heating Heat Exchanger	Y	Zilmet 17B315 18 Plates
2	Domestic Hot Water Heat Exchanger	Y	SWEP
3	Controller for Space Heating	Y	Selco Inta
4	Control Valve and Actuator for Space Heating	Y	Frese Optima OEM Cartridge
5	Space Heating Strainer	N	N/A
6	Controller for Domestic Hot Water	Y	Selco Inta
7	Control Valve and Actuator for Domestic Hot Water	Y	Frese Fast Acting Actuator
8	Temperature Sensors	Y	Nordgas
9	Domestic Hot Water Isolating Valve	Y	Rbn and Wras 1304026 150142
10	Primary Side Strainer	Y	Installation Manual, PICV Inlet Block assembly
11	Drain Valves	Y	Rbm
12	Vent Valves	Y	Rbm
13	Circulation Pump set with AAV & PRV	Y	Grundfos UPM3
14	Heat Meter	Y	Zenner Zelsius C5-IUF
15	Domestic Hot Water Flow Sensor	Y	Nordgas
16	Pipes	N	Copper
17	Connections	Y	Flat face with Gasket
18	Joints	N	N/A
19	Gaskets	Y	Fasit Omnia
20	Expansion Vessel	Y	Zilmet
21	Insulation	N	N/A
22	Pressure Sensors	Y	Ma-Ter
A2	Commissioning Guide.	Y	Manufacturers operating manual
A3	Operation guides with a function description / description of operation and care instructions as suited to the intended user category.	Y	Manufacturers operating manual
A4	Declaration of Conformity for CE-Marked HIUs.	N	
A5	Full Parameter List for Electrically Controlled HIUs.	Y	Manufacturers operating manual
A6	Maximum Primary Static Operating Differential Pressure.	16 bar	
A7	Deactivation Procedure of the Internal SH Pump.	N/A	
	Model Name and Type Number	HIPER2TP1580ZE	
	Serial Number	INE211410015AR	

7.2 Appliance Components

7.2.1 Details of the main appliance components are given in Table 8.2.

Table 8.2 – Appliance Components Details

HIPER2TP1580ZE	
Appliance Serial Number	INE211410015AR
Space Heating Heat Exchanger	Zilmet 17B315 PHE 18Plates
Domestic Hot Water Heat Exchanger	SWEP
Controller for Space Heating	Selco Inta
Control Valve & Actuator for Space Heating	Frese Optima OEM Cartridge
Controller for Domestic Hot Water	Selco Inta
Temperature Sensors	Nordgas
Domestic Hot Water Isolating Valve	Rbn and Wras 1304026 150142
Primary Side Strainer	Installation Manual, PICV Inlet Block assembly
Circulation Pump	Grundfos UPM3
Heat Meter	Zenner Zelsius C5-IUF
Domestic Hot Water Flow Sensor	Nordgas
Pipes	Copper
Connections	Flat face with Gasket
Gaskets	Fasit Omnia
Expansion Vessel	Zilmet
Pressure Sensors	Ma-Ter
Insulation	N/A
Software / Firmware	RBM / R3 (Revision 3 Firmware) Date of issue: 29/06/2021

7.3 Appliance Photographs



Figure 8.1 – Photograph of Appliance [Case Fitted]

inta

Airfield Industrial Estate
Hixon
Stafford
ST18 0PF
www.intatec.co.uk

HIPERII

Hiper II Twin Plate HIU
80 kW DHW, 3 – 30 HTG

Technical Support

Ph: 01889272199


Technical@intatec.co.uk


Max Working (Rated) Pressure for:		
Primary System (District Heating):	16	bar g
Secondary Heating System:	3	bar g
Domestic Hot Water System:	10	bar g


Max Working Temperature:	90	°C
--------------------------	----	----

Max Primary Flow Rate:	1300	l/h
Min Domestic Hot Water Flow Rate:	1.2	l/h
Max Output with Max Primary Flow Rate at 85 °C:	80	kW

Electrical Data for:		
Max Rated Input:	52	W
Voltage Supply:	230	V~
Frequency:	50/60	Hz
Electronics Casing:	IP42	

 **WRAS**
APPROVED PRODUCT

The image contains three logos: the 'kiwa approved' logo with a bird icon, the 'CE' mark, and the 'UK WATER REGULATION 4' logo with a crossed-out trash can icon.

 Scan QR Code
for Hiper II HIU
Manuals.

MADE IN EUROPE

INE211410015AR


A standard 1D barcode representing the product code INE211410015AR.

Figure 8.2 –Appliance Data Label



Figure 8.3 – Photograph of Appliance (Case Removed)

7.4 Calibrations and uncertainties

7.4.1 A list of equipment, their calibrations and uncertainties are given in Table 8.3 below.

Table 8.3 - EIL Equipment Calibration and Uncertainties

Equipment Name	ID Number	Calibration Certificate	Measurement Uncertainty $K=2 \frac{U}{\sqrt{20}}$	Units	Calibration Date	Calibration Due
Flow Meter [Primary Flow Rate]	FM 601	U99513-19	±0.0004	l/s	26-06-2019	26/06/2021
Flow Meter [DHW Flow Rate]	FM 602	U98515-19	±0.00305	l/s	26-06-2019	26/06/2021
Flow Meter [SH Flow Rate]	FM 603	U98530-19	±0.04871	l/s	27-06-2019	27/06/2021
Flow Meter [DHW Flow Rate]	FM 605	U98539-19	±0.00576	l/s	28-06-2019	28-06-2021
Pressure Transducer [Primary Supply]	PT 086	U98458-19	±6.82	kPa	22-06-2019	22/06/2021
Pressure Transducer [Primary Return]	PT 085	U98460-19	±7.88	kPa	22-06-2019	22/06/2021
Pressure Transducer [DHW Output Pressure]	PT 083	U98469-19	±7.73	kPa	23-06-2019	23/06/2021
Pressure Transducer [DHW Cold Water Supply]	PT 084	U98468-19	±7.31	kPa	23-06-2019	23/06/2021
Pressure Transducer [SH Flow]	PT 087	U98463-19	±7.26	kPa	22-06-2019	22/06/2021
Pressure Transducer [SH Return]	PT 088	U98461-19	±7.30	kPa	22-06-2019	22/06/2021
PRT Probe [Primary Supply Temp]	PRT 4709	EIL 436771	±0.4	°C	31/07/2019	31/07/2021
PRT Probe [Primary Return Temp]	PRT 4708	EIL 436771	±0.6	°C	31/07/2019	31/07/2021
PRT Probe [DHW Output Temp]	PRT 4711	EIL 436772	±0.4	°C	31/07/2019	31/07/2021
PRT Probe [Cold Water Supply Temp]	PRT 4710	EIL 436771	±1.9	°C	31/07/2019	31/07/2021
PRT Probe [SH Supply Temp]	PRT 4707	EIL 436771	±0.4	°C	31/07/2019	31/07/2021
PRT Probe [SH Return Temp]	PRT 4706	EIL 436771	±1.0	°C	31/07/2019	31/07/2021
Pressure Transducer [Static Pressure Test]	PT 090	U100553-19	±50	kPa	21/11/2019	20/11/2021
Power Meter [Electrical Consumption]	PM1022	U103585-20	±1.03	W	27/07/2020	27/07/2021
Software	VERSION – LabVIEW, Version 5, Service pack 1					

Report Issue No	Reason for Report Update
1	Original Issue
2	Data from E4412 for DHW tests added into report.
3	Software / Firmware numbers added to table 8.2
4	BESA summary sheet added to report.



1 Malmo Road
Sutton Fields
Kingston upon Hull, HU7 0YF

+44 (0) 1482 877500
enertekinternational.com
Registered in England No. 2262638

